Appendix A BASIC ZONING ORDINANCE

DRAFT ORDINANCE 8/24/16

The version of the underlying code has been updated through enrolled Ordinance 171-1, effective 6-10-16.

Page #'s will be updated upon completion of final ordinance. Table of contents may be enlarged to include the titles of subsections.

Sec. 1	Interpretation and Purposes	Page 2
Sec. 2	Definitions	Page 3
Sec. 3	General Provisions	Page 19
Sec. 4	Districts	
Sec. 5	C-1 Conservancy District	
Sec. 5a	C-1 Conservancy Overlay Disetrict.	Page 77
Sec. 6	FLC Farmland Conservancy District	Page 78
Sec. 6.1	FLP Farmland Preservation District.	
Sec. 6.2	A-B Agricultural Business District	Page 90
Sec. 6.3	A O Existing Agricultural Overlay District(Reserved)	Page 92
Sec. 6.4	A-T Agricultural Transition District	Page 92
Sec. 6.5	AD-10 Agricultural Density-10	Page 94
Sec. 6.6	A-5 Mini-Farm District	Page 99
Sec. 6.7	EC Environmental Corridor District	Page 101
Sec. 6.8	EC Environmental Corridor Overlay District.	Page 105
Sec. 7	A-1 Agricultural District	Page 105
Sec. 7a	A-la Agricultural District	Page 107
Sec. 7b	HG High Groundwater District	Page 108
Sec. 8	A-2 Rural Home District	Page 110
Sec. 8a	A-3 Suburban Estate District	Page 111
Sec. 8b	RRD-5 Rural Residential Density District 5	Page 112
Sec. 9	R-1 Residential District	Page 117
Sec. 9a	R-1a Residential District	Page 119
Sec. 10	R-2 Residential District	Page 120
Sec. 11	R-3 Residential District	Page 121
Sec. 12	P-I Public and Institutional District	
Sec. 13	B-1Restricted Business District	
Sec. 14	B-2 Local Business District	Page 126
Sec. 15	B-3 General Business District	Page 128
Sec. 15.1	B-4 Community Business District	Page 129
Sec. 15.2	BP Mixed Use Business Park District	Page 132
Sec. 16	Q-1 Quarrying District	Page 137
Sec. 17	M-1 Limited Industrial District	Page 138
Sec. 18	M-2 General Industrial District	Page 139
Sec. 19	Board of Adjustment	Page 141
Sec. 20	Changes and Amendments	Page 143
Sec. 21	Public Hearings	Page 147
Sec. 22	General Administration	Page 148
Sec. 23	Validity	Page 151

Commented [BA1]: A-O District no longer exists within the County's jurisdiction.

Editor's Note: Updated for changes made through Enrolled Ordinance 171-xx, effective 05-xx-2016.

SECTION 1 INTERPRETATION AND PURPOSES

1.01 Purpose.

The provisions of this Ordinance shall be held to be minimum requirements adopted to promote the health, safety, morals, comfort, prosperity and general welfare of the County of Waukesha. Among other purposes, such provisions are intended to provide for adequate light, air, sanitation, drainage, convenience of access, conservation of wetlands, and safety from fire and other dangers; to promote the safety and efficiency of the public streets and highways; to aid in conserving and stabilizing the economic values of the community; to preserve and promote the general attractiveness and character of the community environment; to guide the proper distribution and location of population and of the various land uses; and otherwise provide for the healthy and prosperous growth of the community.

1.02 General interpretation.

It is not intended by this Ordinance to repeal, abrogate, annul, impair or interfere with any existing easement, covenants or agreements between parties or with any rules, regulations, or permits previously adopted or issued pursuant to laws; provided, however, that where this Ordinance imposes a greater restriction upon the use of buildings or premises, or upon the height of a building or requires larger open spaces than are required by other rules, regulations or permits or by easements, covenants or agreements, the provisions of this Ordinance shall govern.

SECTION 2. DEFINITIONS

2.01 General interpretation.

For the purpose of this Ordinance, and when not inconsistent with the context, words used herein in the present tense include the future, words in the singular number include the plural, and words in the plural number include the singular; the word "structure" includes buildings; the word "occupied" includes designed or intended to be occupied; the word "used" includes designed or intended to be used; the word "inhabit" includes intended to be inhabited; the word "shall" is always mandatory and not merely permissive; "county" refers to the County of Waukesha, Wisconsin; "town board" refers to the town board of supervisors of any town under the jurisdiction of this Ordinance; "plan commission" refers to local town plan commission established under village powers pursuant to Chapter 62 Wisconsin Statutes, the Town Park Commission established pursuant to Chapter 60 Wisconsin Statutes, or any other agency created by the town board and authorized by statute to plan land use; and reference to any officer such as "clerk," "building inspector," "engineer," or "attorney," means that officer appointed or otherwise officially designated by the town or county in such capacity, unless otherwise specifically designated; the words "code" and "Ordinance" are to be used interchangeably; the word "person" may be taken for persons, associations, partnerships or corporations.

(Section 2.02 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

2.02 Specific words and phrases.

For the purposes of this Ordinance certain words and phrases shall be defined as follows:

- (1) <u>Administrative Officer</u>: Any officer such as a Clerk, Building Inspector, Engineer, Attorney, or Zoning Administrator, or his agent, who is appointed, elected, or is otherwise officially designated by the Town, and/or County and does not include any Committee, Commission, or Board or its individual members.
- (2) Adult Arcade means any place to which the public is permitted or invited wherein coin, slug, electronically, or mechanically controlled or operated still or motion picture machines, projectors, computers, or other image producing devices are maintained to show images to five or fewer persons per machine at any one time, and where the images so displayed are distinguished or characterized by depicting or describing "Specified Sexual Activities" or "Specified Anatomical Areas".
- (3) Adult Bathhouse means a commercial establishment which provides a bath as a service and which provides to its patrons an opportunity for engaging in "Special Sexual Activities."
- (4) Adult Body Painting Studio means a commercial establishment wherein patrons are afforded an opportunity to be painted or to paint images on "Specified Anatomical Areas". An Adult Body Painting Studio does not include a tattoo parlor.
- (5) <u>Adult Bookstore</u> means any commercial establishment having as its stock in trade the sale, rental or lease for any form of consideration, any one or more of the following:
 - (A) Books, magazines, periodicals or other printed matter, photographs, films, motion pictures, video cassettes, video reproductions, slides, or other visual representations which are distinguished or characterized by their emphasis on "Specified Sexual Activities" or "Specified Anatomical Areas";
 - (B) Instruments, devices, or paraphernalia which are designed for use in connection with "Specified Sexual Activities";
 - (C) Facilities for the presentation of "Adult Entertainment" as defined herein, including Adult-Oriented films, motion pictures, video cassettes, video reproductions, slides or other visual representations for observation by patrons therein.
- (6) Adult Cabaret means a nightclub, bar, restaurant, or similar commercial establishment which features:
 - (A) Live performances which are characterized or distinguished by the exposure of "Specified Anatomical Areas" or the removal of articles of clothing; or,
 - (B) Films, motion pictures, video cassettes, video reproductions, slides or other visual representations which are distinguished or characterized by depicting or describing "Specified Sexual Activities" or "Specified Anatomical Areas."
- (7) Adult Entertainment means any exhibition of any motion picture, live performance, display

or dance of any type, which has as its dominant theme, or is distinguished or characterized by any one or more of the following:

- (A) "Specified Sexual Activities";
- (B) "Specified Anatomical Areas";
- (C) removal of articles of clothing;
- (8) Adult Massage Parlor means a commercial establishment with or without sleeping accommodations which provides the service of massage or body manipulation, including exercise, heat and light treatment of the body, and any form or method of physiotherapy, which also provides its patrons with the opportunity to engage in "Specified Sexual Activities."
- (9) Adult Motel means a hotel, motel or other similar commercial establishment which:
 - (A) offers accommodations to the public for any form of consideration; provides patrons with closed circuit television transmissions, film, motion pictures, video cassettes, video reproductions, slides, or other visual reproductions characterized by depicting or describing "Specified Sexual Activities" or "Specified Anatomical Areas"; and, has a sign visible from the public right of way which advertises the availability of this type of <u>Aadult Eentertainment</u>; or
 - (B) offers a sleeping room for rent for a period of time that is less than 10 hours; or
 - (C) allows a tenant or occupant of a sleeping room to sublet the room for a period of time that is less than 10 hours.
- (10) Adult-Oriented Establishment includes: Adult Arcade, Adult Bathhouse, Adult Body Painting Studio, Adult Bookstore, Adult Cabaret, Adult Massage Parlor, Adult Motel, Adult Theater, and any commercial establishment presenting Adult Entertainment, whether or not such establishment is operated or maintained for a profit.
- (11) <u>Adult Theater</u> means an enclosed building such as theater, concert hall, auditorium or other similar commercial establishment which is used for presenting "Adult Entertainment."
- (12) Agricultural Accessory Use: Any of the following land uses on a farm:
 - (A) A building, structure, or improvement that is an integral part of, or is incidental to, an agricultural use.
 - (B) An activity or business operation that is an integral part of, or incidental to, an agricultural use.
 - (C) A Ffarm Rresidence that existed on May 31, 2015.
 - (D) A business, activity, or enterprise, whether or not associated with an agricultural use, that is conducted by the owner or operator of a farm, that requires no buildings, structures, or improvements other than those described in paragraph (A) or (C), that employs no more than 4 full-time employees annually and that does not impair or

limit the current or future agricultural use of the farm or of other protected farmland.

(E) Any other use that the Department of Agriculture, Trade and Consumer Protection ("DATCP"), by rule, identifies as an agricultural use and that is determined by the plan commission and zoning administrator to be compatible with the purpose and intent of the Farmland Preservation Zoning District.

(The definition of Agricultural Accessory Use was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (13) Agricultural or Farm Use: Any of the following uses:
 - (A) Any of the following activities:
 - 1. Crop or forage production.
 - 2. Keeping livestock, horses and poultry.
 - Beekeeping.
 - 4. Nursery, sod, or Christmas tree production.
 - 5. Floriculture.
 - 6. Aquaculture.
 - 7. Fur farming.
 - Forest management.
 - Enrolling land in a federal agricultural commodity payment program or a federal or state agricultural land conservation payment program.
 - (B) Any other use that DATCP, by rule, identifies as an agricultural use and that is determined by the plan commission and zoning administrator to be compatible with the purpose and intent of the Farmland Preservation Zoning District.

(The definition of Agricultural or Farm Use was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (14) Agriculture-Related Use: Any of the following uses:
 - (A) An agricultural equipment dealership, facility providing agricultural supplies, facility for storing or processing agricultural products, or facility for processing agricultural wastes.
 - (B) Any other use that DATCP, by rule, identifies as an agriculture-related use and that is determined by the plan commission and zoning administrator to be compatible with the purpose and intent of the Farmland Preservation Zoning District.

(The definition of Agriculture-Related Use was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (15) Apartment: A suite of rooms or a room in a multiple dwelling which a suite or room is arranged, intended, or designed to be occupied as a <u>R</u>residence of a single family, individual or group of individuals.
- (16) <u>Apartment houseHouse</u>: See "dwelling, multiple."
- (17) Applicant: The applicant for any permit, variance, special exception, conditional use, site plan, plan of operation, rezoning, license or other application for governmental approval under this ordinance Ordinance shall be a utility company that holds an appropriate easement or has established prescriptive rights under s. 893.28(2), Wisconsin Statutes or the landowner, specifically a person or entity holding fee title to the property, as set forth

Commented [BA2]: Modified definition to allow utility companies the ability to sign permit applications.

below:-

- (A) In the case of a corporation, an officer or by a member of the corporation who has overall responsibility for the operation of the site for which the permit is sought.
- (B) In the case of a limited liability company, a member or manager.
- (C) In the case of a partnership, a general partner.
- (D) In the case of a sole proprietorship, the proprietor.
- (E) For a unit of government, by an elected official or other duly authorized representative.
- (F) In the case of an individual, by the individual, an attorney, or one allowed authorized to act as agent under a power of attorney.

The applicant must sign the application or execute the Landowner's Authorized Agent Form, which is available through the Waukesha County Department of Parks and Land Use.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

- (18) <u>Arcade</u>: Any premises containing three (3) or more amusement devices or games usually of an electronic nature, for the primary use of entertainment of the public or the patrons of the establishment.
- (19) <u>Base setback-Setback lineLine</u>: The ultimate street line as established by the building location provisions of this ordinance, and from which all required setbacks shall be computed.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

(20) <u>Basement:</u> A level of a building that is more than one-half below the finished grade on at least one side.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

- (21) <u>Bed and Breakfast Facility</u>: An owner occupied <u>R</u>residence often in a building with landmark or historically significant qualities where lodging for paying guests is offered and which offers breakfast to these guests as its only meal.
- (22) <u>Boarding houseHouse</u>: A house or building where regular meals are generally furnished or served to three (3) or more persons at a stipulated amount for definite periods of one (1) month or less.
- (23) Boathouse: A structure located close to the ordinary high water mark and designed and used for the storage of boats normally used in the daily activities of lakefront property and which has a large garage type door for primary access on the side of the building facing the water. Said boathouse may also be used for the storage of accessory marine and other items used by the occupants of the lot. A boathouse shall be placed on a foundation extending below the frost line or concrete slab and contain at least 200 square feet in area. Boathouses may contain limited plumbing facilities, not including showers and/or baths, for occasional use and convenience of the occupants of the lot but under no circumstances may the boathouse

Commented [BA3]: Zoning Code does not regulate areas adjacent to the shore where boathouses are proposed.

6

be used for human habitation, human habitation being defined as utilizing the building for occupancy for overnight living or longer periods of time and including the aggregate of normal living activities such as lounging, cooking, eating, sleeping, etc.

Breezeway: An above-ground, roofed area for passage for the purpose of connecting two structures or buildings, as between a house and a garage, with either open or enclosed sides, with or without a foundation, and which must be designed and constructed in keeping with the existing structures or buildings.

(24) <u>Building</u>: Any structure used, designed or intended for the protection, shelter or enclosure of persons, animals or property.

(25) <u>Building, accessoryAccessory</u>: A <u>B</u>building or portion of a <u>B</u>building subordinate to the principal building and used for a purpose customarily incident to the permitted use of the principal building.

Building Footprint: The area of all roofed structures on a lot, except for the area of a roof overhang that measures twenty-four inches (24") or less in depth

(26) <u>Building, height-Height of</u>: The vertical distance measured from the lowest exposed point of a structure to the highest point of any roof.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Amended by Enrolled Ordinance 160-03, effective 05-03-05.)

- (27) <u>Building, principalPrincipal</u>: The main <u>B</u>building on a lot, intended for primary use as permitted by the regulations of the district in which it is located. Any <u>B</u>building intended to be used for human habitation shall constitute the principal building, except as in Section 3.20.
- (28) <u>Contiguous</u>: When referred to in this ordinance in the context of farmland preservation provisions, contiguous lands or parcels shall mean adjacent to, sharing a common boundary and including lands that are separated by a road, stream or section line.

 $(The\ definition\ of\ Contiguous\ was\ created\ by\ Enrolled\ Ordinance\ 170-72,\ effective\ 12/31/15.)$

(29) <u>Contractor's Yard:</u> The exterior premises on which construction and maintenance materials (i.e. salt, sand, cement, decorative block, stone, etc.) or landscaping materials (i.e. sand, gravels, stone, timbers, wood chips, etc.) or construction or maintenance equipment (i.e. bulldozers, front-end loaders, back-hoes, trucks, trailers, etc.) are stored to be utilized for off-site construction, maintenance, or landscaping purposes. Where landscape materials are stored or sold for retail or wholesale markets and accessory to an otherwise permitted use by right, such uses shall not be considered a contractor's yard.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

- (30) <u>Dance Hall</u>: A facility including any room, place or space in which a public dance, public ball with live or amplified music (not including juke box) and live entertainment including shows, disc jockeys, comedy or dramatic acts, is conducted excluding any public or parochial school or church hall when used for public dances sponsored by the school or church authority or of a parent teachers' association.
- (31) <u>Deck</u>: A structure characterized by a flat open horizontal surface or platform suspended above the grade of the land it covers and which may be supported by posts, beams,

Commented [W4]: Added definition that is also in shoreland ordinance

Commented [W5]: Added definition to give meaning to a new area regulation that replaces floor area ratio and open space.

cantilever and/or by other similar methods.

(32) <u>Development Right</u>: When used in the context of the Farmland Preservation ("FLP") or Farmland Conservancy ("FLC") Districts, the term, Development Right, shall be synonymous with the number of dwelling units and new parcels of less than 35 acres that a farm tracking unit is entitled to create.

(The definition of Development Right was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (33) <u>District</u>: A Section of the County of Waukesha for which the regulations governing the height, area, and the use of building and premises are the same.
- (34) Dwelling, one family: A detached or semi-detached building designed for and occupied exclusively by one (1) family.
- (35) <u>Dwelling, Meaultiple family</u>: A <u>Behuilding</u> or portion thereof designed for and occupied by more than one (1) family, including duplexes, row houses, town houses and <u>Aepartments</u>.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

Dwelling, Single-family: A detached or semi-detached Building designed for and occupied exclusively by one (1) family.

Environmental Corridors: Environmental corridors (Primary, Secondary and Isolated Natural (36)Resource Areas) are concentrations of key significant natural resource elements including surface water such as lakes, streams, and rivers and their associated undeveloped floodlands and shorelands; woodlands, wetlands, and wildlife habitat; prairie remnants; areas of groundwater discharge and recharge; unfarmed wet, poorly drained and organic soils, rugged terrain and high relief topography; and significant geological formations and physiographic features. In general, Primary Environmental Corridors are concentrations of significant natural resources at least 400 acres in area, at least two miles in length, and at least 200 feet in width. Secondary Environmental Corridors are concentrations of significant natural resources at least 100 acres in area and at least one mile in length (possibly smaller and shorter if considered a primary link). Isolated Natural Resource Areas are concentrations of significant natural resources at least five acres in area and at least 200 feet in width. Generalized Environmental Corridor boundaries are mapped by the Southeastern Wisconsin Regional Planning Commission, typically at five-year intervals, and precise boundaries are field delineated by, or reviewed and approved by, the Southeastern Wisconsin Regional Planning Commission Staff. A description of the processes for further defining and delineating Primary and Secondary Environmental Corridors and Isolated Natural Resource Areas is set forth in the Southeastern Wisconsin Regional Planning Commission's Technical Record, Volume 4, No. 2, and is incorporated herein by reference.

(Amended by Enrolled Ordinance 169-46, effective 09/09/2014.)

(37) Environmentally Seignificant Aareas: Environmentally significant areas are lands which are zoned as C-1 Conservancy District, A-E Exclusive Agricultural Conservancy District, or EC Environmental Corridor District, or are designated as Primary Environmental Corridor, Secondary Environmental Corridor, or Isolated Natural Resource area on the Waukesha County Comprehensive Development Plan.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.) (Amended by Enrolled Ordinance 169-46, effective 09/09/2014.) **Commented [BA6]:** Replaced term with Dwelling, Single-family (see below).

- (38) <u>Family</u>: The body of persons who live together in one (1) dwelling unit as a single housekeeping entity.
- (39) <u>Farm</u>: All contiguous land under common ownership that is primarily devoted to Aegricultural Uese.

(The definition of Farm was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (40) Farm Acreage: The size of a farm in acres.
 - (The definition of Farm Acreage was created by Enrolled Ordinance 170-72, effective 12/31/15.)
- (41) <u>Farm Consolidation</u>: A division of land that includes a farm house or houses and may include existing associated agricultural buildings that splits a limited amount of land from a larger pre-existing <u>E</u>farm.
 - (The definition of Farm Consolidation was created by Enrolled Ordinance 170-72, effective 12/31/15.)
- (42) <u>Farm, Ffur:</u> A tract of land devoted in whole or part to the raising of fur bearing animals for commercial purposes.
- (43) <u>Farm, Ppig:</u> A tract of land devoted principally to the raising and feeding of pigs and hogs.
- (44) Farm, Ppoultry and/or Eegg Pproduction: A tract of land, which may or may not be part of a larger farm operation, devoted principally to the raising of poultry and/or egg production.
- (45) <u>Farm Residence:</u> Any of the following structures that is located on a <u>F</u>farm:
 - (A) A single-family or duplex residence that is the only residential structure on the Ffarm or is occupied by any of the following:
 - 1. An owner or operator of the F‡arm.
 - 2. A parent or child of an owner or operator of the Ffarm.
 - An individual who earns more than 50 percent of his or her gross income from the Ffarm.
 - 4. A migrant labor camp that is certified under s. 103.92.

 $(The\ definition\ of\ Farm\ Residence\ was\ created\ by\ Enrolled\ Ordinance\ 170-72,\ effective\ 12/31/15.)$

(46) Farm Tracking Unit: One or more contiguous parcels that were part of a single Farm or in the same ownership on May 31, 2015 that are designated on the Comprehensive Development Plan for Waukesha County as a Farmland Preservation Area.

(The definition of Farm Tracking Unit was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (47) <u>Farmland Preservation Area</u>: An area that is planned primarily for Aegricultural <u>U</u>use or Aegriculture-<u>R</u>related <u>U</u>use, or both, and that is one of the following:
 - (A) Identified as an agricultural preservation area in a farmland preservation plan described in s. 91.12(1), Wis. Stats.

(B) Identified under s. 91.10(1)(d), Wis. Stats. in a farmland preservation plan described in s. 91.12(2), Wis. Stats.

(The definition of Farmland Preservation Area was created by Enrolled Ordinance 170-72, effective 12/31/15.)

(48) <u>Farmland Preservation Plan</u>: A plan for the preservation of farmland in a county, including an agricultural preservation plan under subch. IV of ch. 91, 2007 stats.

(The definition of Farmland Preservation Plan was created by Enrolled Ordinance 170-72, effective 12/31/15.)

(49) Floor area ratio: The term "Floor Area Ratio" or F.A.R. shall be used to indicate the total floor area of buildings allowed on a given lot, expressed as a percentage ratio to the total area of the lot; i.e., an F.A.R. of one hundred (100) percent allows a floor area equal to the total area of the lot, an F.A.R. of fifty (50) percent allows a floor area of one half the total area of the lot, etc. A floor area ratio of fifty (50) percent could be applied to a one story building occupying fifty (50) percent of the lot or a two story building occupying twenty five (25) percent of the lot.

Floor Area: The sum of the horizontal areas of each floor of an enclosed Bbuilding as measured to the outside edges of the outside walls. This definition does not include Bbasements, exterior balconies, unenclosed porches, or garages.

(50) Fur-bearing Aenimals: Animals which are specifically raised for their pelts, including, but not limited to badger, beaver, bobcat, coyote, fisher, fox, lynx, marten, mink, muskrat, opossum, otter, raccoon, skunk, weasel and wolf.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

- (51) <u>Garage, Pprivate</u>: A private garage is one where private vehicles are kept for storage purposes only and wherein such use is accessory to the residential use of the property on which it is stored.
- (52) <u>Garage, Ppublic or Ceommercial</u>: Any <u>B</u>-building or premises, other than a private or a storage garage where motor-driven vehicles are equipped, repaired, serviced, hired, sold or stored for monetary gain as a business.
- (53) <u>Grade, Eestablished</u>: The elevation of the finished street at the centerline or curb as fixed by the Engineer or by such authority as shall be designated by law to determine such an elevation.
- (54) <u>Green Space</u>: A natural or man-made land area not occupied by any structure or impervious

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

- (55) <u>Guesthouse</u>: A structure used principally for occasional occupancy by guests of the owners, and shall not be leased or rented for human occupancy.
- (56) <u>Highway</u>: A right-of-way, designated by the Waukesha County Established Street and Highway Width Map or any other comprehensive system, for the principal purpose of providing vehicular thoroughfare and not necessarily affording direct access to abutting property.

Commented [BA7]: Replaced floor area ratio with new footprint and revised height scheme.

Commented [BA8]: Added definition that exists in shoreland ordinance.

(57) Home Occupation: Any occupation for monetary gain or financial support conducted entirely within the principal residence.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

- (58) <u>Horticulture</u>: The culture of growing and cultivating fruits, flowers and related plant material.
- (59) Hotel: See Motel.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

- (60) Housekeeping Entity: A housing or lodging unit where all of the amenities of bathing and sanitary facilities, eating, cooking, living, sleeping and storage are provided the person or body of persons occupying and living together as a single entity within the unit. A single-family residence or a dwelling unit in a multiple family structure are deemed to be a single housekeeping entity.
- (61) <u>Human Habitation</u>: The use of a <u>Bbuilding</u> or structure for overnight living or longer periods of time, and including the aggregate of normal occupancy activities such as lounging, cooking, eating, sleeping, bathing, sanitation, etc.
- (62) Impervious Surface: An area that releases as runoff all or a majority of the precipitation that falls on it. Impervious Surface includes, but is not limited to, rooftops, sidewalks, driveways, parking lots, Decks, patios, sport courts, swimming pools, retaining walls and hot tubs. Land area and surfaces where precipitation is unable to infiltrate into the soil. Such surfaces include, but are not limited to roadways and pathways that are paved with concrete or asphalt, roofs, patios and similar surfaces.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

- (63) <u>In-law Unit</u>: A room or suite of rooms used or occupied as a separate <u>H</u>housekeeping <u>E</u>entity and located in a single-family dwelling occupied by persons related by blood or marriage to the family or persons occupying the single-family dwelling.
- (64) Junk: Junk means garbage, waste, refuse, trash, any motor vehicle upon which no current license plate is displayed, any inoperable or abandoned motor vehicle, any used tire or used motor vehicle part, and any scrap material such as metal, lumber, furniture, paper, cans or bottles. Any trailer which is required to be licensed by the State of Wisconsin, but which is unlicensed, or any trailer which is abandoned or inoperable is considered junk under this ordinance.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

- (65) Kennel, Ceommercial: An establishment, structure or premises where dogs are raised and sold, bred, boarded, trained or groomed for commercial purposes. The raising and selling of three (3) or more litters of dogs from any number of adult dogs per year shall constitute a commercial kennel.
- (66) Kennel, Hhobby: A private, non-commercial establishment, structure, premises or pursuit accessory to the Perincipal Uses of the property where three (3) or more dogs of six (6) or more months of age are kept for such private purposes as pets, field trials, shows or hobby. The occasional raising of not more than two (2) litters of dogs per year on a premises and the

Commented [BA9]: Generally matched language in shoreland ordinance.

sale or disposal of said dogs within six (6) months of their birth shall also be considered a private hobby kennel.

(The definition of Kennel, hobby was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

(67) <u>Land-Aæltering Aæctivity</u>: Any man-made change of the land surface, including removing vegetative cover which changes the land surface, cutting of trees which changes the land surface, excavating, soil removal, filling, grading, dredging and channel improvements in excess of those limits set forth in Section 3.04(5), but not including agricultural land uses such as planting, growing, cultivating and harvesting of crops, growing and tending of gardens and harvesting of trees, and tree nurseries.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(68) <u>Livestock</u>: Animals which are typically kept for breeding, production of agricultural products, sale or pleasure, including, but not limited to cattle, bovine, emus, llamas, alpaca, pigs, swine, hogs, sows, horses and other equine animals, sheep, goats, farm raised deer, camelids, ratites, farm-raised fish, farm-raised game birds and bison. For purposes of the FLC and FLP Districts, Livestock is defined as bovine animals, equine animals, goats, poultry, sheep, swine, farm-raised deer, farm-raised game birds, camelids, ratites, and farm-raised fish.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Amended by Enrolled Ordinance 170-75, effective 12-31-15.)

- (69) <u>Lodging Hhouse</u>: A <u>Bhuilding</u> where lodging only is provided for compensation and having not more than five (5) sleeping rooms for this purpose.
- (70) Lot: A parcel of contiguous land with described boundaries and abutting or having access via an approved easement to a public street or other approved way, and exclusive of any land lying in public rights-of-way, mill tax roads, or below the ordinary high water mark of navigable waters, public streams or other public water body. Where such streams or public rights-of-way divide a single described parcel into two (2) or more parts, such severed portions shall be considered separate individual lots_Lots if such separate parcels individually meet the use regulations, building location and area regulations of the zoning district in which they are located. Where such separate parcels do not meet those requirements and have been described as a single parcel of record, together such severed portions shall be considered to be a single lot_Lot for regulatory purposes under the provisions of this Ordinance, and such severed areas shall not be sold separately. constitute a single lot for computation of area regulations and other locational provisions of this OrdinanceSee Section 3.11 to determine how area regulations are applied to a Lot.
- (71) Lot Area: The area of a Lłot as defined herein bounded by lot lines exclusive of land provided for public rights-of-way, mill tax roads, and lands below the ordinary high water mark of navigable waters. public streams or other public bodies of water.
- (72) Lot depthDepth: The mean horizontal distance measured between the street line and the opposing rear line or lines of the lot.
- (73) Lot, legal Legal nonconforming Nonconforming. Any lawfully created lot Lot or parcel which existed at the time of passage of this Ordinance or any amendment thereto, which does not meet the current dimensional requirements of the Delistrict in which it is located.

Commented [BA10]: Modified language to incorporate the findings of a supreme court case that concluded that a stream does not sever a single parcel. Added language to direct reader to lot regulations of this ordinance.

Commented [BA11]: Clarification regarding where lot area is measured with regards to the bed of a waterway.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

- (74) <u>Lot linesLines</u>: The lines bounding a <u>L</u>lot as defined herein.
- (75) Lot <u>lineLine</u>, <u>sideSide</u>: A <u>Liot Line</u> extending from a street line towards the interior of the block and separating adjoining <u>lotsLots</u>.
- (76) Lot of Record: A platted Lator or Lator described in a Certified Survey Map, which has been approved by the Town and has been recorded in the office of the Waukesha County Register of Deeds, or a metes and bounds description of a Lator which has been recorded in the Waukesha County Register of Deeds Office prior to the adoption of this original Ordinance

(February 26, 1959). (Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(77) Lot widthWidth, minimum Minimum average Average: The mean horizontal distance measured between side lot lines, perpendicular to the lot depth and at a point in relation to the depth where the product of the two (2) would produce the minimum required lot area. The average horizontal distance measured between Sside Lot Lines at the established Bbase Ssetback Line and the rear lot line. The Zoning Administrator shall determine where to measure lot width on an irregular shaped lot. A newly created Liot shall be at least as wide as the specified minimum average width for a distance of at least one-half the length of the Liot.

Maintenance: The act or process of restoring to original soundness, including redecorating, refinishing (such as painting, decorating, or paneling), non-structural repairs, or the replacement of existing fixtures, systems or equipment with equivalent fixtures, systems or equipment.

- (78) Mobile homeHome: A structure Structure or vehicle which is used, titled and registered as living quarters, and contains sleeping accommodations, a flush toilet, a tub or shower bath, kitchen facilities, and plumbing and electrical connections for attachment to outside systems; and is designed for transportation after fabrication on streets or highways on wheels and arrives at the site where it is to be occupied complete and ready for occupancy except for minor and incidental unpacking and assembly operations, locations on jacks or other temporary or permanent foundations, connections to utilities, and the like. A mobile home-Home is not considered a recreational vehicle as defined herein.
- (79) Mobile Home Park: Any plot or plots of ground upon which two (2) or more units occupied for dwelling dbwelling or sleeping purposes are located, regardless of whether or not a charge is made for such accommodations. Wisconsin Statutes, Section 66.0435.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

- (80) Modular Home: A principal structure which is partially pre-assembled at a manufacturing plant and placed together or erected on a Lłot or parcel as a dwelling Dwelling unit or units (also called a "pre-fabricated" or "pre-cut" homes or "double-wide" units) meeting the requirements of all applicable state and local building codes.
- (81) Motel (also Hotel): A B-building or series of B-buildings, with or without the availability of meals being served in a restaurant associated with the facility, in which short term lodging (not a H-bousekeeping E-entity) and normally not exceeding two (2) weeks in duration, is offered for the traveling public for compensation and which may have more than five (5) individual sleeping rooms, or grouping of rooms (or a suite) or units and toilet and bathing

Commented [BA12]: Modified definition to clarify where average width measurements are applied.

Commented [BA13]: Added definition to be consistent with shoreland ordinance and because the term is used several times within code.

facilities for the purpose of overnight sleeping and which is distinguished from a <u>H</u>hotel primarily by reason of providing direct independent access to each room and adjoining parking for each room or unit. Such facilities shall provide longer term housing (normally more than two (2) weeks) to person or groups of persons as a residence as such uses are considered <u>A</u>epartments with each unit serving as a single <u>H</u>housekeeping <u>E</u>entity.

(82) Motor vehicle Vehicle: Motor vehicle means a Any automobile, truck, trailer, tractor, bus, vehicle or other conveyance that is self-propelled by an internal combustion engine or motor, and for the purposes of this zoning ordinance Ordinance shall include but not be limited to boats, recreational vehicles, all-terrain vehicles, motorized farm equipment and mobile machinery, motorcycles and snow mobiles.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

- (83) Navigable waters Waters/Waterway: Lake Superior, Lake Michigan, all natural inland lakes within Wisconsin and all streams, ponds, sloughs, flowages and other waters within the territorial limits of this state, including the Wisconsin portion of boundary waters, which are navigable under the laws of this state. Under Section 281.31(2(d), Wis. State Statutes, notwithstanding any other provision of law or administrative rule promulgated thereunder, shoreland ordinances required under Section 59.692 Wis. Stats. (2013)State Statutes and Chapter NR 115, Wis. Adm. Code, do not apply to lands adjacent to:
 - A. Farm drainage ditches where such lands are not adjacent to a natural navigable stream or river and such lands were not navigable streams before ditching; and
 - B. Artificially constructed drainage ditches, ponds, or stormwater retaining basins that are not hydrologically connected to a natural navigable waterway.

Those intermittent and perennial rivers, streams, ponds, lakes and flowages shown on the U.S.G.S. Topographic Quadrangle 7.5 minutes series maps of Waukesha County (and as periodically updated) and those stream reaches shown on the large scale topographic mapping control survey project for Waukesha County conducted under Section 87.31 Wisconsin Statutes. Any water is considered navigable in fact if it meets the tests outlined in state laws. Determinations of navigability are ultimately field determinations and map delineations are merely the best representation of navigable conditions at any particular time.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(84) Nonfarm Residence: A single-family or multi-family residence other than a Farm Residence.

(The definition of Nonfarm Residence was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (85) Offset: The horizontal distance measured from the side or rear lot line, not along a street, to any roofed or enclosed portion of a Bbuilding, and not including a roof overhang, as defined herein, of twenty-four (24") inches or less.
- (86) Open Space: Land area used for recreation, agriculture, resource protection, amenities for recreational purposes or buffers.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(87) Open Space, Common: Lands which are Open Space and owned in common by individuals within a development or land trusts or other private conservation organizations,

Commented [BA14]: Modified to match language of shoreland ordinance and NR115.

if access is available to the public, and as may be agreed to in the approval of the development by the plan commission of the local community and either the zoning administrator or the zoning agency.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(88) Open Space, Public: Lands which are Open Space, dedicated and owned by a public entity, such as a town, city, village, county or other public entity, and used for a public purpose.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(89) Ordinary High Water Mark: The point on the bank or shore up to which the presence and action of surface water is so continuous as to leave a distinctive mark such as by erosion, destruction or prevention of terrestrial vegetation, predominance of aquatic vegetation, or other easily recognized characteristic. Where the bank or shore at any particular place is of such character that it is difficult or impossible to ascertain where the point of ordinary highwater mark is, recourse may be had to the opposite bank of a stream or to other places on the shore of a lake or flowage to determine whether a given stage of water is above or below the ordinary high_water mark.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(90) Outdoor/Indoor Recreational Facilities: Land and structures, along with accessory equipment, designed and utilized for leisure time activities of a predominantly "outdoor or indoor" nature and of having a more specific purpose such as tennis courts, swimming pools, basketball or racquetball courts, ice arenas, etc., other than passive park-like open areas, and further classified as follows:

<u>Public</u>: Facilities owned and operated by a governmental agency for limited

or general public use.

Private Commercial: Facilities owned and operated by an individual, group, or

corporation for profit as a business whether or not open to general

public use.

Private Non-Commercial Group:

Facilities owned and operated by a group for the exclusive use of the members of such group and their guests and not for profit as a

business.

- (91) Overhang: That portion of a roof over a structure and designated as an integral part of the structure, which extends from the outer wall of the structure to the eave. Rain gutters are not included or considered part of the overhang.
- (92) Parent Parcel: The term parent parcel, when used in the Farmland Preservation District or Farmland Conservancy District, shall mean a parcel, as it existed, on January 1, 1997.

(The definition of Parent Parcel was created by Enrolled Ordinance 170-72, effective 12/31/15.)

(93) Patio: A structure characterized by a flat, open, horizontal surface or platform and usually constructed of materials including, but not limited to, concrete, brick, flagstone, crushed stone, compacted stone, gravel, wood, or other natural or man-made materials. A patio is

Commented [BA15]: Modified language to match shoreland

located on the surface of the ground or at the average grade of the ground surface. This definition includes sport courts such as tennis courts, basketball courts, and similar structures that are not associated with normal driveway construction. A structure characterized by a flat, open, horizontal surface or platform usually constructed of concrete, brick, wood or other natural or man made materials which is located on the surface of the ground or at the average grade of the ground surface.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

(94) Permitted Use: A use that is allowed without a conditional use permit, special exception, or other special zoning permission but that may require a zoning permit or other approval as specified in this ordinance.

(The definition of Permitted Use was created by Enrolled Ordinance 170-72, effective 12/31/15.)

- (95) Planned Unit Development (PUD): A development strategy, process or procedure whereby a relatively large parcel of land is developed for a specific use in such a way as to provide specific benefits to the community as well as the developer and future citizens who will reside within the development, and when the normal application of standards and requirements are waived or made more flexible, and which shall contain substantial amounts of Ceommon Open Sepace for aesthetic, natural preservation or recreational purposes.
- (96) Planned Unit Development, Mixed: A Planned Unit Development which is a mixture of retail, service uses, industrial uses or residential uses. Buildings associated with Oepen Space and recreational uses, either public or private, shall be considered part of the open space use.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

- (97) <u>Planting screenScreen</u>: An area landscaped with natural growing plant material which effectively screens from vision the objects it is intended to hide from view.
- (98) Porch/steepStoop: A functional element of the ingress/egress of a principal structure allowing for easy and convenient passage between the exterior and interior of said structure. For the purposes of regulation in this Ordinance, a stoop is considered to be twenty (20) square feet or less whereas a porch exceeds twenty (20) square feet in area.
- (99) <u>Poultry</u>: Poultry means domesticated birds kept for eggs or meat or as pets.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

- (100) Private etubClub: A building Building or grounds used for regular or periodic meetings or gatherings of a group of persons organized for a non-profit purpose, but not groups organized to render a service customarily carried on as a business.
- (101) Professional efficeOffice: The office of a doctor, practitioner, dentist, minister, architect, landscape architect, professional engineer, lawyer, author, musician or other similar recognized professional.
- (102) Public and semiSemi-public Public buildingBuilding: Public and semiSemi-public Public buildings Buildings and uses in the sense of this Ordinance are Structures principally of an institutional nature and serving a public need such as: hospitals, rest homes, schools, including private academic schools and nursery schools, libraries, museums, public and private utilities, and other services; but not including the operation of a public bar, restaurant

Commented [BA16]: Modified language to match shoreland ordinance

or recreational facility as a commercial enterprise.

- (103) Pyramiding: The act of obtaining or providing access to public bodies of water across private lots or lands in a manner which increases the number of families which have access to that water to a degree greater than what would occur with individual riparian owners having individual lots fronting on the water. The effect of pyramiding is to funnel backlot development from offshore lots of residences via a narrow parcel of land to provide access to the water. Publicly owned access points shall not fall within this definition.
- (104) Quarrying: The removal of rock, slate, gravel, sand, topsoil or other natural materials from the quarrying site by excavating, stripping, leveling or any other such process, including the mining of non-metallic minerals.
- (105) Recreational Vehicle: Motorized vehicles that include a cabin for living accommodations and are commonly used for recreational travel and touring. Vehicles included in this category come in several forms: travel trailers, tent trailers and camping trailers, all of which must be towed by another vehicle; and truck campers, motor homes and camper vehicle, all of which have a motor within the body of the vehicle and are self-propelled.
- (106) Refuse disposal Disposal siteSite: A tract of land operated by a public or private agent, subject to restrictions of use and under supervision, and where more than one (1) Examily may take all types of refuse, including organic and inorganic wastes (but excluding human excreta, sewage, and/or other liquid wastes), for compacting and burial by sanitary land fill methods. Hard or clean fill operations involving materials such as foundry sand, dirt, gravel, concrete or other forms of clean fill material shall not be required to conform to the provisions of Section 3.08(7)(T).

Residence: See Dwelling(s)

(107) Restaurant: "Restaurant" means and includes any Bbuilding, room or place wherein meals or lunches are prepared, served or sold to transients or the general public, and all places used in connection therewith. Meals or lunches shall not include soft drinks, ice cream, milk, milk drinks, ices and confections. The serving in taverns of free lunches consisting of popcorn, cheese, crackers, pretzels, cold sausage, cured fish or bread and butter shall not constitute such taverns to be restaurants. The term Restaurant does not apply to churches, religious, fraternal, youth or patriotic organizations, which occasionally serve or sell meals or lunches to transients or the general public, nor shall it include any private individual selling foods from a movable or temporary stand at public farm sales. Section 254.61(5) Wisconsin Statutes

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

(108) <u>Retaining Wall:</u> A structure more than 18 inches in height from grade or a combination or series of multiple structures more than 24 inches in height from grade, constructed of manmade or natural materials for the purpose of retaining land or stone and resisting the lateral pressure of the land or stone.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(109) <u>Road</u>: A public or private right-of-way usually affording primary access to abutting property. **Commented [BA17]:** Modified language to match shoreland ordinance.

Road, Local: A public road that is not a county, state or federal Hhighway.

- (110) Roadside standStand: A farm building used or intended to be used solely by the owner or tenant of the farm_Farm on which such building_Building is located for the sale of the farm products raised on said farmFarm.
- (111) Sand or gravel-Gravel pitsPits: See quarrying.
- (112) <u>Setback, roadRoad</u>: The horizontal distance between the <u>base-Base setback Setback line</u>. <u>Line</u> and the closest point of a principal or accessory structure, excluding a roof <u>O</u>everhang measuring twenty-four inches (24") or less.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(113) Setback, shore: The horizontal distance between and the closest point of a structure or building and the ordinary high water mark of navigable waters, the one hundred year floodplain, or the conservancy/wetland district, whichever distance is greater.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

Setback, Wetland: The horizontal distance between the closest point of a structure or Building and the wetland boundary, excluding a roof Ooverhang measuring twenty-four inches (24") or less.

- (114) <u>Sign</u>: Any structure or device displaying advertising in the form of lettering, pictures, symbols or other media.
- (115) Special Exception: means a request for a minor adjustment to the requirements of the Zoningthis Ordinance only where specifically authorized by this Ordinance, owing to special conditions of the property. The special exception must be necessary and desirable and must not adversely affect adjacent property owners. A special exception differs from a variance in that a special exception does not necessarily require the demonstration of an unnecessary hardship or practical difficulty. In the granting of a special exception, the approving body must still consider whether the proposed special exception would be hazardous, harmful, noxious, offensive or a nuisance to the surrounding neighborhood by reason of physical, social or economic effects and may impose such restrictions or conditions they deem necessary for the protection of adjacent properties and the public interest and welfare.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

- (116) Specified Anatomical Areas means:
 - (A) Less than completely and opaquely covered human genitals, pubic region, buttock
 or female breasts below a point immediately above the top of the areola; or
 - (B) Human male genitals in a discernibly turgid state, even if opaquely covered.
- (117) Specified Sexual Activities: means and includes any of the following, simulated or actual:
 - (A) The fondling or other erotic touching of human genitals, pubic region, buttocks, anus, or female breasts;

Commented [BA18]: Added definition because the term is used in the road setback provisions of this ordinance.

Commented [BA19]: Shore setback regulation does not apply in general zoning code.

Commented [BA20]: Removed reference from shore setback and created a separate wetland setback because shore does not apply in general zoning code.

18

- (B) Acts of masturbation, sexual intercourse, sodomy, bestiality, necrophilia, sadomasochistic abuse, fellatio, cunnilingus, anilingus.
- (C) Showing of human genitals in a state of sexual stimulation or arousal.
- (D) Excretory functions during a live performance, display or dance of any type.
- (118) <u>Stable, boardingBoarding</u>: A tract of land or structure where horses or other <u>L</u>ivestock are kept for hire, boarding, sale or used for commercial recreational purposes.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

(119) <u>Stable, privatePrivate</u>: A tract of land or structure where horses or other <u>L</u>tivestock are kept for personal use by the property owner or occupant of the principal residential structure on the property.

(Created by Enrolled Ordinance 159-69, effective 1-17-05.)

- (120) Story: That portion of a Building included between the surface of a floor and the surface of the floor next above it; or if there is no floor above it, then the space between the floor and the ceiling or roof next above it, including Basements that are exposed at least six feet on at least one side. That portion of a Building included between the surface of a floor and the surface of the floor next above it; or if there be no floor above it, then the space between the floor and the ceiling next above it. A Basement or cellar having one half (1/2) or more of its height above grade shall be deemed a story for purposes of height regulation.
- (121) Street: Same as "Road."
- (122) Street, Arterial: Arterial Street means a road providing for efficient, safe and direct connection to or separation of developed areas for circulation to destinations outside the developed area and deemed as such on the "Established Street and Highway Width Map for Waukesha County" or other official map adopted by the municipality.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

(123) <u>Street, Collector</u>: Collector Street means a road providing for circulation to serve local traffic moving between minor streets and <u>Aerterial Setreets</u> as designated on the "Established Street and Highway Width Map for Waukesha County" or other official map adopted by the municipality.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

- (124) <u>Street, frontageFrontage</u>: A street contiguous and parallel to a traffic artery and affording direct vehicular access to abutting property.
- (125) Street lineLine: A dividing line between a lot, tract or parcel of land and a contiguous street.
- (126) Street, Minor: Minor Street means any other road not deemed as a collector or Aerterial Street on the "Established Street and Highway Width Map for Waukesha County" or other official map adopted by the municipality.

(Created by Enrolled Ordinance 161-13, effective 09/04/06.)

Commented [BA21]: Modified language to match shoreland ordinance.

- (127) <u>Structural alterations Alterations</u>: Any change in the supporting members of a <u>building</u> <u>Building</u> or any substantial change in the roof structure or in the exterior walls.
- (128)Structure: Any man-made object with form, shape and utility that is constructed or otherwise erected on the ground or attached to something on the ground, or permanently or temporarily placed, either upon the ground or upon another structure. For the purposes of this Ordinance, the term "structure" includes, but is not limited to, Principal and Accessory Buildings (including garages, sheds, Pporches and gazebos), signs, swimming pools, hot tubs, Patios, Decks, sidewalks, walkways, Rretaining Wwalls, monuments, entrance gates, radio towers and television towers, but does not include landscaping, earthwork, or Lland-Aeltering Aectivities including graded areas, filled areas, ditches, berms, or earthen terraces. The term "structure" does not include flag poles, mailboxes, fences, basketball hoops, satellite dishes eighteen (18) inches or less in diameter, or small objects that are easily moved by hand, such as lawn chairs, portable grills, portable picnic tables, fences, doghouses, bird feeders, birdhouses, and birdbaths. Anything constructed or creeted on the ground or attached to something on the ground. Structures include, but are not limited to buildings, swimming pools, hot tubs, radio and television towers, sheds, signs, patios, decks, gazebos, retaining walls, monuments and entrance gates.

(Amended by Enrolled Ordinance 159-69, effective 1-17-05.)

- (129) <u>Structure, legal-Legal nonNon-conforming</u>: A <u>buildingBuilding</u>, <u>structureStructure</u>, or portion thereof, lawfully existing at the time of the passage of this Ordinance, but which does not conform in one or more respects to the regulations of this Ordinance.
- (130) Sustained vield-Yield forestryForestry or Silviculture: The management of forested lands, including planting, thinning, and harvesting to provide annual or periodic crops of forest products.
- (131) Swimming poolPool: A structureStructure, designed to hold water more than thirty (30) inches deep for the purpose of swimming.
- (132) Temporary structure: A movable structure not designed for human Human habitation-Habitation or occupancy, but for the temporary protection of goods or chattels during a period of construction, but not to exceed one (1) year; for the enclosure or screening of goods or property; or for the display of Seigns and advertising.
- (133) Tourist homeHome: A building Building in which lodging, with or without meals, is offered to transient guests for compensation, and having no more than five (5) sleeping rooms for this purpose with no cooking facilities in any such individual room or △epartment.
- (134) Traffic arteryArtery: Same as "highway."
- (135) <u>Use, accessory-Accessory</u>: A use subordinate to and customarily incident to the permitted principal use of the property or <u>B</u>buildings and located upon the same <u>lot-Lot</u> as the principal use.
- (136) <u>Use, legal-Legal nonNon-conforming:</u> The use of a building or land lawfully carried on at the time of the passage of this Ordinance or amendments thereto, but which does not conform to the use regulations of this Ordinance.
- (137) Use, principal Principal: The main or primary use of property or buildings Buildings as

Commented [BA22]: Incorporated definition from shoreland ordinance, except excluded "firepits", which is required to be included in the shoreland ordinance.

Commented [BA23]: Incorporated definition of shoreland ordinance.

specified and permitted by the regulations of the Delistrict in which it is located.

- (138) <u>Variance</u>: Variance means an authorization granted by the Board of Adjustment to construct or alter a <u>buildingBuilding</u>, land use or <u>structure-Structure</u> in a manner that deviates from this Ordinance.

 (Created by Enrolled Ordinance 161-13, effective 09/04/06.)
- (139) <u>Vision setbackSetback</u>: An unoccupied triangular space, at the street corner of a corner <u>lotLot</u>, as established by Section 3.09(1)(B).

Wetlands: Those areas where water is at, near or above the land surface long enough to be capable of supporting aquatic or hydrophytic vegetation and which have soils indicative of wet conditions.

(140) Youth-Ffacility means any facility where minors gather for education or recreational activities including but not limited to playgrounds, Swimming Ppools, libraries, licensed child-care facilities or youth clubs.

Commented [BA24]: Added state definition for wetlands

SECTION 3 GENERAL PROVISIONS

3.01 Compliance.

Except as may be otherwise specifically provided, the use, size, height and location of \underline{B} -buildings now existing or hereafter erected, converted, enlarged or structurally altered, the provisions of \underline{O} -open \underline{S} -spaces, and the use of land, shall be in compliance with the regulations established herein for the \underline{D} -district in which such land or \underline{B} -building is located.

3.02 Building permit.

- (1) Required: No Beuilding shall be erected, structurally altered, or relocated until a building permit has been issued by the building inspector, certifying that such Beuilding, as proposed, would be in compliance with the provisions of this Ordinance and with the building code of the town.
- (2) <u>Application for</u>: An application for a building permit shall be made to the proper Town in which the proposed <u>B</u>-building is to be located.
- (3) <u>Issuance</u>: No building permit shall be issued by the Town, until a zoning permit has been issued by the county zoning administrator.

3.03 Zoning and occupancy and use permits.

(1) Required: No vacant land shall be occupied or used except for agricultural purposes and no B-building shall be hereafter erected, structurally altered, relocated, used, or occupied until zoning and occupancy use permits have been issued certifying that any such B-building, use, or occupancy complies with the provisions of this Ordinance; like permits shall be obtained before any change is made in the type of use or before any nonconforming use is resumed, changed, extended, or granted conditional use status pursuant to Section 3.17(35).

- (2) Application for: Such permits shall be applied for from the county zoning administrator or from the local building inspector where he has been designated as a deputy to the zoning administrator as provided by Section 22.02(4). No application for any permit, V-variance, S-special E-exception, conditional use, site plan, plan of operation, rezoning, license, or other governmental approval under this ordinance shall be deemed to be properly filed unless it is signed by the A-applicant. Application shall be made prior to or at the same time as the application for a building permit, and shall be prepared in triplicate and shall include for the purpose of proper enforcement of this Ordinance the following data:
 - (A) A statement by the Aapplicant as to the intended use of the premises and of any existing or proposed Bauildings thereon.
 - (B) An accurate map of the property, in triplicate, drawn to a reasonable scale and properly dimensioned showing:
 - 1. The boundaries of the property involved.
 - 2. The location of the centerline of any abutting streets.
 - 3. The location on the Lator of any existing Bauildings, proposed additions, or proposed new Bauildings, including the measured distances between such Bauildings and from the Lator Later and from the centerline of any abutting street to the nearest portion of such Bauilding.
 - 4. The proposed floor elevation of any proposed Beuildings in relation to the existing and/or Eestablished Gerade of any abutting streets.
 - 5. The high water line of any stream or lake on which the property abuts.
 - The location of any existing and proposed septic system and well, including those within fifty (50) feet of the property lines.
 - The location and results of any percolation tests and soil borings of the involved property.
 - (C) Where the use involves human occupancy, a plan of the proposed sewage disposal system, if not connected to an approved municipal sewerage system, shall require the certification of the building inspector or plumbing inspector that it conforms to all county and town Ordinances and other governmental laws or regulations then applicable to sewage disposal systems.
 - (D) Satisfactory evidence that a safe and adequate supply of water is to be provided, and the location of any well for that purpose on the property.
 - (E) A fee, as may be established and periodically modified under Section 22.02(5), shall accompany each application. Such fee shall be paid by cash, check or money order to the Waukesha County Park and Planning Commission.
 - Where two or more kitchens are proposed within a single-family Dwelling, the owner shall file a deed restriction in the Waukesha County Register of Deeds office stating, at a minimum, that the residence is to be used for single-family residential

Commented [BA25]: Incorporated language of the shoreland ordinance related to multiple kitchens.

purposes and shall not be used as a multiple family residence.

- Accommodations for persons with disabilities: The Zoning Administrator may issue a permit to modify the standards of this Ordinance in order to provide reasonable accommodations as required by provisions of federal and state law. Such modification shall be the minimum necessary to be consistent with federal guidelines for accommodation of persons with disabilities and shall, where practicable, be terminated when the facility is no longer used by the disabled person(s). A person applying for a permit for construction under this section shall establish the nature and extent of the disability and that the modification requested is the minimum necessary to provide reasonable use of the facility. The reasonable accommodations shall be evidenced by an instrument that is reviewed and approved by the Zoning Administrator and recorded in the Office of the Register of Deeds.
- (3) <u>Issuance</u>: Zoning and occupancy and use permits shall be issued by the zoning administrator after adequate investigation as to compliance or upon recommendation of the deputy where he has made the necessary investigation.
 - (A) Zoning permit: Provided the application is in order and any Bauilding, occupancy, or use as proposed would be in compliance with the provisions of this Ordinance, a zoning permit shall be issued upon such application, and a certification that such permit has been issued shall be posted in a prominent place on the premises during the period of any construction or other activity involved in readying the land or Bauildings for use occupancy.
 - (B) Occupancy and use permit: Within ten (10) days after the notification of the completion of the erection, alteration or relocation of a Beuilding, or of intent to commence a use, the zoning administrator or his deputy shall make an inspection of the premises and any Beuildings thereon, and if such Beuilding, use, or occupancy comply with the requirements of this Ordinance an occupancy and use permit shall be issued.
- (4) Expiration: If within six (6) months of the date of issuance of a zoning permit, the proposed construction or preparation of land for use has not commenced, or if within eighteen (18) months an occupancy and use permit has not been issued, if required by the Town, or the construction has not been completed, said zoning permit shall expire, except that upon showing of valid cause, the zoning administrator may grant an extension of such permit for a period not to exceed six (6) months. Said permit extension shall be issued for the full fee and based upon full conformance with the Ordinance at the time of issuance for the new permit. If the construction has not commenced or is not completed after a total of twenty-four (24) months, a new permit must be applied for and received subject to all fees and subject to the Ordinance in effect at the time of such new permit issuance. Previous incomplete work is not entitled to a new permit if the Ordinance no longer permits said use or Setructure or if changes to the Ordinance have been made subsequent to the original issuance of the permit.
- (5) Temporary occupancy and use permit: Pending the issuance of a regular permit, a temporary permit may be issued for a period not exceeding six (6) months during the completion of alterations or during partial occupancy of a Beuilding pending its permanent occupation. Such temporary permit shall not be issued except under such restrictions and provisions as will adequately insure the safety of the occupants. A temporary permit shall be voided if the Beuilding fails to conform to the provisions of this Ordinance to such a degree as to render it

Commented [BA26]: Incorporated accommodations for persons with disabilities as recommended by WDNR.

unsafe for the occupancy proposed.

- (6) Zoning and Occupancy and Use Permits Site Plans and Plans of Operation: Certain Permitted Uses as well as certain conditional uses require the submission of a Site Plan and Plan of Operation which provide a detailed description of the proposed use and serve as a basis for consideration prior to approval of the plan commission, and either the zoning agency or zoning administrator. The purpose of such a Site Plan and Plan of Operation review is to document the permit file, determine adequacy of the data submitted to describe the permitted and Aaccessory Uses and Bbuildings proposed and document the plan and method of operation to enable a determination of compatibility with the Ordinance and consideration of approval. A Site Plan and Plan of Operation shall include the following information, as well as any other specific information requested by the plan commission, zoning agency or zoning administrator to review the plans and determine compliance with the regulations of this Ordinance:
 - (A) A Plan of Operation is a statement of operations, signed by the property owner and tenant or operator of the business or use, including a detailed description of the request, number of employees, hours of operation, and types of uses, products or services offered.
 - (B) A Site Plan and/or Plat of Survey of the property (in standard engineering or mapping scale which permits a clear representation of the property to a scale not to exceed two hundred (200) feet to one (1) inch), in quadruplicate, showing the location and dimensions of all existing and proposed Beuildings and Setructures and other attributes on the site, the location, number and arrangement of parking spaces or loading areas, lighting fixtures, easements, dumpsters, Seigns, landscaping and screening, and any other factors affecting the development of the site.
 - (C) A stormwater management and erosion control plan consistent with the requirements of the Waukesha County Construction Site Erosion Control and Stormwater Management Ordinance. A grading plan, where required, shall be submitted in quadruplicate to the same scale as the Site Plan, including existing and proposed contours at a maximum of two (2) foot vertical intervals for slopes less than twelve (12) percent and at no more than five (5) foot intervals for slopes twelve (12) percent or greater, existing and proposed features (i.e. berms, swales, ponds, ditches, storm sewers, inlets, etc.), vegetative plan, timetable for completion, the name of the responsible party and a letter of credit, if deemed necessary. The plan commission, zoning agency or zoning administrator has the discretion to request a grading plan in a scale different than the Site Plan in order to show with sufficient detail the contours and features of the property.
 - (D) One set of building plans, State approved if required, at a standard architectural scale, including exterior elevation drawings of all Beuildings proposed.
 - (E) A rendering of all Seigns visible from the exterior, along with the location, dimensions, overall height, illumination and colors of the Seigns.
 - (F) Lighting or photometric plan, including cut sheets of each type of exterior light fixture proposed or existing.
 - (G) A detailed landscaping plan showing the location, sizes and types of proposed vegetation, including seeding mixtures and the amount of topsoil and mulch, the

timetable for completion, and any surfacing plan for parking and loading areas.

(Sections 3.03(4) and (6) were amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Section 3.03(2) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

3.04 Site regulations

(1) Building must be on a Lot: Every Building hereafter erected, structurally altered or relocated shall be located on a Llot as defined in this Ordinance. Any Building used for the Pprincipal Uuse permitted in a particular District shall constitute the Principal Building and there shall be no more than one (1) Principal Building on a Llot unless otherwise stated in this Ordinance. An Accessory Building is considered attached to and part of a Principal Building only if the attachment consists of a Breezeway that is at least a minimum of eight (8) feet in width and a maximum of twenty (20) feet in length and is enclosed on all sides. No Accessory Building shall be constructed until the Principal Building is under construction or completed, and no Accessory Building shall remain on a Lot once the Principal Building has been removed without a Variance from the Waukesha County Board of Adjustment, unless: (1) a Letter of Credit or some other form of financial assurance acceptable to the Waukesha County Department of Parks and Land Use - Planning and Zoning Division is submitted to the Department in an amount sufficient for the Department to have the Accessory Building removed in the event a principal Sstructure is not constructed on the Lot within two years of the date of issuance of the Zoning Permit for the new Principal Building or the date of removal of the Accessory Building, and (2) a deed restriction is recorded in the Waukesha County Register of Deeds office stating a principal Structure shall be constructed on the Lot within two years of the date of issuance of the Zoning Permit for the new Principal Building or the date of removal of the Accessory Building or the Letter of Credit on file with the Department will be used to have the Accessory Building removed. Once the principal Structure is constructed or the Accessory Building is removed, the Waukesha County Department of Parks and Land Use shall cooperate in the rescission of the deed restriction and the release of the Letter of Credit or other financial assurance. Building must be on a lot: Every building hereafter erected, structurally altered or relocated shall be located on a lot as defined herein. Any building used for the principal use permitted in that district shall constitute the principal building and there shall be no more than one (1) principal building on a lot except in business districts, industrial districts, planned unit developments and agricultural districts. In the agricultural district, no more than one (1) residence may be permitted on a single parcel of land unless it can be demonstrated that more than one (1) residence is necessary and accessory to the principal agricultural use of the property. The plan commission and the zoning agency may give approval to permit more than one (1) principal building on a lot in any district where such grant would not be contrary to the spirit and intent of the Ordinance, and provided that sufficient lot area is provided and the building so located so as to individually meet the setback, offset, and lot size and open space requirements of the district in which it is located. No accessory building shall be constructed until the principal building is under construction or completed.

Where the use of the land is principally for agricultural pursuits, and on parcels of thirty-five (35) acres or more, farm buildings may be allowed without the necessity of having a Residence in place or under construction subject to the approval of the plan commission and zoning agency if it is determined that the Beuilding will not be contrary to the spirit and intent of the Ordinance and will not include the operation of a commercial boarding or riding stable for horses or agricultural pursuits specializing in the forced feeding of Livestock, and where it is determined that the use of the Beuilding will be accessory to a

Commented [BA27]: Incorporated language from shoreland ordinance. New language provides a standard for when an accessory building may be considered an attachment to a principal building and be regulated as a principal building and also allows for an opportunity to have an accessory building without a principal building for a limited period of time.

farming operation which is consistent with the use provisions of the \underline{D} elistrict in which it is located.

Buildings or Creation of Lots on a Private Street or Way: The intent of this provision is to discourage the creation of lots and placement of Setructures which do not have adequate access for emergency vehicles and equipment and to provide a right-of-way width which could accommodate a public right-of-way, if necessitated in the future. Subject to the approval of the Plan Commission and the County Zoning Agency, a parcel may be created and a Beuilding may be permitted on a tract of land which does not abut or have direct frontage on a public street or officially approved way (frontage on a controlled access Haighway or a freeway where vehicular access is prohibited does not constitute access or frontage for the purposes of this provision) provided such tract of land is at least three (3) acres in area and has a minimum average width of two hundred (200) feet, has access by a permanent easement at least thirty-three (33) feet in width to a public street or way, will have a paved or gravel driveway width of at least twelve (12) feet and does not conflict with the plans for the future development of Setreets in the area.

Typical or normal lots with Lłot Lłines radiating from the terminus or center of a public culde-sac street are not affected by this provision that requires minimum road frontage on a public street. In a situation where more than one (1) principal Residence or parcel is proposed, the easement for access shall be at least sixty-six (66) feet in width and the paved or gravel drive shall be sixteen (16) feet in width, unless required to be greater, pursuant to a local Ordinance. Where such a Lłot has a narrow strip of land as part of the Lłot (not as an approved easement) extending to the public road from the main part of the Lłot where the B-building could lawfully be placed (flag lot), such narrow portion shall not constitute frontage or part of the three (3) acre lot size requirement unless that narrow portion of the Lłot is as wide as the required minimum average width for the D-district in which it is located. Not more than two (2) such parcels or B-buildings shall be permitted unless necessitated by exceptional circumstances.

(3) <u>Junk and Undesirable Buildings or Structures</u>

- (A) Junk, as defined by this Oerdinance, shall at all times be stored in an enclosed Beuilding thereby securing it from the view of the public and adjacent property owners.
 - This subsection is not intended to regulate or place limitations on any property properly zoned junk yard, salvage dealer, or other Jɨunk, waste disposal or storage activity for which a valid license from the State or Wisconsin or other necessary municipal issuing authority is required and proper permits have been issued and all such licenses and permits are in full force and effect and the operation is in full compliance therewith.
 - 2. This subsection is not intended to regulate or place limitations on the storage of idle, but operable farm equipment on Ffarms greater than thirty-five (35) contiguous acres or the storage of inoperative or abandoned farm equipment on Ffarms greater than thirty-five (35) contiguous acres if such inoperative or abandoned farm equipment is screened from the view of the public and adjacent property owners by a natural or man-made visual barrier.
 - This subsection is not intended to regulate or place limitations on the storage of idle but operative snow removal vehicles or equipment, or lawn mowing equipment.

- This subsection is not intended to regulate or place limitations on the orderly storage of firewood for fuel.
- 5. This subsection is not intended to regulate the temporary storage of construction materials which are for use on the site for the project authorized by an active zoning permit and which are stacked, stored and secured on the site in an orderly method.
- (B) No Undesirable Structures: No Beuilding or Setructure shall be erected, structurally altered or relocated in a manner which shall be of such character as to adversely affect the nearby properties or general desirability of the neighborhood. The determination by the Plan Commission shall be stated in writing, including the reason for denying a permit or conditions of approval for a permit, and may be based upon considerations that the design or appearance is of such an unorthodox or abnormal character as to have an adverse effect on the nearby properties or general desirability of the neighborhood.
- (4) <u>Street grade</u>: Every <u>B</u>building hereafter erected, structurally altered, or relocated, shall be at a grade approved by the building inspector as being in satisfactory relationship with the established street grades, or with the existing street grade where one is established, with particular consideration for proper drainage and safe vehicular access.
- (5) Preservation of topography: In order to protect the property owner from possible damage due to change in the existing grade of adjoining lands, and to aid in preserving and protecting the natural beauty and character of the landscape, no change in the existing topography of any land shall be made which would result in increasing any portion of the slope to a ratio greater than three (3) horizontal to one (1) vertical, within a distance of twenty (20) feet from the property line, except with the written consent of the abutting property owner and with the approval of the plan commission; or which would alter the existing drainage or topography in any way as to adversely affect the adjoining property. In no case shall any slope exceed the normal angle of slippage of the material involved and all slopes shall be protected against erosion.
 - (A) The construction of a Retaining Wwall (stone, ties, brick or other material), five (5) feet or less from a property line, may be specifically authorized by the Plan Commission and County Zoning Agency and on agreement made between the Plan Commission, County Zoning Agency and Amplicant stating the method and purpose of construction and will not in any way adversely affect drainage or the aesthetics of the adjacent lot. A Retaining Wwall greater than five (5) feet from a property line, may be allowed pursuant to issuance of a Zoning Permit (Minor Grading Permit) and an agreement being made between the owner and the Town Planning Commission and the County Zoning Administrator which will serve to promote the purpose and intent as stated in this Ordinance.

Fill or grading considered by the zoning administrator to be necessary backfill and/or excavation for an otherwise permitted Setructure may be permitted without the necessity of securing a conditional use permit as long as said fill or grading is accessory to said construction and does not create slopes greater than three (3) horizontal to one (1) vertical and does not extend to a distance greater than thirty (30) feet from the foundation and does not divert runoff directly onto adjacent property or adversely affect adjoining property. In order to make such a determination, the property owner shall submit a grading plan of existing and

proposed grades on the subject Ltot and adjacent lands where said accessory fill and/or grading is closer than twenty (20) feet to a property line.

Land \underline{A} altering \underline{A} activities extending greater than thirty (30) feet from the foundation may be allowed subject to issuance of a minor grading permit (zoning permit) without benefit of a Conditional Use Permit unless the quantities and the area of fill exceeds three thousand (3,000) square feet and fifteen (15) cubic yards. This provision excludes the area normally associated with septic system installation, backfilling and grading around the foundation, as above, and normal driveway construction. Further, no fill or alterations on existing topography shall be allowed under any circumstances which will alter the drainage or topography in a way which will adversely affect the surrounding lands. In making such a determination, the Zoning Administrator shall have the authority to determine the affect of the construction or fill on surrounding property and require improvements and/or facilities as may be in the best interest of preserving the topography and drainage system and which will have the effect of lessening the impacts on either upstream, downstream or adjacent properties. In case of a dispute or question arising as to the adversity or effect of the project on either the property owner, adjacent owners or the general public, said question shall be submitted to the County Board of Adjustment pursuant to the procedures for appeal as enumerated in Section 19. Land Antering Anctivities may also be subject to locally adopted or state mandated Erosion and Sediment Control Ordinances in addition to the requirements set forth herein.

- (B) Land Aaltering Aactivities such as the placement of fill, excavation, and other earth moving activities in excess of the above may be allowed subject to issuance of a conditional use permit as long as said fill, excavation or earth moving activities do not occur in a wetland as indicated on the Final Wisconsin Wetlands Inventory Maps for Waukesha County or subsequently revised by hydraulic analysis and approved by the Army Corps of Engineers and/or the Department of Natural Resources. The performance of such earth altering must not impede drainage or reduce the floodwater storage capacity of any floodland.
- (6) Site Protection: Any property disturbed with Lłand Aeltering Aectivities as may be authorized thru the issuance of a Zoning Permit or a Conditional Use Permit, shall be required to protect the disturbed land surface of the Llot or building site that is susceptible to erosion while under construction and which is not occupied with Beuildings, dedicated parking areas or other hard surfaced areas with suitable stabilization measures. Said disturbed areas shall be permanently stabilized and continuously maintained with suitable vegetative cover or other approved landscape material, and in any case, shall be required to conform with the provisions of the Waukesha County Construction Site Erosion Control and Stormwater Management Ordinance and Uniform Dwelling Code for one and two family dwellings. A Letter of Credit or other forms of financial guarantee to ensure performance may be required by the building inspector, plan commission, the zoning administrator, zoning agency or the Land Resources Division of the Waukesha County Department of Parks and Land Use.

(Sections 3.04(1) and (5)(C) were amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Section 3.04(3) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

3.05 **Drainage regulations**

Commented [BA28]: Matched language of shoreland ordinance regarding the separation of the lowest level of a building from seasonal high groundwater conditions.

- (1) Building Construction: In no case may a Pprincipal Bbuilding be located in an area zoned conservancy or field identified as Wwetland. No Pprincipal Bbuilding shall be erected, or relocated, and no below grade Sstructures shall be expanded on newly created oron existing Liots that are not in compliance with the site drainage standards contained in the Waukesha County Stormwater Management and Erosion Control Ordinance, including all county technical procedures and forms used to enforce these standards (Chapter 14-342(c)). The lowest floor, including any basement floor, shall not be less than one (1) foot above the highest seasonal ground water level. For the purposes of this Section, the highest seasonal ground water level is defined as the upper limit of the zone of soil saturation caused by underlying ground water at its highest level. Where groundwater limitations exist, subdivision plats and certified survey maps shall state the lowest allowed floor elevation for any proposed principal Sstructure as needed to ensure compliance with the above noted site drainage standards. All basement elevations must comply with the subdivision plat or certified survey map or with the master grading plan referenced on the subdivision plat or certified survey map. The zoning administrator and/or building inspector may request at the owner's expense the advice and assistance of a licensed professional engineer specializing in soils engineering or other qualified person in fulfilling their duties pursuant to this provision. Building, drainage, grading or other similar plans may be required to determine compliance with this Section. The town and the county accept no liability for construction activities involving groundwater limitations.
 - (A) In the event the Aapplicant disputes the necessity for or the adequacy of the site drainage standards noted above, the matter shall be reviewed by the Waukesha County Board of Adjustment pursuant to the appeal provisions of this Ordinance and the Waukesha County Stormwater Management and Erosion Control Ordinance.

 The Aapplicant may also request a Variance from the 1-foot groundwater separation requirement for Basements, which shall also be reviewed by the Waukesha County Board of Adjustment pursuant to the appeal provisions of this Ordinance and the Waukesha County Stormwater Management and Erosion Control Ordinance.
- (2) Site Protection: Any property disturbed with Lłand Aæltering Aæctivities as may be authorized through the issuance of a zoning permit or a conditional use permit, shall be required to protect the disturbed land surface of the Llot or building site that is susceptible to erosion while under construction and which is not occupied with Beuildings, dedicated parking areas or other hard surfaced areas with suitable stabilization measures. Said disturbed areas shall be permanently stabilized and continuously maintained with suitable vegetative cover or other approved landscape material and shall be required to conform with the provisions of the Waukesha County Stormwater Management and Erosion Control Ordinance and the Uniform Dwelling Code for one and two family dwellings, when applicable. A Letter of Credit or other forms of financial guarantee to ensure performance may be required by the building inspector, plan commission, the zoning administrator, zoning agency or the Waukesha County Department of Parks and Land Use, Land Resources Division.

Adequate drainage required: In no case may a principal building be located in an area zoned Conservancy or in an area considered to be one of the eight (8) types of wetlands (type 1-8) as described in Circular 39 of the Fish and Wildlife Service, U. S. Department of Interior, published in 1956 and which are on record on the 1975 aerial maps of the Southeastern Wisconsin Regional Planning Commission. No principal building shall be erected, structurally altered or relocated on land which is not adequately drained, which has an observed or estimated high ground water table condition or having soils which may have a seasonal zone of water saturation as may be determined by use of USDA soil survey, an

onsite soil investigation by a certified soil tester or other qualified engineer or soil scientist, unless adequate measures are taken to protect the building, its basement and its foundation from such water conditions. The identification of mottled characteristics in the soil profile may be utilized to identify soil conditions which may require additional protective measures as outlined below. Where soil monitoring tests have been made, the data resulting from such testing procedures may also be utilized to assist in establishing soil conditions requiring protection measures.

Normally, a few faint mottles or a very low incidence of mottling will not necessitate any special consideration. Basements will be allowed to extend into such soils where those conditions exist as long as appropriate construction measures are provided. Where the incidence of mottling is considered very severe or where ground water is observed in the soil profile, no basement area will be allowed to be placed below the level at which such a condition exists. The zoning administrator and/or building inspector may review such conditions by observation and other evidence at the building site and shall require appropriate measures to be taken beyond normal footing drains as normally required by local building codes to adequately protect the building and its basement and foundation from such potential water related problems. The zoning administrator and/or building inspector may request, at the owner's expense, the advice and assistance of a licensed professional engineer specializing in soils engineering or other qualified person in fulfilling their duties pursuant to this provision.

- (A) The zoning permit and building permit issued for the erection, structural alteration or relocation of a principal building shall state specific design, engineering and construction requirements, as a condition of the permit, notwithstanding applicable construction codes, which must be incorporated within the improvement to be done on and in soil which has such conditions necessitating additional protection of the building, basement, foundation, occupants and personal property. Such provisions which may be required may include but shall not be limited to the techniques enumerated below: auxiliary power supplies; gravity drainage of foundation footings together with the installation of a sump pump which will be operative in the event of blockage of the gravity drains, gravel backfill and extra drains, waterproof poured concrete basements.
- (B) Subdivision plats and certified survey maps shall state, on their face, whether protection measures, pursuant to the above, are likely to be required as a condition of a zoning and building permit. The planning commission or the county zoning agent may cause such notice to be affixed to the face of the document.
- (C) In the event a dispute arises as to the necessity for or the adequacy of the protection measures set forth above, the matter shall be reviewed by the Waukesha County Board of Adjustment pursuant to the appeal provisions of this Ordinance.
- (23) Obstruction to drainage prohibited: The damming, filling, relocating or otherwise interfering with the natural flow of surface water along any surface water drainage channel or natural water course shall not be permitted except with approval of the plan commission, county zoning agency and the department of natural resources pursuant to chapter 30 of the Wisconsin Statutes.
- (4) Building restricted adjacent to non-navigable drainage channels, and water courses, and

eonservancy districts: No building Sstructure other than a water dependent structure, bridge, culvert, walkway, dam, boathouse, or revetment, subject to the aforesaid approval shall be erected, structurally altered or relocated within seventy five (75)thirty-five (35) feet of the Oerdinary Hhigh Wwater Mmark of a non-navigable surface water drainage channel and water courses., body of water having at least five (5) acres in surface area and a minimum average depth of at least three (3) feet, man made drainage channel or natural water course, nor closer than seventy five (75) feet from the boundary line of a conservancy zoning district.

(Section 3.05(3) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

3.06 Sanitation and water supply

(1) Safe sewage disposal possible: No Pprincipal Bbuilding shall be erected, structurally altered, or relocated unless it has been certified by the building inspector or plumbing inspector that it conforms to all town Ordinances, county Ordinances, and other governmental laws or regulations then applicable to sewage disposal systems, and that satisfactory evidence has been submitted to show that suitable provision for disposal of sewage, based on the proposed use, is possible on said Llot if it is not served by an approved municipal or other state approved sewage disposal system.

(Explanatory note: While every attempt has been made, through control of minimum lot size, building location and plumbing standards, to insure that proper disposal of sewage will be provided on any lot, it is recognized that no such standard will completely insure adequate disposal in every situation. This Section has been written for the purpose of giving the community the authority to require whatever additional provisions are necessary to prevent a sanitary problem from developing in a situation where the normal requirements will not insure proper sewage disposal.)

- (2) Approved septic system: No Perincipal Beuilding shall be erected, structurally altered or relocated unless a sewer is installed running to a septic tank designed and located in accordance with the town Ordinances and other governmental laws or regulations then applicable to sewage disposal systems, or to an approved municipal or other state approved sewage disposal system.
- (3) <u>Outhouses prohibited</u>: No outhouse or privy shall be hereafter erected.
- (4) Water supply required: No occupancy and use permit shall be issued for a Beuilding used for residence residential purposes unless provision is made for a safe and adequate supply of water in or within three hundred (300) feet of said dwelling or connection is to be made to an approved municipal or community water system.
- (5) Reduction in Lot Size, Lot Width, Offset, Road Setback, Open Space and Increase in Floor Area Ratio and Increase in Density in Planned Unit Development: In the case of any lot proposed to be served by a municipal or municipally approved communal sewage system or water system, and where such service would be provided prior to any occupancy of such lot, the Plan Commission and Zoning Administrator may authorize the reduction of the lot size, lot width, open space, offset and road setback requirements applicable to such lot and increase the floor area ratio and increase the density in planned unit developments without the necessity of public hearing. In making the decision, the Plan Commission and Zoning Administrator shall give particular consideration to the following:

A The suitability of soil, terrain and groundwater table conditions and the practicality

Commented [BA29]: Modified provision to relate to nonnavigable drainage channels and watercourses with a reduced setback of 35 ft. to protect buildings from flooding. Wetland setback is addressed in S. 3.09(2).

Commented [BA30]: Relocated applicable sewer reduction language to applicable districts. Deleted lot size reduction for single-family lots served by sewer and water to simplify code and because of lack of municipal water service within general code jurisdiction.

of providing municipal sewer or water service to the parcel.

B The effect of any reduction in the lot size, lot width, open space, road setback and offset requirements and the increase in floor area ratio and density requirements on the character and value of surrounding development.

The maximum amount of reduction in the lot size, lot width, open space, offset and road setback requirements or increase in floor area of individual lots and the maximum increase in the density of planned unit developments shall not exceed 30% and in no case reduce the lot area requirements for the individual lots to less than twelve thousand (12,000) square feet except as provided and for multi-family type units in Sections 3.08 (7) (N) and (P).

3.07 Use regulations

- (1) <u>Uses Restricted</u>: In any <u>D</u>district, no <u>B</u>duilding or land shall be used and no <u>B</u>duilding shall be hereafter erected, structurally altered or relocated except in conformance with the regulations hereinafter established for the <u>D</u>district in which the property is located, or as otherwise provided in this Ordinance. Where a change in use or a new use of a <u>B</u>duilding or premises is proposed in any Business, Industrial District or Public and Institutional District or at the site of a <u>L</u>degal <u>N</u>non-conforming <u>U</u>duse or a conditional use, a Site Plan and Plan of Operation shall be prepared for review and approval pursuant to Section 3.03(6) of this Ordinance. Where a change in ownership or operator of a <u>B</u>duilding or premises is proposed in any Business, Industrial District or Public and Institutional District or at the site of a <u>L</u>degal <u>N</u>non-conforming <u>U</u>duse or a conditional use, a Plan of Operation shall be prepared for review and approval pursuant to Section 3.03(6) of this Ordinance.
- (2) Accessory Usses: In Delistrict, Accessory Behuildings and uses customarily incident to the Permitted Usses in that Delistrict shall be permitted to such requirements as may be hereinafter designated for that Delistrict in which they are located. No Peyramiding as defined herein shall be permitted on any lands fronting on a lake except as may be specifically permitted accessory to a marina or resort and which may be allowed under the terms of a conditional use permit for a Pelanned Usnit Delevelopment.
- (3) <u>Unclassified Uses:</u> Any use not specifically listed as <u>Ppermitted Uses</u> or conditional use shall be considered to be prohibited except as hereinafter provided. Where deemed appropriate the Plan Commission and Zoning Agency shall have the authority to authorize uses not specifically enumerated or authorized under other procedures or zoning districts under the terms of Section 3.08(7)(X) of this Ordinance.
- (4) Additional Requirements: For any use or Structure in any Delistrict, which becomes hazardous, harmful, noxious, offensive or a nuisance to the surrounding neighborhood, the owner or occupant may be required to correct, improve or abate such conditions by such measures as may be mutually directed by the Plan Commission and Zoning Administrator consistent with reasonable technology and economic practicality and in conformance with reasonable standards or may be determined by the Plan Commission and Zoning Administrator as may be contained in this Ordinance. Any Beuilding determined to be unfit for Hehuman Hebabitation or which may endanger the health, safety and welfare of the public as may be determined by the Town board after recommendation by the Plan Commission or Zoning Administrator shall be removed pursuant to the procedures outlined by the Wisconsin Statutes.

(Section 3.07(1) was amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Section 3.07(3) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

3.08 Conditional uses

- (1) Approval required: Certain uses and situations which are of such a special nature, or are so dependent upon actual contemporary circumstances, as to make impractical the predetermination of permissibility, or the detailing in this Ordinance of specific standards, regulation, or conditions which would permit such determination in each individual situation, may be permitted as conditional.
- (2) Application: Applications for conditional use permits shall be made in triplicate to the county on forms furnished by the county zoning administrator, and shall include the following where pertinent and necessary for proper review by the county zoning agency and the town plan commission:
 - (A) A map (preferably a topographic map) in triplicate, drawn to a scale of not less than two hundred (200) feet to one (1) inch showing the land in question; its legal description and location; location and use of existing Beuildings; sanitary systems and private water supplies on such land; the high water elevation of any №avigable Wwaters within one hundred (100) feet of the land in question; and the proposed location and use of any Beuildings, sanitary sewer systems and wells on such land and within one hundred (100) feet of such land in question.
 - (B) The names and complete mailing addresses, including zip codes of the owners of all properties within three hundred (300) feet of any part of the land included in the proposed change.
 - (C) Additional information as may be required by the county zoning agency, the county health department or the town plan commission.
 - (D) A fee, as may be established and periodically modified under Section 22.02(5) shall accompany each application, except those submitted by a governmental body or agency. Such fee shall be paid by cash, check or money order to the Waukesha County Park and Planning Commission to defray the cost of official notification and posting of the public hearing. Costs incurred by the county zoning agency in obtaining legal, planning, engineering and other technical and professional advice in connection with the review of conditional use applications and preparation of conditions to be imposed on such uses shall be charged to the △applicant, and if required by the county zoning agency, a fee covering such costs shall accompany the application.
 - (E) Where necessary, to comply with certain Wisconsin Statutes, an application will be submitted to the department of natural resources.
- (3) Public Hearing: Upon receipt of the application, the foregoing data and fees, the Zoning Administrator shall establish a date for a joint public hearing by the Town Plan Commission and the County Zoning Agency, or its designee, and shall publish notice of said hearing once each week for two (2) consecutive weeks in a newspaper of general circulation in the area of the proposed conditional use. Notice of the public hearing shall be given by first class mail to the owners of all lands within three hundred (300) feet of any part of the land

included in such conditional use at least seven (7) days before such public hearing.

A copy of the notice of public hearing along with pertinent information relative to the specific nature of the matter (copy of application and map) shall be transmitted without delay to the Town Clerk by first class mail not less than ten (10) days prior to the date of the hearing. Testimony of all interested parties will be recorded at the public hearing and the Town Plan Commission shall take action within thirty (30) days, to either recommend approval or disapproval of the application along with any recommended conditions of approval or reasons for recommending denial. If additional time is necessary beyond the thirty (30) days referred to above, unless time is extended, such time may be extended with the consent of the petitioner.

- (4) Final review and approval: The county zoning agency shall review the proposal as submitted along with any requirements as may be required by the department of natural resources. Any conditions deemed necessary by the town plan commission or county zoning agency shall be made an integral part of the permit. These conditions shall be complied with by the Aepplicant and any deviation or alteration of those conditions set forth in the permit shall constitute a violation of the terms of the conditional use permit. Such violation shall constitute a violation of this Ordinance and will be subject to prosecution and penalties under the terms of this Ordinance. Notification of county zoning agency action on conditional use permits shall be sent to the department of natural resources where applicable.
- (5) Application for change of conditional use permit: If any holder of a conditional use permit wishes to extend or alter the terms of said permit, he must apply for such extension or alteration through the procedure of application for conditional use permits detailed herein.
- (6) Expiration of conditional use status: Conditional use status will terminate when, after public hearing, the plan commission and county zoning agency determine any of the following:
 - (A) The conditional use has not continued in conformity with the conditions of the permit.
 - (B) A change in the character of the surrounding area or in the conditional use itself causes such use to be no longer compatible with surrounding uses.
 - (C) The conditional use has been discontinued for a period of twelve (12) consecutive or eighteen (18) cumulative months in a three-year period. A business of a seasonal nature shall not be deemed discontinued during periods in which it is normally inactive (i.e., summer camps, snowmobile courses, ski areas, marinas, quarries, etc.). Upon such determination, the owner of the premises shall be required to bring all such land and Beuildings into conformity with the district regulations of the Delistrict in which such former conditional use is located, and all other provisions of this Ordinance within ninety (90) days from such determination.

Upon such determination, the owner of the premises shall be required to bring all such land and \underline{B} -buildings into conformity with the district regulations of the \underline{D} -district in which such former conditional use is located, and all other provisions of this Ordinance within ninety (90) days from such determination.

(7) <u>Conditional use permitted</u>: Subject to the foregoing, in addition to such uses enumerated in the district regulations, the following may be permitted as conditional uses in the <u>Delistricts</u> specified, provided further that a public hearing shall be held by the approving body before approval for any such conditional use is granted:

- (A) Airports, Landing Fields and Take off Strips: In all agricultural, AD-10, RRD-5

 Delistricts, HG High Groundwater District and non-wetland C-1 Conservancy

 Delistricts, except that in the FLP Farmland Preservation District and the FLC

 Farmland Conservancy District, the aviation use must be agriculturally or

 municipally related and shall comply with all provisions of Section 6.1, subject to
 the approval of:
 - Building and site plans and a plan of operation for the conduct of the use shall be approved by the Plan Commission and County Zoning Agency.
 - Review and approval by the Federal Aviation Administration and/or the State of Wisconsin Bureau of Aeronautics or a letter waiving their approval or indicating such approval is unnecessary.
- (AA) <u>Land-Aeltering Activities</u>: Land-Aeltering Aectivities may be permitted as a conditional use in any <u>Delistrict</u>, except the Conservancy <u>Delistrict</u> unless rezoned to allow such activity.

Highway construction which may be exempted by a written Memorandum of Understanding between the Wisconsin Department of Natural Resources and Department of Transportation for a specific highway project, home construction and the attendant limited grading and fill necessary to achieve positive drainage away from the foundation and dredging as may be allowed in Section 3.04(5) of this Ordinance and minor grading as defined in the Ordinance, shall be excluded from regulation under this provision, but may be regulated elsewhere under this Ordinance.

Land \underline{A} -altering \underline{A} -activities permitted as a conditional use shall be subject to the following:

- Detailed plans, at a scale of not less than 1" = 100', of the project including areas to be graded, filled or otherwise altered along with seeding and/or vegetation plans and planting schedule and erosion and sedimentation practices to be employed shall be submitted for review and approval.
- No such use shall create flooding, concentrated runoff, inadequate drainage, unfavorable topography, excessive erosion and sedimentation or restrict navigability in any state water.
- Such use shall comply with the conditions established by the plan commission, the zoning agency, and where applicable, the State pursuant to Chapter 87 and Chapter 281 of the Wisconsin Statutes and any federal regulations.
- If a rezoning is required, the procedure established in this Ordinance shall be complied with and the amendment to any other appropriate zoning district shall be approved.
- 5. The proposed grading and Lłand_-Aaltering Aactivities shall conform to the

35

Waukesha County Construction Site Erosion Control and Stormwater Management Ordinance and a permit under that ordinance must be received from the Waukesha County Department of Parks and Land Use, Land Resources Division, prior to the issuance of the conditional use permit.

- (B) Antique Shops, Gift Shops, Art Studios and Similar Uses: Such uses are permitted by right in business districts. In addition, such uses are permitted conditionally in all other Delistricts except the FLP, FLC, HG and C-I Districts subject to the following:
 - The location, site plans and plan of operation have been submitted to and approved by the Plan Commission and County Zoning Agency.
 - 2. Such use is compatible with surrounding land uses.
- (BB) Business, Park and Shopping Center Uses: In the B-P and B-4 zoning districts certain uses may be allowed as a conditional use, as those uses or situations are of such a special nature or are so dependent upon the actual circumstances that it is impractical to allow them as a Permitted Uses by right. In evaluating the proposed use the Town and County Plan Commissions shall base their action on whether or not the proposed use will violate the spirit or intent of the Ordinance, be contrary to the public health, safety or general welfare, be hazardous, harmful, noxious, offensive or a nuisance by reason of noise, dust, smoke, odor, traffic congestion, incompatibility of uses, or other similar factors or for any other reason causes substantial adverse effect on the property values and general desirability of the neighborhood or the center. The following considerations shall be utilized in the determination of the appropriateness of the contemplated uses by the Town and County:
 - The Town and County Plan Commissions must review and approve all existing and proposed uses and the Plan of Operation.
 - 2. The economic practicality of the proposed use.
 - The proposed use shall be served by adequate off-street parking, loading and service facilities.
 - The proposed use shall not create an adverse effect upon the general traffic patterns, circulation or adjoining property.
 - 5. The architecture, landscape, lighting and general site development shall be compatible with the surrounding neighborhood and uses.
 - The use may be granted with any reasonable conditions deemed necessary by the Town and County Plan Commissions.
 - The proposed development shall have adequate drainage and stormwater retention facilities, sewage and water facilities. Restrictions may be placed on uses without public sewer.
 - 8. The intended use complies with the locally adopted Land Use Plan.
- (C) <u>Automobile Service Station, Gasoline Sales and Convenience Stores Associated</u> <u>with Gasoline Sales</u>: In B-2 and B-3 Business Districts and any Industrial District,

subject to the following:

- The location, building and site plans and plan of operations shall be submitted to and approved by the Plan Commission and County Zoning Agency.
- No gasoline pumps and accessory equipment shall be closer than fifteen
 (15) feet to the Bbase Setback Lline and fifty (50) feet Ooffset to the side and rear yards. Underground or above ground storage tanks shall conform with state standards.
- No lighting installation shall be permitted which creates a hazard to traffic
 or a nuisance to surrounding property and shall be shielded, baffled or
 shaded to effectuate and avoid such hazard or nuisance.
- (D) Animal Hospitals, Veterinarian Clinics, Commercial Kennels: In any Delistrict, except C-1 and EC Environmental Corridor Delistricts. However, animal hospitals and veterinarian clinics shall be Ppermitted Uesses by right in the A-B Agricultural Business Delistricts and business districts as long as such facilities do not include the operation of a Ceommercial Kennel. In the FLP and FLC Districts, such uses shall comply with all requirements of Sections 6 and 6.1. No Setructures are allowed in the FLC or HG District. The following requirements shall be met:
 - The location, building and site plans, and a plan of operation shall be submitted to and approved by the Plan Commission and the County Zoning Agency.
 - Animal hospitals and clinics not involved in the operation of a Ceommercial Kkennel may be permitted on lots of not less than one (1) acre and shall be in conformance with building location, height regulations and area regulations of the Odistrict in which such facilities are located. A commercial kennel operation shall not be permitted on parcels of less than three (3) acres and three hundred (300) feet of minimum average width.
 - 3. No Beuilding other than one used only for residence residential purposes shall be closer than fifty (50) feet to the Letot Letine of an adjoining Letot in an Agricultural or Residential Zoning District. Where the Beuildings are to be used to board or house dogs in a Ceommercial Kennel, including outdoor kennel runs, such structures and fenced runs shall not be closer than one hundred (100) feet to an adjoining Letot Letine.
- (E) <u>Churches, Synagogues and other Buildings for Religious Assembly</u>: In any <u>D</u>district, except in the C-1, HG, FLC and EC Environmental Corridor <u>D</u>districts subject to the following requirements:
 - The location, building and site plans and a plan of operation shall be submitted to and approved by the Plan Commission and County Zoning Agency.
 - A floor area ratio Building Footprint of no more than fifty percent (50%) be allowed.

- Off-street parking be provided for one (1) automobile for each four (4) seats provided in the main assembly of the <u>B</u>building.
- Such use shall conform to the setback, height, and double the offset requirements of the Delistrict in which it is located.
- 5. The height limitation may be extended to a maximum of fifty (50) feet provided the minimum required setbacks and Ooffsets shall be increased two (2) feet for every additional foot of height in excess of the permitted maximum in that Odistrict. The aforesaid height regulation shall not apply to the spire or belfry of a church except where Airport Safety Zone regulations specifically limit the maximum height.
- (F) Cemeteries and Mausoleums for the Burial of Human Remains only: In any Delistrict, except C-1, FLC or EC Environmental Corridor Districts subject to the approval of the Town Board following recommendation of the Plan Commission. In the FLP Delistrict, cemeteries and mausoleums that are governmental, institutional, religious, or nonprofit are permissible if they comply with the terms of Section 6.1.
- (G) Commercial fish or bait ponds or hatcheries: Such uses are considered Ppermitted U+ses by right within the FLP and FLC Districts. In all other Delistricts such uses are permitted conditionally, subject to the following:
 - The location, building and site plans, and plan of operation shall be submitted to and approved by the plan commission.
 - 2. No such use shall be permitted on a Litot less than five (5) acres in area.
 - 3. No <u>B</u>building other than one used only for <u>residence-residential</u> purposes shall be closer than fifty (50) feet to the <u>L</u>lot <u>L</u>line of an adjoining <u>L</u>lot in a <u>D</u>elistrict permitting residential uses.
- (H) <u>Contractor's Yard</u>: In A-1 Agricultural Districts, A-5 Mini-Farm District, B-3 General Business District, Q-1 Quarry District, or Industrial Districts subject to the following:
 - 1. The minimum Lifot Agrea shall be at least five (5) acres.
 - 2. All Bbuildings used in the conduct of the business shall be located at least one hundred (100) feet from the Litot Litine of an adjoining Litot in a residential district or at least fifty (50) feet from a Litot Litine of an adjoining Litot in any other Delistrict.
 - 3. No such use shall be allowed on any parcel, except as may front directly upon and have access to an arterial or major Ceollector Setreet, as defined in the Waukesha County Shoreland and Floodland Subdivision Control Ordinance or within an established industrial park, where the Reoads can accommodate the heavy equipment.
 - A planting screen at least ten (10) feet high in initial height shall be provided between any abutting property line and the proposed use. The plan commission or the zoning agency may increase or decrease the

38

planting screen requirements as may be deemed appropriate.

- 5. In determining whether or not the proposed conditional use should be approved, the plan commission and zoning agency shall make a determination that the proposed conditional use is compatible with adjacent land uses. If it is determined that the proposed conditional use would in any way be incompatible with the adjacent land uses or represent an adverse effect or nuisance to adjacent land uses, the proposed conditional use shall not be approved.
- 6. A Site Plan and Plan of Operation shall be submitted to the plan commission and zoning agency for review and approval and must include the type and quantity of equipment and vehicles owned or leased by the property owner, the storage of materials, and hours of operation.
- (I) Fur Farms, Pig Farms, Creameries, Condenseries, Commercial or Custom Grain

 Drying Operations, Poultry and/or Egg Production: In the A-1, A-B, A-O, A-5,

 AD-10, FLP, FLC, A-T, and RRD-5 Delistricts. Commercial or custom grain drying,
 poultry and/or egg production are considered Permitted Uesses by right in the A-B

 Agricultural Business Delistrict and conditional uses in all other of the above
 agricultural districts. The following minimum requirements shall be complied with
 in the granting of conditional uses under this Section:
 - The location, building and site plans and a plan of operation shall be submitted to and approved by the Plan Commission and County Zoning Agency.
 - No Be building other than one used only for residential purposes shall be located closer than one hundred (100) feet of the Let Letine of an adjoining Let in a residential district. In all other cases a minimum Offset of fifty (50) feet shall be maintained.
 - 3. Although the Ordinance does not prescribe exactly how a plan of operation is to be put together, of particular interest to the plan commission will be the method by which animal waste will be handled in a safe and healthful manner. No such consideration or approval will be granted on a Liot of less than five (5) acres in size.
- (J) Testing Laboratories (Experimental or Analytical): Agricultural, medical, biological, food processing and industrial design and manufacturing uses are Permitted Utses by right in the B-3 General Business and Industrial Districts subject to the site plan and plan of operation provisions of those review Delistricts and conditional uses in the A-B Agricultural Business, A-1 Agricultural and A-la Agricultural Districts, subject to the following standards:
 - The location, building and site plans and a plan of operation shall be submitted to and approved by the Plan Commission and County Zoning Agency.
 - 2. The minimum lot size shall be three (3) acres.
 - 3. The minimum Ooffset for a Bouilding housing such uses shall be fifty (50)

39

feet where the zoning upon the adjoining Liot permits residential use.

- Off-street dedicated parking at a rate of one (1) space for each three hundred (300) square feet of <u>F</u>floor <u>A</u>area.
- 5. Approvals of any other applicable state or federal agencies.
- (K) <u>Legal N+on-conforming U+ses</u>: In any <u>D</u>elistrict as provided by Section 3.17.
- (KK) <u>Limited Family Business</u>: The purpose and intent of this Section is to provide a listing of procedures and standards of operation for limited family businesses that may operate in an attached garage or detached <u>Aeccessory Beuilding</u> under a conditional use permit in residential or agricultural districts except the EC Environmental Corridor District and FLC District. Within the FLP District, such uses must comply with the terms of Section 6.1.
 - A conditional use permit for a limited family business is designed to
 accommodate small family businesses without the necessity for relocation
 or rezoning, while at the same time protecting the interest of the adjacent
 property owner and any future development of the area. Any expansion of
 the limited family business will be subject to an amendment to the
 conditional use permit and, if said amendment is denied, the conditional use
 permit would either terminate or the expansion could not take place.
 - All employees, except one full-time equivalent, shall be members of the F\u00e5amily residing on the premises.
 - The plan commission and zoning agency shall determine the percentage of the property that may be devoted to the limited family business and the more restrictive determination shall apply.
 - 4. The limited family business is restricted to a service oriented business or home occupation business and is prohibited from manufacturing or assembling products. The sale of products on the premises which are not produced by the limited family business is prohibited. The sale of products available for sale as accessories to the business may be permitted or limited by specific conditions in the conditional use permit (i.e. hair care products such as shampoo and conditioners normally associated with a business that cuts or styles hair).
 - 5. The conditional use permit shall restrict the number and types of machinery and equipment the limited family business operator may be allowed to bring onto the premises and whether the machinery and equipment must be stored inside a Beuilding.
 - 6. The Setructures used in the limited family business shall be considered to be residential Aeccessory Beuildings and shall meet all the requirements for such Beuildings. The design and size of the Setructures are subject to conditions in the conditional use permit.
 - The conditional use permit shall automatically expire and terminate on the sale of the property or its transfer to a non-occupant of the property.

- 8. The limited family business shall not operate on a parcel having less than the minimum parcel size for the Delistrict in which it is located. For certain uses which are determined by the town and county to have a potential adverse effect on adjacent residential zoned properties, additional requirements regarding location and site standards (i.e. screening) may be required as conditions of the use.
- (L) <u>Mobile Home Parks and Camps</u>: In the B-1 and B-2 Business Districts, subject to the following:
 - The location, building and site plans and plan of operation shall be submitted for review and approval by the Plan Commission and the County Zoning Agency.
 - The provision of all county, state and local regulations upon trailer Mmobile
 Hhomes and Mmobile Hhome Pparks shall be met.
 - No such use shall be allowed unless served by municipal sewage disposal facilities_and the density of the project shall not exceed that which may be authorized by applying the provisions of Section 3.06(5) of this Ordinance.
- (M) <u>Motels and Hotels</u>: In the B-1 Restricted Business District and B-2 Local Business District only, subject to the following:
 - The location, building and site plans and a plan of operation shall be submitted to and approved by the Plan Commission and County Zoning Agency.
 - 2. No such use shall be permitted on a Litot less than three (3) acres in area.
 - Off-street parking shall be required in accordance with Section 3.12(1)(J) of this Ordinance.
 - No <u>B</u>building shall be closer than fifty (50) feet to the <u>L</u>lot <u>L</u>line of an adjoining <u>L</u>lot in a <u>D</u>district permitting residential use.
 - 5. All provisions of the motel Ordinance of the town shall be complied with.
- (N) Multiple Family Units: In the R-3 Residential District, B-1 Restricted Business District, B-2 Local Business District, AD-10 Agricultural Density District, RRD-5 Rural Residential Density District, A-5 Mini Farm District or in a Planned Unit Development which may be allowed pursuant to Section 3.08(7)(P) of this Ordinance subject to the following:
 - Only aA duplex (2-family residential use) is the only type of multi-family use that may be allowed in the AD-10 Agricultural Density District and the RRD-5 Rural Residential Density District.
 - A duplex (2-family residential use) may be allowed in an A-5 Mini Farm
 District, but only if the duplex is proposed to be made by conversion of a
 farm dwelling that existed at the time of the adoption of this original

Commented [BA31]: Rephrased for clarity.

Ordinance (February 26, 1959).

- The location and building plans, and a Site Plan and Plan of Operation shall be submitted to and approved by the plan commission and zoning agency.
- 4. The minimum Ltot Aarea shall be determined by the number of units to be constructed. The number of units shall be based on a density of one (1) unit for each fifteen thousand (15,000) square feet of land area, exclusive of wetlands Wetlands or 100 Year Floodplain or lands zoned C-1. Where the use will be served by municipal sewerage and water facilities, the density requirements can be reduced to a minimum of ten thousand five hundred (10,500) square feet per unit and nine thousand (9,000) square feet per dwelling unit if both municipal sewer and water service is available. The width of the Ltot shall be increased as the size of the Ltot increases in order to avoid excessively long and narrow lots and shall, however, be no less than one hundred and eighty (180) feet in width. The amount of Gereen Sepace on the property, exclusive of parking areas, driveways, Reoads and other paved or impervious areas, shall be five thousand (5,000) square feet per unit.
- 5. The manner in which the units are to be serviced with sewerage disposal is subject to approval by the State Department of Commerce and the Waukesha County Department of Parks and Laud Use, Environmental Health Division prior to any approval of the proposed conditional use by the plan commission and zoning agency.
- 6. The minimum Ffloor Aerea per unit shall be nine hundred (900) square feet for one bedroom units, one thousand (1,000) square feet for two bedroom units, and one thousand one hundred (1,100) square feet for three bedroom units comply with Section 3.11(1) of this Ordinance.
- The plan commission or zoning agency may require architectural review of the project.
- 8. There shall be at least two (2) off-street parking spaces for each dwelling unit. The location and arrangement of these spaces is subject to the approval of the plan commission and the zoning agency.
- 9. The offset, setback and landscaping requirements are subject to approval of the plan commission and the zoning agency. However, the offset, setback and height requirements shall at minimum comply with not the standards of the R-3 Residential District, be reduced to less than twenty (20) feet from any lot line of an adjoining lot in a residential district. The road setback minimum shall be fifty (50) feet. The maximum height shall not exceed thirty five (35) feet. Additional height may be permitted if the offset and setback requirements are increased by one (1) foot for each additional one (1) foot in height beyond thirty-five (35) feet.
- (O) <u>Outdoor theater</u>: In local and general business and industrial districts subject to the following:
 - The location, building and site plans and a plan of operation shall be submitted to and approved by the Plan Commission and County Zoning

 $\begin{tabular}{ll} \textbf{Commented [BA32]:} Consolidate multiple tiers of density relief for ease of regulation. \end{tabular}$

Commented [BA33]: Removed specific floor area requirements and refer reader to general minimum floor area section of ordinance. The minimum floor area requirements of the general section are modified to allow smaller units.

Commented [BA34]: Simplified regulation by referring reader to R-3 Residential District standards.

Agency.

- 2. No portion of the theater area shall be closer than two hundred (200) feet to the Bbase Seetback Line or closer than two hundred (200) feet to the Liot Line of an adjoining Liot in a Delistrict permitting residential use.
- A planting screen at least forty (40) feet in width and at least six (6) feet high shall be provided along any Liot Line abutting a Delistrict permitting residential use.
- 4. Additional highway width sufficient to provide for the safe control of traffic at the theater entrance shall be dedicated and the necessary highway improvements constructed to provide for a divided roadway, with adequate reservoir area in the center strip to shelter cars entering the theater.
- (P) Planned Unit Development (P-U-D-): Due to increased urbanization and the associated greater demands for Oppen Space and the need to create a more desired and creative living environment than would result through the strict application of the standard zoning requirements, it is herein provided that there be flexibility in the regulations governing the development of land. This provision is intended to encourage Pplanned Umit Odevelopment in directions which will recognize both the changes in design and technology in the building industry and the new demands in the housing market. It is intended that these provisions create imaginative and interesting communities with substantial open area owned in common or dedicated to the public and for the enjoyment of the residents, and will encourage a more efficient and desirable use of the land and Open Space areas thereby resulting in more variety of the physical development of the County.

An overall development plan showing how the above objectives are to be achieved must be submitted to the Plan Commission and the County Zoning Agency for review and approval. This use is permitted in any Delistrict except A-B, FLP, FLC, A-T, A-B, AD-10 and RRD-5 Districts except that no portions of any building lots or Setructures shall be allowed in the C-1 or HG Districts, subject to the following:

- Lot size, Lot Width, height, offsetOffset, Road setbackSetback, Wetland Setback, open space, floor area ratioBuilding Footprint, minimum Floor Area, building size and building location requirements may be modified according to the following conditions:
 - That all sanitary provisions are approved by the Waukesha County Department of Parks and Land Use, Environmental Health Division.
 - b. That the proposed development is in conformity with the County and Town-town comprehensive plans or County Land Use Plan and is not contrary to the general welfare or economic balance of the community, and that the benefits and amenities of the resultant development justifies the variation from the normal requirements of the Delistrict.
 - Wetland Setbacks can only be reduced if wetland mitigation is provided that offsets the impacts of the reduced setback. Wetland

Commented [BA35]: Added wetland setback relief and minimum floor area to list of regulations that can be flexed via PUD. Replaced floor area ratio with building footprint.

mitigation requirements shall be established by the County Zoning Agency.

ed. That all other requirements of the Pelanned Uunit Deevelopment are met as set forth in this Section.

2. <u>Residential Planned Unit Development:</u>

a. The following table may be utilized to compute the maximum dwelling unit density requirements of the P-U-D-, except that areas which are Primary or Secondary Environmental Corridors are also subject to (b) below.

A-1	120,000 sq. ft. (2.75 acres) per dwelling unit
A-2	120,000 sq. ft. (2.75 acres) per dwelling unit
A-3	80,000 sq. ft. (1.84 acres) per dwelling unit
A-5	200,000 sq. ft. (4.59 acres) per dwelling unit
Environmental Corridors	5 acres per dwelling unit *
R-1a	39,000 sq. ft. (0.89 acres) per dwelling unit
R-1	39,000 sq. ft. (0.89 acres) per dwelling unit
R-2	25,000 sq. ft. (0.57 acres) per dwelling unit
R-3	15,000 sq. ft. (0.34 acres) per dwelling unit**

- * Calculations for Environmental Corridors shall occur as established in (b) below.
- ** The density may be increased by forty percent (40%) to nine thousand (9,000) square feet per dDwelling unit if municipal sewer is provided.
 - b. If all of the Primary and Secondary Environmental Corridor or Environmental Corridor zoned lands are preserved in their entirety within the Ppublic Oppen Space or Common Oppen Space and preserved in their natural state, the density of one unit per five (5) acres may be added to the maximum number of dwelling units derived from utilizing the table above.
 - c. Lands currently zoned C-1 may not be used in formulating the density of the project. When lands border a lake or other public body of water, Ppyramiding as defined herein, may be allowed if the minimum water frontage at the high water mark is one hundred (100) feet for the first dwelling unit and an additional twenty-five (25) feet for each additional dwelling unit thereafter. No more dwelling units may have access to the water body than would result from the application of this provision irrespective of the overall size of the development parcel.
 - d. Public \underline{O} open \underline{S} space or \underline{C} common \underline{O} open \underline{S} space shall be of a size

Effective 05-xx-2016

44

Commented [BA36]: Added wetland setback relief mitigation requirements.

Formatted Table

Commented [BA37]: Matched shoreland ordinance densities.

and shape to provide an integrated system of Oopen Spaces to the greatest extent possible and to narrow bands or corridors, but shall be larger blocks or wide corridors of land, usually not less than one (1) acre in area. Corridors linking large blocks of Ppublic Oppen Sepace or Ceommon Oopen Sepace shall be not less than fifty (50) feet in width to provide adequate buffers from adjacent residential lots. The size, shape and location of said Ppublic Oopen Space or Ceommon Oepen Sepace shall be subject to review and approval of the Plan Commission and Zoning Administrator in order to qualify the project for consideration as a P-U-D- Public Oopen Sopace or Ceommon Oopen Sepace shall be a minimum of thirty percent (30%) of the entire development, while no more than ten percent (10%) of the entire acreage of the development included in the required thirty percent (30%) Oopen Sspace can be Conservancy zoned land. In any development, no more than $\underline{\text{five percent }(5\%)}$ of the Ppublic Oopen Sepace may be used for Ppublic Bbuildings, such as schools, fire stations, municipal buildings, etc.

- e. In Poublic Oopen Sepace or Common Oopen Sepace containing Eenvironmentally Seignificant Aereas, a maximum of two percent (2%) of the Eenvironmentally Seignificant Aereas may be used for limited construction of recreational related Setructures and recreational trails.
- f. Public Oppen Sepace or Common Oppen Sepace shall contain at least ninety percent (90%) Gereen Sepace. Such Pepublic Oppen Sepace or Common Oppen Sepace shall not be part of individual residential building lots and all but five percent (5%) of the Oppen Sepace shall be free of Setructures and Impervious Seurface. The Zoning Administrator and the Plan Commission may increase as a Sepecial Eexception the maximum requirement in conformance with the overall intent of these provisions while also protecting the public's interest.
- g. Adequate guarantee shall be provided for permanent retention of the Open Sepace resulting from these regulations, either by private reservation for use of the residents within the development or others as may be specifically provided for, i.e.: farmers use of Open Sepace, dedication to a public entity or development of a private recreational facility open to the general public in perpetuity for a fee, subject to Plan Commission and Zoning Agency approval. There shall not be any clear cutting or clearing of vegetation other than dead, diseased, or dying vegetation or removal of invasive species on any lands being so preserved in Ppublic Open Sepace or Ceommon Open Sepace which are considered Primary or Secondary Environmental Corridor or Isolated Natural Resource Areas, as depicted on the Waukesha County Comprehensive Development Plan, except as provided in (e) for limited trail or recreational related development.
- h. Perpetual care and maintenance of Ppublic Oppen Space or Common Oppen Space shall be provided for by an agreement

45

recorded with the Waukesha County Register of Deeds. Said agreement shall include an operation plan, which shall preserve the natural qualities of the environmentally significant lands. The agreement shall be submitted to and approved by the Plan Commission and the Zoning Administrator and may be subject to review by the Waukesha County Naturalist if required by the Plan Commission and/or the Zoning Administrator and this condition is not satisfied unless all such appropriate approvals are granted.

- Ownership and tax liability of the Oppen Sepace areas shall be established in a manner acceptable to the Plan Commission and Zoning Administrator and made part of the conditions of approval.
- 3. Commercial P-U-D-: The use of a Commercial P-U-D- may be authorized only where the underlying zoning is mapped in one or more of the business districts on the parcel or a portion thereof. If only a portion is zoned for business, the commercial P-U-D- may only be used for the same percentage of the site that would result from the normal application of the Business Delistrict requirements. The location of the proposed business uses can however, be flexed on the site so long as no more area is devoted to such use than is permitted in the underlying Delistrict. The attendant parking areas and service facilities for the commercial areas shall be included in the areas allocated to such non-residential uses.
 - a. The proposed P-U-D- shall be served by adequate off-street parking, loading and service facilities.
 - b. The $P_TU_TD_T$ shall not create an adverse effect upon the general traffic pattern or adjoining property values.
 - Architecture, landscaping, lighting and general site development shall be compatible with the surrounding neighborhood.
 - The aforementioned requirements shall be certified by the Town and County as having been fully met.
- 4. Mixed P-U-D-: A mixed P-U-D- shall consider allowing a mixture of business, residential or other uses as the underlying zoning would allow. The percentage of area in the project shall be the same as would result from the application or the strict adherence of the normal district regulations. The location of the uses can however, be flexed on the site so long as no more area is devoted to the various uses than would be permitted in the underlying zoning district. The attendant parking and service facilities for the non-residential part of the project shall be included in the area allocated to such non-residential uses.
 - The proposed mixture of commercial, industrial, residential, and other uses shall produce a unified composite which is comparable both within itself and with the surrounding neighborhood.

- b. The mixed uses shall conform to the general requirements applicable to each of them as here-in-before set forth.
- c. The maximum allowable dwelling unit density shall be computed using only the residential area portion of the total P-U-D- area. If residential use and non-residential use occur in the same proposed B-building, that percentage of the commercial use of the B-building shall be deducted from said building lot and only the remaining area shall be used in the density computation for the remaining residential units.
- 5. After all conditions of a planned unit development project are certified by the town and county as being completed, the conditional use status of such completed development shall be changed to a Ppermitted Utiese in the Delistrict in which it is located.
- 6. Example Computing Maximum Dwelling Unit Density in a Planned Unit Development: A developer wishes to divide one hundred (100) acres of land into a Pelanned Unit Deevelopment. Ten (10) of these acres are zoned C-1 Conservancy. The rest is zoned R-1 Residential. The preliminary plan shows an additional ten (10) acres proposed for commercial uses but not zoned for business.

The following computations demonstrate the method of determining how many residential units will be allowed in the project.

a) .	Gross acreage	100 acres
b) .	Less ten (10) acres zoned C-1	- 10 acres 90 acres
c) .	Less ten (10) acres zoned for B-2 Business use	- 10 acres 80 acres
d) .	Total residential acreage in sq. ft.	3,484,800 square feet (80 acres x 43,560)
e) .	Divide by square feet per dwelling unit requirement for R-1 Residential Delistric 3,484,800 divided by 41,000)	ets 85 units

- f). The 10 acres zoned for commercial use cannot be included in the PUD as it is not zoned for business uses and must be rezoned to be considered.
- (Q) Private Clubs and Resorts: Without limitation because of enumeration, this category includes resorts and Pprivate Celubs such as indoor/outdoor recreational and athletic facilities (i.e., tennis, racquet ball, volleyball, basketball, driving ranges, baseball batting cages, tanning booths, campgrounds, golf courses, beaches, yacht clubs, Bboarding Setables, etc.) are permitted in any Delistrict except that Bbuildings and Setructures are not permitted within the C-1, HG, or FLC Districts. Such uses may only be allowed in the FLP or FLC Districts if incidental to and compatible with the

continued long term Aagricultural \underline{U} as of the lands and in conformance with Section 6.1. Such uses shall be subject to the following:

- The location, building and site plans, and plan of operation shall be submitted to and approved by the Plan Commission and the County Zoning Agency.
- No such use shall be permitted on a Ltot less than three (3) acres in area
 except in a restricted business or less restrictive Delistrict.
- 3. No Bbuilding, other than one used only for residence residential purposes, shall be closer than fifty (50) feet to the Llot Lline of an adjoining Llot in a Delistrict permitting residential use.
- Off-street parking shall be provided as required by the plan commission adequate to meet the particular needs of the proposed use.
- No such <u>P</u>permitted <u>U</u>use shall include the operation of a commercial facility such as a bar, <u>R</u>restaurant or <u>A</u>urcade except as may be specifically authorized in the grant of permit.
- (R) Public and Ssemi-public Bbuildings and uses: In any Delistrict, except the C-1 Conservancy District. Such uses within the FLP and FLC shall comply with all terms of Section6.1. No Sstructures are permitted within the HG or FLC Districts. Such uses shall be subject to the following:
 - 1. The location, building and site plans and plan of operation shall be submitted to and approved by the plan commission.
 - Such use shall conform to the setback, height, and double the offset requirements of the <u>Delistrict</u> in which it is located.
 - The height limitation may be extended to a maximum of fifty (50) feet provided the minimum required setbacks and Opffsets shall be increased two (2) feet for every additional foot of height in excess of the permitted maximum of that Ophistrict.
- (S) Quarrying as defined in this Ordinance: In any Delistrict, except the EC Environmental Corridor, AD-10, RRD-5, A-2, A-3, A-4, R-1, R-2, R-3, P-I, B-1, B-2, B-3, B-4, BP or M-1. Existing quarries may continue to operate in the C-1, HG and FLC Districts. New quarries are prohibited in the C-1, HG and FLC Districts. Quarries within the FLP or FLC Districts shall comply with all terms of Section 6.1. All quarries are subject to the following:
 - 1. Procedure for application:
 - a. Permit: No quarrying operation shall take place in any Delistrict until a conditional use permit has been received and approved by the plan commission, town board and county zoning agency.
 Except in a quarrying or general industrial district, such permit shall be for an initial period as is deemed appropriate to the specific situation but not to exceed three (3) years provided application

therefore shall be made at least sixty (60) and no more than one hundred twenty (120) days before expiration of the original permit. Application after such date shall be treated as an original application.

- Application: Application for a conditional use permit shall be made
 on forms supplied by the Waukesha County Park and Planning
 Commission and shall be accompanied by a fee as may be
 established and periodically modified under Section 22.02(5) of this
 Ordinance. Such fee shall be paid by cash, check or money order to
 the Waukesha County Park and Planning Commission.
 - i. A full and adequate description of all phases of the contemplated operation and the specific mention of type of machinery and equipment which will be or might be necessary to carry on the operation. Where the operation is to include the washing of sand and gravel, the estimated daily quantity of water required, its source and its disposition shall be made part of the description.
 - ii. A legal description of the proposed site with a map showing its location with indications of private access roads, existing or proposed, and of public Hhighways adjacent to the site which will be affected by the operation.
 - iii. A topographic map of the area at a minimum contour interval of five (5) feet extending beyond the site to the nearest public street or Haighway or to a minimum distance of three hundred (300) feet on all sides.
 - iv. A restoration plan as required by Section 3.08(7)(S) 3(e).

2. <u>Procedure for action on applications:</u>

49

- Referral to plan commission: The application and all data and information pertaining thereto shall be referred to the plan commission for public hearing and report and recommendation back to the town board within thirty (30) days after the public hearing.
- b. Public hearing: Within thirty (30) days after an application has been filed, a public hearing shall be held at which all interested parties may be heard. In addition to the normal posting and publishing, notices also shall be sent through the mail or otherwise placed in the hands of all land owners within a half-mile radius of the approximate center of the proposed quarrying operation. These notices shall be mailed or delivered at least ten (10) days prior to the date of hearing. Substantial compliance with the notice requirements of this Section shall be deemed sufficient. No hearing shall be required precedent to issuing a permit in a quarrying district.
- c. Action by town board: The town board shall, within ten (10) days

after receipt of the recommendation of the plan commission, take action to approve or disapprove the application for the proposed quarrying operation and shall be guided by consideration of the public health, safety and welfare, and shall give particular consideration to the following factors in making their decision:

- The effect of the proposed operation on existing Reads and traffic movement in terms of adequacy, safety, and efficiency.
- The effect of the proposed operation on drainage and water supply.
- iii. The possibility of soil erosion as a result of the proposed operation.
- iv. The degree and effect of dust and noise as a result of the proposed operation.
- v. The practical possibility of restoration of the site.
- vi. The effect of the proposed operation on the natural beauty, character, tax base, land value, and land uses in the area.
- The most suitable land use for the area with particular consideration for future residential value.
- d. <u>Approval by zoning agency</u>: The determination of the town board shall be immediately transmitted to the county zoning agency which shall within thirty (30) days approve or disapprove of the determination.
- Additional conditions: Any conditions accessory to the granting of a permit shall be in writing and copies made a part of the permit and a part of the records of the town and of the county zoning agency.
- f. Renewals: The procedure as designated in Sections (a), (b), (c), (d) and (e) above shall apply to applications for renewal of a permit. Determination in regard to renewal shall be based particularly on an evaluation of the effect of the continuance of the use with relation to changing conditions in the area. Where renewal is not granted, the reasons for refusal shall be presented to the Aepplicant in writing and made a part of the records of the town and of the county zoning agency.

3. Requirements:

- a. <u>General requirements</u>:
 - 4i. No part of the quarrying operation shall be permitted closer than one thousand (1,000) feet, nor shall any accessory

access road, parking area, or office building be permitted closer than five hundred (500) feet to a $\underline{\mathbb{D}}$ -district zoned rural home or residential at the time of the grant of permit except with the written consent of the owners of all rural home or residentially zoned properties within one thousand (1,000) feet, except in a quarrying or general industrial district, but in no case shall such operation be permitted closer than two hundred (200) feet to a residential district.

ii. No quarrying operation shall be permitted except in a quarrying, limited industrial or general industrial district, if thirty (30) or more families reside within a band one-half mile wide around the perimeter of the proposed operation.

b. <u>Setback requirements:</u>

No part of the quarrying operation other than access roads shall be located closer than two hundred (200) feet, nor shall any accessory parking area, stock pile, or office building be located closer than one hundred (100) feet to the Bbase Seetback Lline along any Setreet or Hhighway.

c. Offset requirements:

No part of the quarrying operation shall be permitted closer than two hundred (200) feet, nor shall any accessory access road, parking area, or office building be permitted closer than fifty (50) feet to any property line except with the written consent of the owner of the adjoining property, or except where said line is abutting a quarrying, limited industrial, or general industrial district, or abutting an existing quarrying operation, but in no case shall such operation be closer than twenty (20) feet to any property line except by agreement between abutting quarrying operations, or be in conflict with the provisions of Section 3.04(5) relating to preservation of topography.

d. Operational requirements:

- i. Fencing or other suitable barrier shall be erected and maintained around the site or around portions of the site where in the determination of the town board such fencing or barrier is necessary for the protection of the public, and shall be of a type approved by the town board.
- All machinery and equipment used in the quarrying operation shall be constructed, maintained and operated in such a manner as to minimize dust, noise and vibration.
 Access and haulage roads on the site shall be maintained in a dust-free condition by surfacing or treatment as directed by the town engineer.

- iii. The crushing, washing, refining, or other processing other than the initial removal of material, may be permitted as an Aeccessory Uese only as specifically authorized under the terms of the grant of permit, or as otherwise provided in a quarrying or industrial district.
- iv. In stone quarries the production or manufacturing of veneer stone, sills, lintels, cut flagstone, hearthstones, paving stone and similar architectural or structural stone and the storing or stock-piling of such products on the site shall be considered a permissible part of the operation, provided such production does not require the use of crushing or other heavy machinery except as may be otherwise specifically authorized under the terms of the grant of permit, or as otherwise provided in a quarrying or industrial district.
- v. The manufacture of concrete building blocks or other similar blocks, the production or manufacture of lime products, the production of ready-mixed concrete and any similar production or manufacturing processes which might be related to the quarrying operation shall not be permitted except as otherwise provided in a quarrying or industrial district.
- vi. The washing of sand and gravel shall be prohibited in any operation where the source of water is of doubtful capacity or where the quantity of water required will, in the opinion of the town engineer, seriously affect the water supply for other uses in the area.
- vii. The planting of trees and shrubs and other appropriate landscaping shall be provided where deemed necessary by the plan commission to screen the operation so far as practical from normal view, to enhance the general appearance from the public right-of-way, and generally to minimize the damaging effect of the operation on the beauty and character of the surrounding country-side. Such planting shall be started as soon as practicable, but no later than one (1) year after quarrying operations have begun, and shall be done according to the recommendations of the Waukesha County Park and Planning Commission.
- viii. Except in a quarrying or general industrial district, quarrying operations shall not begin before the hour of 7:00 a.m. and shall not continue after the hour of 6:00 p.m. and no operation shall take place on Sundays or legal holidays. During periods of national or unusual emergency, time and hours of operation may be altered at the discretion of the town board and through the issuance of a special permit which shall be renewable at thirty-day intervals.

e. <u>Restorative Requirements:</u>

- i. In order to insure that the area of quarrying operation shall be restored to a condition of practical usefulness and reasonable physical attractiveness, the owner or operator shall, prior to the issuance of a permit, submit to the town board a plan for such restoration in the form of the following:
 - (a) An agreement with the town whereby the <u>A</u>applicant contracts to restore the premises to a condition and within a time satisfactory to the town.
 - (b) A physical restoration plan showing the contours of the restoration, plantings and other special features of restoration, the method by which such restoration is to be accomplished and documentation that the plan complies with the Waukesha County Code of Ordinances – Nonmetallic Municipal Mining Restoration Ordinance or other ordinances adopted pursuant to Section 295.14, Wisconsin Statutes and Section NR 135.32(2), Wisconsin Administrative Code.
 - (c) A bond, written by a licensed survey company, a certified check, or other financial guarantee satisfactory to the town, in an amount sufficient in the opinion of the town engineer to secure the performance of the restoration agreement.
 - (d) Such agreement and financial guarantee shall be in a form approved by the town attorney.
- ii. In the event of the Aepplicant's failure to fulfill this agreement, such bond, check, or other financial guarantee shall be deemed forfeit for the purpose of enabling the town to perform the restoration.
- iii. Restoration shall proceed as soon as practicable and at the order and direction of the town engineer. However, the owner or operator may, at his option, submit a plan for progressive restoration as the quarrying operation is being carried on. The required bond in such case may cover progressive stages of the restoration for periods of not less than two (2) years.
- At any stage during the restoration the plan may be modified by mutual agreement between the town and the owner or operator.
- v. Where there is any backfilling, the material used or the

method of fill shall not be such as to create a health hazard nor which would be objectionable because of odor, combustibility, or unsightliness. In any case the finished grade of the restored area except for rock faces, out-croppings, water bodies, or areas of proposed building or paving construction, shall be of sufficient depth of earth to support plant growth.

- vi. Within one (1) year after the cessation of the operation, all
 Ttemporary Structures (excepting fences), equipment,
 stock piles, rubble heaps, or other debris shall be removed
 or backfilled into the excavation so as to leave the premises
 in a neat and orderly condition.
- vii. In any restoration procedure which takes place in <u>S</u>sand or <u>Geravel Ppits</u> or on other sites where the material is of a loose or friable nature, no slope shall be left which is steeper than a ratio of one and one-half (1 ½) horizontal to one (1) vertical. In no case shall any slope exceed the normal angle of slippage of the material involved.

f. Exceptions:

- i. The provisions of this Section 3.08(7)(S) shall not apply to the removal of sod.
- ii. When the operation is limited to the removal of topsoil, the plan commission may, consistent with the intent of these regulations, modify any or all of the provisions of this Section 3.08(7)(S) provided, however, that in no case shall such operation be permitted closer than ten (10) feet from any property line, or to a depth in excess of eighteen (18) inches or so as to adversely affect the drainage of the area.
- iii. The provisions of this Section 3.08(7)(S) shall not apply to an operation which is incident to legitimate use of the premises, provided, however, where such operation involves the commercial disposal of the material removed, the approval of the plan commission shall be required and such operation shall be limited to a maximum period of six (6) months.
- iv. In a quarrying or general industrial district, the plan commission may, consistent with the intent of these regulations, modify the provisions relative to permitted hours of operation; and where the character of terrain, surrounding development, or other special conditions would justify, such modification may permit a reduction in the required setback or Offset; provided, however, that in no case shall the setback be less than one hundred (100) feet, or the Offset be less than one hundred (100) feet for quarrying operations or twenty (20) feet for any accessory

access road, parking area, or office building except as may be otherwise provided by Section 3.08(7)(S)3(c).

4. <u>Application to existing operations:</u>

- a. Permit: Within sixty (60) days after the adoption of this Ordinance all existing quarrying operations shall be required to register with the town clerk submitting pertinent data relative to the present operation, including the boundaries of the actual operation and of the ownership. A conditional use permit shall be granted to such existing operation subject to compliance with the operational requirements, Section 3.08(7)(S) 3.(d). of this Ordinance where they can reasonably be applied under existing circumstances.
- b. <u>Plans for restoration</u>: There shall be required within one (1) year after adoption of this Ordinance, the submission of a plan for restoration of the site of any existing quarrying operation as provided by Section 3.08(7)(S) 3.(e). The plan for restoration in such case shall not, however, impose requirements which are economically or engineeringly unreasonable with respect to conditions resulting from operations prior to enactment of this Ordinance.
- c. <u>Renewal permit</u>: Within three (3) years after the date of this Ordinance any such existing operation shall be required to make application for a renewal permit the same as for reapplication in the case of a new operation under this Ordinance, except in a quarrying or general industrial district.
- (T) Refuse Delisposal Seites, public and commercial: In any Delistrict, other than R-1,
 R-2, R-3 residential, C-1, HG FLP and FLC Districts subject to the following:
 - The location, Beuilding, site plan and plan of restoration shall be submitted
 to and approved by the Plan Commission, the Zoning Agency, the
 Waukesha County Department of Parks and Land Use by the
 Environmental Health Division and Land Resources Division, and the State
 Department of Natural Resources pursuant to the State solid waste disposal
 standards.
 - Such plans shall be approved or disapproved upon consideration of the
 effects on topography, drainage, water supply, soil conditions, <u>R</u>+oads and
 traffic, and present and ultimate land development and use.
 - 3. Only sanitary landfill refuse disposal methods, subject to the standards established and enforced by the Waukesha County Department of Parks and Land Use, Environmental Health Division, the Department of Natural Resources and the State Board of Health shall be used. Permission to burn refuse before covering must be specifically included in the zoning permit and may be separately withdrawn at any time the smoke or smell constitutes a health or safety hazard. All garbage must be covered to the specified depth prior to the end of the day during which disposal takes place.

- 4. A responsible person shall be in attendance during the hours of operation, which hours shall be subject to the approval of the town board. No refuse disposal shall take place except during the specified hours of operation, and with the attendant present.
 - a. A non-flammable fence, with a gate which can be locked, must be erected to encompass the disposal site to prevent refuse disposal and scavenging during non-operating hours, and the attendant shall retain the key.
 - Such fence, and additional auxiliary portable fence, such as snow fence, that will minimize the nuisance of blowing paper, shall be approved by the Town Board.

5. Requirements:

- a. <u>Setback</u>: No refuse disposal shall take place, nor shall <u>S</u>structures pertinent thereto be constructed closer than two hundred (200) feet to the <u>B</u>base <u>S</u>setback <u>L</u>line.
- b. Offset: No refuse disposal shall take place closer than two hundred (200) feet to any Llot Lline, nor shall refuse disposal take place closer than five hundred (500) feet to any existing dwelling or the site of a dwelling for which a building permit has been issued prior to the application date for the conditional use permit; nor closer than five hundred (500) feet to a Delistrict zoned R-1, R-1a, R-2 or R-3 Residential, at the time of the grant of the permit. No refuse disposal shall take place closer than five hundred (500) feet to a permanent business or industrial structure without the written consent of the owner of that adjacent property and the written approval of the Waukesha County Department of Parks and Land Use, Environmental Health Division and the State Department of Natural Resources.
- c. <u>Additional Requirements</u>: Restrictions as to the types and sources of refuse, if needed, shall be the responsibility of the Town Board under the advisement of the Waukesha County Department of Parks and Land Use, Environmental Health Division. A planting plan as approved by the Zoning Agency shall be included in the plan of operation.
- 6. All existing refuse disposal operations shall be registered by the operator within sixty (60) days after the adoption of this Ordinance with the town clerk, submitting pertinent data relative to present operation, including the boundaries of the actual operation and ownership. A permit shall be granted to such existing operation subject to compliance with a plan of operation satisfactory to the approving bodies. A plan of restoration shall be submitted to the town by the operator within one (1) year of the adoption of this Ordinance, together with a surety bond to insure such restoration. Such operation and restoration plans shall not impose requirements which are economically or engineeringly unreasonable with respect to conditions

resulting from operations prior to enactment of this Ordinance.

- (U) Restaurants, Supper Clubs, Resorts, Taverns and Similar Uses: In B-2 and B-3
 Business Delistricts such uses shall be considered Permitted Ueses by right. In all other Delistricts, except the C-1, A-T, FLP, FLC, HG, A-B, A-5, P-1 and EC
 Environmental Corridor Delistricts, the above uses shall be considered conditional uses, subject to the following:
 - The location and building plans and a Site Plan and Plan of Operation shall be submitted to and approved by the plan commission and the zoning agency.
 - 2. The minimum Llot Aerea shall be two (2) acres with at least two hundred (200) feet in minimum average width.
 - 3. Off-street parking shall be provided within two hundred (200) feet of the B-building in which such use is occurring, but Q-offset twenty (20) feet from any L-bot L-line of an adjacent property zoned agricultural and any residential zoning district. The amount of space required shall be in accordance with the requirements contained in Section 3.12(1)(C).
 - A Pplanting Secreen of at least six (6) feet in initial height shall be provided between any abutting residential district and the proposed use. Additional Pplanting Secreens may be requested by the plan commission or county zoning agency.
 - The proposed Bauilding shall be Oeffset at least fifty (50) feet from any abutting residential district and one hundred (100) feet from any navigable body of water.
- (V) <u>Salvage yards</u>: Sites used for the storage or sale of salvageable materials, or for the purpose of salvage, wrecking, dismantling, or demolition of salvageable materials, in M-2 <u>I</u>*industrial <u>D</u>districts, subject to the following:
 - The location, building and site plans and plan of operation are submitted to and approved by the plan commission and the county zoning agency.
 - All requirements of the Wisconsin Administrative Code applicable to salvage yards shall be complied with.
- (W) Commercial Truck Parking: Such uses are uses permitted by right in B-3 Industrial and Quarrying Districts. In all residential, agricultural, FLP, FLC, HG, B-1 and B-2 business Delistricts, except the EC Environmental Corridor District and the C-1 Conservancy District, subject to the following:
 - The parking and the storage of commercial type vehicles, dump trucks, school buses, construction vehicles, semi trailers and tractors may be allowed as long as the vehicle is owned or leased and operated by the owner or occupant of the premises. No such use shall be allowed on any parcel, except as may front directly upon and have access to an Aerterial or Ceollector Setreet as defined herein.

- 2. No more than one (1) such vehicle shall be allowed to be parked or stored on the occupant's property and no more than two (2) additional construction vehicles (backhoes, front end loaders, grading equipment, etc.) shall be allowed. Such vehicles shall be fully operative and in active use. Where considered appropriate, two (2) trailers may be allowed, but in no case may there be more than one (1) semi tractor or "cab" unit.
- 3. No such vehicle shall be allowed to be parked or stored closer than fifty (50) feet to any adjacent Llot Lline, and not closer than one hundred (100) feet from the Bbase Seetback Lline. In the case of refrigerator trucks, the refrigeration unit may not be operated in the open if said truck is parked closer than five hundred (500) feet to the nearest neighboring residential property line.
- 4. In determining whether or not the proposed Conditional Use Permit should be issued, a determination of compatibility with adjacent land uses shall be made to the Town Plan Commission and County Zoning Agency in issuing this Conditional Use Permit. If it is determined that it would in any way be incompatible and represents an adverse effect or nuisance to adjacent land uses, the Conditional Use Permit shall not be issued.
- 5. The Conditional Use Permit shall be reviewed every two (2) years by the Town Plan Commission in order to determine conformance with the terms of the permit, and if it is determined that the use is no longer compatible with adjacent land uses as they develop in the vicinity, the Conditional Use Permit may be revoked in accordance with the revocation procedures contained in this Ordinance.
- (X) Other uses or situations not specifically provided for in this conditional use Section and which may be determined to be acceptable under the provisions of Section 3.07(3) and in the judgment of the plan commission and county zoning agency meet the intent of a conditional use as set forth in Section 3.08(1). Any such uses within the FLP or FLC Districts shall comply with all terms of Section 6.1.
- (Y) Bed and Breakfast Facility: In all Delistricts, except the HG High Groundwater, C-1 Conservancy, FLP Farmland Preservation and FLC Farmland Conservancy Districts. The intent is to provide travelers with temporary accommodations and breakfast, for a fee, on a daily or weekly room rental basis, as an Aeccessory Uese in any existing Setructure designed for and occupied as a single family residence in any Delistrict permitting single family residences subject to the following:
 - The location, building and site plans, and plan of operation shall be submitted to and approved by the Plan Commission and the County Zoning Agency.
 - 2. Minimal outward modification of the Setructure or grounds may be made only if such changes are compatible with the character of the area or neighborhood and the intent of the zoning district in which it is located. For Beuildings with significant architectural or historic value, the architectural integrity and arrangement of existing interior spaces must be maintained and the number of guest rooms shall not be increased except as may be required to meet health, safety, and sanitation requirements.

- 3. Off-street parking shall be provided at the rate of one (l) parking space for each room rented. The front yard shall not be for off-street parking for temporary guests unless the parking area is screened from view with natural plant material, and found to be compatible with the neighborhood.
- 4. The number of rooms shall be limited to five (5) sleep-in rooms or less, excluding those used by the occupants of the facility, and no room may contain more than two (2) beds. There must be at least five hundred (500) square feet of gross interior Ffloor Afrea for each sleeping room. Those facilities providing service to a greater number of guests are not considered "license exempt" under state law and must comply with state Hhotel/Mmotel/Restaurant licensing procedures administered by the County or State Health Department. The issuance of such licenses shall not be considered as conferring non-conforming commercial status to the use which would either allow alteration of the facility or otherwise compel rezoning of the property for commercial use beyond the scope of this Section.
- 5. One (1) on-premise <u>Seign</u> may be allowed provided that such <u>Seign</u> is compatible with the residential use of the site and its surrounding areas and is not more than fifteen (15) square feet in size with letter sizes not less than five (5) inches in height.
- All necessary State and County permits, certifications, or requirements shall be obtained as a condition of approval of a bed and breakfast service.
- Room rentals to families or individuals shall not exceed fourteen (14) consecutive days.
- The Bbed and Bbreakfast Ffacility must be accessory to and contained within the single family dwelling occupied by the owner (e.g., not a manager) of said premises.
- The only meal to be provided to travelers/guests shall be breakfast and it shall only be served to guests taking lodging in the facility.
- 10. The Waukesha County Department of Parks and Land Use, Division of Environmental Health, shall examine both the water system and the sewage disposal system, and shall conduct a general health and safety inspection of the proposed facility. The Department may impose any conditions required to ensure that all necessary health and safety standards have been met. The Aapplicant shall not: initiate any construction activity and other improvements related to the Bbed and Bbreakfast Ffacility; or begin operation of the facility until receiving a determination, in writing, by the Department that the necessary inspections have been completed and any deficiencies have been corrected. The proprietor shall have a water quality evaluation conducted by a recognized water testing laboratory on an annual basis following the certification of adequacy by the Department. The results of that test shall be submitted to the Department with a copy to the Zoning Administrator. All requirements must be incorporated into the terms of the conditional use permit.

- (Z) <u>In-Law Unit</u>: In any Residential, Agricultural, B-1 or B-2 zoning district, except FLC, subject to the following. Such uses in the FLP District shall comply with all density provisions of Section 6.1, in addition to the below requirements:
 - The location, building plan, site plan and plan of operation shall be submitted to and approved by the Plan Commission and the County Zoning Agency.
 - The Waukesha County Department of Parks and Land Use, Division of Environmental Health, shall certify that the septic system will accommodate the proposed use and is in accordance with COMM 83, County and State Sanitary Codes.
 - 3. Maximum living area of the Iɨn-law Uɨnit shall not exceed eight hundred (800) square feet and shall contain no more than two (2) bedrooms. There shall be an additional parking space for the Iɨn-law Uɨnit. There shall be no more than one (1) Iɨn-law Uɨnit per single family lot.
 - 4. Architecture of the Residence shall be compatible with the adjacent residential neighborhood and shall appear to be a single family residence. All other appropriate zoning district requirements for the principle living unit shall be complied with. A common entrance to the Residence and In-law Uenit should be designed into the Setructure so that a separate front entrance, off of the common entrance, is available and the Setructure does not appear to be a duplex.
 - The Plan Commission and the County Zoning Agency shall determine if it
 is appropriate to have an interior door between the <u>I</u>in-law <u>U</u>init and the
 principal Rresidence.
 - 6. A Deed Restriction shall be filed in the Waukesha County Register of Deeds office and a copy of the recorded document presented to the Building Inspector prior to issuance of the Building Permit. This Deed Restriction shall state that the Lin-law Uunit is to be occupied by persons related by blood or marriage to the Ffamily occupying the principal unit and that the Conditional Use is not transferable without formal approval of the County Zoning Agency without necessity of a public hearing and that the unit will be used as intended.

 $(Sections\ 3.08(7)(AA),\ (7)(N),\ (7)(S)3(e)(1)(b),\ (7)(S)3(f)(4),\ (7)(U)(1),\ (7)(Y)(10),\ (7)(Z)2\ were\ amended\ by\ Enrolled\ Ordinance\ 159-69,\ effective\ 1-17-05.)$

(Sections 3.08(7)(H) and (KK) were created by Enrolled Ordinance 159-69, effective 1-17-05.)

 $(Sections\ 3.08(7)(E)2,\ 3.08(7)(P)1(a),\ 3.08(7)(P)2,\ 3.08(7)(T)1,\ 3.08(7)(T)3,\ 3.08(7)(T)5(b),\ 3.08(7)(T)5(c)\ and\ 3.08(7)(W)1\ were amended by Enrolled Ordinance\ 161-13,\ effective\ 09/04/06.)$

```
(Section 3.08(3) was amended by Enrolled Ordinance 162-48, effective 10-9-07.) (Section 3.08(7) (B) was amended by Enrolled Ordinance 169-46, effective 09-09-14.) (Section 3.08(7) (KK) was amended by Enrolled Ordinance 169-46, effective 09-09-14.) (Section 3.08(7) (N) was amended by Enrolled Ordinance 167-24, effective 07-24-12.)
```

⁽Section 3.08(7) (P)(2)(a) was amended by Enrolled Ordinance 169-46, effective 09-09-14.)

⁽Section 3.08(7) (P)(2)(b) was amended by Enrolled Ordinance 169-46, effective 09-09-14.)

⁽Section 3.08(7) (P)(2)(g) was amended by Enrolled Ordinance 169-46, effective 09-09-14.)

(Sections 3.08(7)(A), (B), (D), (E), (F), (G), (I), (KK), (P), (Q), (R), (S), (T), (U), (W), (X), (Y) and (Z) were amended by Enrolled Ordinance 170-72, effective 12/31/15.)

3.09 Building location

(1) Road Setbacks:

- (A) Base setback Setback lines Lines, from which building setback shall be measured, are hereby established for all Setreets and Heighways in the county as follows, unless otherwise specified by action of the County Zoning Agency:
 - On all <u>S</u>streets or <u>H</u>highways for which the ultimate width has been established by the Highway Width Ordinance of Waukesha County, the <u>base-Base setback Setback line-Line</u> shall be located at a distance from the center line equal to one-half such established width as designated on the Established Street and Highway Width Map of Waukesha County.
 - On all other streets, which shall be designated as "local streets," the base
 <u>Base setback Setback line Line</u> shall be thirty-three (33) feet from the center
 line of such <u>Setreet</u> or sixty (60) feet from the center point of a cul-de-sac
 unless specifically designated otherwise by action of the County Zoning
 Agency.
 - 3. When a Liot abuts a frontage road, the base_Base_setback_Setback_line_Line shall be located at a distance from the center line equal to one-half the right-of-way width of said frontage road.
 - Such setback lines shall be parallel to and measured at right angles to the centerline of the Setreet or Haighway.
 - 5. There shall be a required setback equal to the offset requirements of the Delistrict in which the property is located, from a private right-of-way providing ingress and egress to the subject land or other lands unless such private right-of-way is considered a mill tax road, in which case the normal road setback requirements contained in this Ordinance shall apply.
- (B) Vision setback lines at the intersections of public streets or Haighways and of a Setreet or Haighway with a railroad, where the grade is not separated, are hereby established as follows:
 - Across each sector between the intersection of a Street or Hhighway with a railroad, a V+ision S+etback line shall be established by a straight line, connecting points on the base Base setback Setback line Line and the railroad right-of-way line, which points are located one hundred twenty (120) feet from the intersection of the base Base setback Setback line Line and the railroad right of-way line.
 - Across each sector between intersecting streets or Hhighways, one (1) or
 more of which has an established width of one hundred (100) feet or more,
 a V-vision Setback line shall be established by a straight line connecting
 two (2) points on the intersecting base-Base setback Setback Lines, which

Effective 05-xx-2016

61

points are located sixty (60) feet distant from the intersection of said base Base setback Setback linesLines.

- 3. Across each sector between any other intersecting streets a <u>V</u>≠ision <u>S</u>setback line shall be established by a straight line connecting two (2) points on the intersecting <u>base Base setback Setback linesLines</u>, which points are located thirty (30) feet distant from the intersection of said <u>base Base setback Setback linesLines</u>.
- (C) No principal Principal or accessory Accessory building Building shall be hereafter erected, altered, horizontally added to, relocated or placed closer to the base Base setback Setback line Line than the Road Setback distance specified by the regulations for the Delistrict in which such building Building is located except as specified here-in-after:
 - 1. Building within Road Setback on one side only: If there is a Beuilding which is non-conforming with respect tohas less than the required Rroad Setback, with a similar use as the proposed Beuilding, located on an adjacent parcel on one side of the proposed building or within two hundred (200) feet of the proposed building, the average of the Rroad Setback of that Beuilding of similar usage and the required minimum Rroad Setback shall apply, provided that the existing Building is on an adjacent Llot, is located within two hundred fifty (250) feet of the proposed Building and is located on the same side of the Rroad.
 - 2. Buildings within Road Setback on both sides. If there are two buildings Buildings which are non-conforming with respect to have less than the required road—Road setbackSetback, with similar uses as the proposed buildingBuilding, located on adjacent parcels on each side of said building or within two hundred (200) feet of the proposed buildings, the average of the road-Road setbacks-Setbacks of those buildings Buildings of similar usage shall apply, provided that the existing Buildings are on adjacent Lots, are located within two hundred fifty (250) feet of the proposed Building and are located on the same side of the Rroad.
 - 3. Addition to an existing Building within Road Setback. In the case of a proposed addition to an existing Building which has less than the required Road Setback, the Road Setback of such existing Building may be used to determine the required Road Setback for the proposed addition, as set forth below:
 - a. If there are no existing Buildings with a similar use as the Building with the proposed addition on either of the adjacent Lots on the same side of the Rroad, the average of the Road Setback of the existing Building and the required Road Setback shall apply to the addition.
 - If there is only one existing Building with a similar use as the
 Building with the proposed addition on an adjacent Lot on the same
 side of the Rroad, the average of the Road Setback of the existing
 Building and the existing Building on the adjacent Lot shall apply
 to the addition.

Commented [BA38]: Modified road setback averaging to allow averaging within 250 feet rather than 200 ft. and limit road setback averaging to same side of road and on adjacent properties to provide consistency with setbacks of shoreland ordinance. Also provides a reference to the nonconforming structure section of ordinance, which provides additional flexibility.

c. If there are existing Buildings with similar uses as the Building with the proposed addition on both adjacent Lots, but one of the adjacent Buildings is located further from the Rroad than the existing Building with the proposed addition, the average of the Road Setback of the existing Building and the Building on the adjacent Lot located closest to the Rroad shall apply to the addition.

In the case of a proposed addition to an existing building which has less than the required road setback, the road setback of such existing building may be used to determine the required road setback for the proposed addition, as set forth above.

- If the above exceptions do not apply and an improvement or addition is proposed to an existing Nonconforming Structure, the provisions of Section 3.17 apply.
- 45. On corner lots Lots of recordRecord, as of the date of adoption of this Ordinance, the effect of the setback regulations shall not reduce the buildable width of such corner lot Lot to less than thirty (30) feet. Where such reduction would result in an area narrower than thirty (30) feet after applying the offset reduction, the Zoning Administrator shall have the authority to modify the setback or offset provision to the extent necessary to minimize the encroachment on both the offset and setback standard while maintaining the thirty (30) feet area required herein.
- 6. No other Setructures of any kind, except necessary highway and traffic signs, Retaining Wwalls, open stairs extending six (6) feet or less from the enclosed portion of the Setructure, open stairs in combination with Setoops and/or Peorches which are unenclosed and provide no more than twenty (20) square feet in area and extend no more than six (6) feet from the enclosed portion of the Setructure, public utility lines, rural mailboxes, and those Setigns permitted in a residential or agricultural district shall be hereafter erected, altered or placed within such base setback area. Monuments and-entrance gates are Setructures which require a zoning permit and shall be located at least ten (10) feet from the Bease Setback Line and shall not restrict safe access and visibility of the intersecting drive and the Reoad and shall be subject to review and approval by the plan commission and the zoning administrator and the applicable municipality having jurisdiction over the Reoad or Heighway.
- In the V+ision Setback area no Setructure of any kind shall be permitted which exceeds a height of three-two (32) feet above the elevation of the center of the intersection, except for necessary highway and traffic signs, public utility lines, and open fences through which there is clear vision, nor shall any plant material be permitted which obscures safe vision of the approaches to the intersection.
- (FE) Additions to and replacements of existing Setructures may be made within the established road right-of-way as set forth by Section 3.09(1)(A) of this Ordinance, subject to approval of the Town Board and the Waukesha County Board of Adjustment, provided the owner will file with the Waukesha County Register of

Commented [BA39]: Relocated road setback exception from Section 3.09(1)(K)

Commented [BA40]: Revised language to be consistent with Department of Public Works Department.

Deeds an agreement in writing to the effect that the owner will remove all new construction, additions and replacements erected after the adoption of this Ordinance at his expense, when said right-of-way is necessary for the improvement of the \underline{H} kighway.

- (GF) In all cases where any of the Hhighways for which setback lines are established by this Ordinance are located on municipal boundaries, such establishment shall apply only within the unincorporated area.
- (2) Wetland Setback: (H) _ Every structure Structure, except boathouses and any other structure excepted from shore setback by another Section of this Ordinance, shall be shall have a set back of at least seventy five (75) feet from a navigable body of water or the Conservancy District boundary linewetland boundary, whichever is greater, except for the following:
 - 1. Where structures were erected prior to the passage of this original Ordinance (February 26, 1959) and are located closer than seventy five (75) feet but not closer than fifty (50) feet from a navigable body of water or the Conservancy District boundary line, such structures may be considered in a conforming location. Additions or alterations to such existing structures not closer than fifty (50) feet from a navigable body of water or the Conservancy District boundary line may be allowed, so long as such additions or alterations do not result in an encroachment closer to the ordinary high water mark of the navigable body of water or the Conservancy District Boundary than currently exists.
 - Boathouses may be permitted within fifty (50) feet of the ordinary high
 water mark of a navigable body of water or a Conservancy District
 boundary line, but not closer than five (5) feet from the ordinary high water
 mark or within a wetland.
 - 3. The Zoning Administrator may grant a special zoning permit for a structure that extends closer than seventy five (75) feet to the ordinary high water mark of a navigable body of water if all of the following requirements are met, but in no case is a structure exempt from the shore setback requirements from the Conservancy District boundary line:
 - (a). The part of the structure that is nearest to the water is located at least thirty five (35) feet landward from the ordinary high water
 - (b). The total floor area of all structures in the shore setback area of the property shall not exceed two hundred (200) square feet. In calculation the square footage, boathouses shall be excluded.
 - (c). The structure that is subject to the request for special zoning permission has no sides or has open or screened sides.
 - d). The zoning administrator shall review a plan submitted by the applicant which shall be subject to the zoning administrator's approval and which will be implemented by the owner of the property to preserve or establish a vegetative buffer zone that

Commented [BA41]: Removed shore setback elements that do not apply to the general zoning code. Per recent State law, a County ordinance can no longer regulate floodplain matters beyond the floodplain boundary.

covers at least seventy (70) percent of half of the shore setback area that is nearest to the water.

- _4(A)- A retaining Retaining wall Wall shall be set back at least seventy five (75) feet from the ordinary high water mark of a navigable body of water and located outside of the conservancy district wetland boundary and wetlands and may be allowed if the Zoning Administrator determines that the retaining wall is necessary to abate a known and identified soil erosion and sedimentation problem.
- 5(B-) A single stairway and walk, determined by the Zoning Administrator to be necessary for access to a lake, pond or river, shall be permitted to have a shore setback of less than seventy five (75) feet provided the width of the stairway or walk does not exceed three (3) feetor walkway may be permitted within the W-retland S-setback. If the walkway is proposed in an area designated as Wetland, the walkway shall be constructed on pilings.
- 6. Where there is an existing pattern of development with principal buildings having shore setbacks less than seventy five (75) feet from the ordinary high water mark of a navigable body of water or the Conservancy District boundary line, the setback requirements for new principal buildings or additions to the principal building shall be allowed to be reduced in accordance with the following setback averaging formula, however, in no case shall the required minimum shore setback from the ordinary high water mark or Conservancy District boundary be reduced to less than thirty (30) feet:
 - 1. If there is a building which is non-conforming with respect to shore setback with a similar use as the proposed building and located on an adjacent parcel on one side of the proposed building and within two hundred (200) feet of the proposed building, the average of the shore setback of that building of similar use and the required minimum shore setback shall apply.
 - 2. If there are two buildings which are non conforming with respect to shore setback with similar uses as the proposed building and located on adjacent parcels on each side of said building and within two hundred (200) feet of the proposed building, the average of the shore setbacks of those buildings of similar use shall apply.
 - In the case of a proposed addition to an existing building which has less than the required shore setback, the shore setback of such existing building may be used to determine the required shore setback for the proposed addition, as set forth above.
 - In applying these shore setback averaging provisions, the shore setback
 measurements shall be taken from the principal buildings only and the
 measurements shall not be from any immediately adjacent structures, such
 as decks or patios.
- (C) Where there is an existing pattern of development with Pprincipal Bbuildings having setbacks less than seventy-five (75) feet from the wetland boundary line, the setback requirements for new Pprincipal Bbuildings or additions to Pprincipal Bbuildings shall be allowed to be reduced in accordance with the following setback averaging formula, however, in no case shall the required minimum Wwetland

Commented [BA42]: Modified language to match shoreland ordinance.

Commented [BA43]: Modified to make language easier to understand for the reader.

Ssetback be reduced to less than thirty-five (35) feet:

- 1. Building within Wwetland Seetback on one side only: If there is a Pprincipal Bbuilding that is located less than seventy-five (75) feet from the Wetland with a similar use as the proposed Bbuilding and located on an adjacent Lot on one side of the proposed Bbuilding and within two hundred fifty (250) feet of the proposed Bbuilding, the average of the Wwetland Seetback of that Bbuilding of similar use and the required minimum Wwetland Seetback shall apply.
- Buildings within Wwetland Seetback on both sides: If there are two Pprincipal Bbuildings which are located less than seventy-five (75) feet from the Wwetland with similar uses as the proposed Bbuilding and located on adjacent Lots on each side of said Bbuilding and within two hundred fifty (250) feet of the proposed Bbuilding, the average of the Wwetland Seetbacks of those Bbuildings of similar use shall apply.
- 3. Addition to an existing Bbuilding within Wwetland Ssetback: In the case of a proposed addition to an existing Pprincipal Bbuilding which has less than the required Wwetland Ssetback, the Wwetland Ssetback of such existing Bbuilding may be used to determine the required Wwetland Ssetback for the proposed addition; as set forth below.
 - a. If there are no existing Bbuildings with a similar use as the
 Bbuilding with the proposed addition on either of the adjacent
 Llots, the average of the Wwetland Seetback of the existing
 Bbuilding and the required Wwetland Seetback shall apply to the
 addition.
 - b. If there is only one existing Bbuilding with a similar use as the
 Bbuilding with the proposed addition on an adjacent Llot, the
 average of the Wwetland Ssetback of the existing Bbuilding and the
 existing Bbuilding on the adjacent Lot shall apply to the addition.
 - c. If there are existing Bbuildings with similar uses as the Bbuilding with the proposed addition on both adjacent Lots but one of the adjacent Bbuildings is located further from the Wwetland than the existing Bbuilding with the proposed addition, the average of the Wwetland Ssetback of the existing Bbuilding and the Bbuilding on the adjacent Lot located closest to the Wwetland shall apply to the addition
- 4. In applying these wetland setback averaging formulas to a proposed Pprincipal Bbuilding or addition to a Pprincipal Bbuilding, the wetland setback measurements shall be taken from other Pprincipal Bbuildings only and the measurements shall not be from any immediately adjacent Setructures, such as Decks or Ppatios, Retaining Wwalls, Sewimming Ppools or sports courts.
- In applying these wetland setback averaging formulas to a proposed
 Structure, such as a Deck or Ppatio, which is immediately adjacent to the

Pprincipal Bbuilding, the wetland setback measurements may be taken from other Pprincipal Bbuildings or immediately adjacent Sstructures, such as Ddecks or Ppatios, but not from Retaining Wwalls, Sewimming Ppools and sports courts.

- 7. An addition to a principal building or a deck or patio immediately adjacent to a principal building, may be located as close as forty (40) feet from the Conservancy District boundary if it is in conformity with the required setback from the ordinary high water mark and if the existing natural ground elevation adjacent to the lowest level of the building is at least three (3) feet above the one hundred year flood plain elevation or the high water mark of the conservancy or wetland area.
- 8. In the case of an addition to a principal building into the minimum required road or shore setback area and where such addition would not extend closer to the established setback line, shoreline, one hundred year floodplain or Conservancy District boundary than the existing building to which it is attached or immediately adjacent and said addition may be closer than the required distance would allow when using the setback averaging formula set forth in 3.09(1)(H)(6) above, the board of adjustment may grant a special exception to the addition so long as the extension does not encroach closer to the setback line, one hundred year floodplain or Conservancy District than the existing building to which it is attached.
- (I) In the case of an extension or addition of a structure into the minimum required road or shore setback area and where such extension would not extend closer to the established setback line, shore line, 100 year Floodplain or Conservancy district than the existing structure to which it is attached and said extension may be closer than the required distance would allow, using the averaging formula, a Special Exception may be allowed by the Board of Adjustment for such an extension or addition, as long as said extension or addition does not encroach closer to the setback line, shore 100 Year Floodplain or Conservancy district than the existing structure to which it is attached.
- (D) The effect of the wetland setback regulations in combination with the road setback regulations shall not reduce the buildable depth of such Liot to less than thirty (30) feet. Where such reduction would result in a depth less than thirty (30) feet after applying the wetland setback and road setback averaging formulas, the zoning administrator shall have the authority to modify the road setback and wetland setback -provisions to the extent necessary to minimize the encroachment on the road setback and wetland setback standards while maintaining the thirty (30) foot depth.
- E) One (1) accessory Sstructure with a maximum size of two hundred (200) square feet may be located as close as thirty-five (35) feet from the Wsstaland provided there is no other conforming location available and no other accessory Sstructures located on the Llot
- (F) If the above exceptions do not apply and an improvement or addition is proposed to

Commented [BA44]: Modified to make language easier to understand for the reader.

Commented [BA45]: Provides additional wetland setback flexibility for minor structures when no other available conforming location.

an existing Legal Nnonconforming Sstructure, the provisions of Section 3.17 apply

- (J) Where an overhang exceeds two (2) feet as defined herein, the additional overhang is not allowed unless the building is relocated the additional distance from the base setback line or lot line that the amount the overhang exceeds two (2) feet unless a variance is granted by the Board of Adjustment.
- (K) Retaining walls do not need to meet the road setback requirements of the individual zoning district.

$(\frac{23}{})$ Offsets:

- (A) No principal building or its accessory building shall be hereafter erected or altered so that any roofed or enclosed portion thereofSstructure, excluding a roof Oeverhang measuring twenty four inches (24") or less, is shall be located closer to any Llot Lline than the Oeffset distance hereinafter specified by the regulations for the Delistrict in which such building Sstructure is located, with the following exceptions:
 - 1. Only one (1) boathouse per lot is allowed and the boathouse may not be permitted closer than five (5)-feet from the ordinary high water mark.
 - 2. In the case of a lot of record, which has a minimum average width less than the required minimum average width of the district in which it is located, the required offset for the principal structure from a side lot line may be reduced proportionately to the ratio between the actual average width and the required minimum average width, but not less than ten (10) feet except in accordance with Section 3.06(5) or as may be permitted within an approved Planned Unit Development.

Example: Actual Average Lot Width x Required Offset = Reduced Offset Required Minimum Average Lot Width

- Offsets for detached accessory buildings exceeding two hundred (200) square feet in area on lots of one hundred and twenty (120) feet in width or less may be reduced to an amount equal to the proportionate amount between the actual width and one hundred and twenty (120) feet and not less than five (5) feet, even when consideration is given to Section 3.06(5). However, no detached accessory building shall be located closer than ten (10) feet to any structure used for residential purposes.
- In the case of a Llot of Record, which has a minimum average width of less than one hundred twenty (120) feet, the required Ooffset for a Setructure from a Seide Llot Lline may be reduced as follows, unless the district requirement is less restrictive, in which case, the less restrictive requirement applies:

Lot Width (ft.)	Required Offset (ft.)
35 ft. or less	<u>5 ft.</u>
Greater than 35 ft. to 50 ft.	<u>7 ft.</u>
Greater than 50 ft. to less than 84 ft.	<u>10 ft.</u>
84 ft. to less than 120 ft.	<u>14 ft.</u>

Commented [BA46]: References the nonconforming section, which provides additional flexibility.

Commented [BA47]: Replaced offset reduction formula with a table that specifies the required offset based on the width of the lot. Modified offsets for decks, patios, stairways, and walkways to provide flexibility and make regulation easier to calculate. Reorganized language within subsection.

- 42. Offsets for Beuildings housing Livestock, Ffur Bearing Aemimals, pigeons, swine, goats and Peoultry, shall be not less than fifty (50) feet from an adjacent property line. This does not include doghouses.
- 53. When a detached accessory Setructure lies on an adjacent Llot and closer than five (5) feet of the common Llot Lline, a new detached accessory Setructure may be located the same distance from the common boundary as the existing detached Setructure on the adjacent Llot, as long as they are within ten (10) feet of each other. In such a case, the new detached accessory Setructure shall contain a firewall sufficient to meet the one-hour fire rating contained in the building code. However, unless a common wall with a one-hour fire rating is constructed with agreement of both property owners, building sidewalls may be no closer than three (3) feet in order to accomplish proper maintenance Maintenance. A deed restriction shall be recorded prior to issuance of the zoning permit prohibiting the construction of fences between said Beuildings and permitting maintenance Maintenance of said Beuildings from adjacent properties Lots.
- 64. One detached accessory Bbuilding on any parcel Lot which is less than two hundred (200) square feet in area may be located five (5) feet to the Saide Liot Line unless otherwise excepted under any other provision.
- 7. In the case of an extension or addition of a structure into the minimum offset distance, and where such extension would not extend closer to the side lot line than the existing structure to which it is attached, a Special Exception may be granted by the Board of Adjustment to allow such an extension or addition as long as said extension or addition does not encroach closer to the side lot line than an existing structure to which it is attached.
- 5. Offsets on Delecks and Ppatios may be reduced to fifty percent 60(50%) of the distance between the principal Setructure and the Leot Letine, otherwise required for the principal Setructure, but shall in no case be located closer than five (5) feet of a Leot Letine. This includes any reduction allowed in Section 3.06(5).
- 6. Stairways or walkways, five (5) feet in width or less, shall be located a minimum of five (5) feet from a Llot Lline. Stairways or walkways that exceed five (5) feet in width, shall comply with subsection 5 above. Existing stairways or walkways may be replaced in-kind within five (5) feet of a Llot Lline.
- Retaining <u>W</u>-alls do not need to meet the offset requirements of the individual zoning districts if they comply with the provisions of Section 3.04(5).
- 8. If the above exceptions do not apply and an improvement or addition is proposed to an existing Legal N#onconforming Sstructure, the provisions of Section 3.17 apply.
- (B) Where a \underline{L} -lot abuts a \underline{D} -district boundary line, the \underline{O} -offset from such line in the

Commented [BA48]: The nonconforming section of the ordinance specifies requirements for extensions or additions. A cross-reference to the nonconforming section is made below.

 $\underline{\mathbb{D}}$ district of less restricted use shall be not less than that required for the $\underline{\mathbb{D}}$ district of more restrictive use.

- (C) In the case of multiple family or commercial use <u>S</u>-structures, the <u>O</u>⊕ffsets may be modified as follows:
 - Two (2) or more Bbuildings on adjoining Ltots may be erected with common or directly adjoining walls provided the requirements of the state industrial code relative to such construction are complied with, and provided that at both ends of such "row" type buildings, the applicable offset requirements shall be complied with.
 - 2. The required Oeffset may be reduced on one (1) side of a Setructure provided the Oeffset on the other side is increased by an equivalent amount, and provided the owners of any property adjoining the area of reduced Oeffset shall file with the town board a copy of a recorded deed restriction stipulating that no Beuilding shall be erected on said property so as to reduce the combined Oeffset in such case to a distance less than that resulting from the normal application of the minimum offset requirements to both properties, except as permitted under [paragraph] (1)subsection (3)(A) above.
- (34) Maintenance and use of Seetback and Oeffset areas: Any such required setback or offset area shall be landscaped and kept clean and free from the accumulation of debris or refuse and shall not be used for the storage or display of equipment, products, vehicles or any other material
- (45) Accessory Beuilding location: No detached Accessory Beuilding shall be erected, structurally altered or placed or a Leot so that any roofed or enclosed portion thereof is closer than ten (10) feet to the Perincipal Beuilding on said Leot.
- (5) <u>Vertical location</u>: No building intended for human habitation shall be located so that its lowest floor, including any basement floor, is less than one (1) foot above the highest seasonal ground water level.

(Sections 3.09(1)(A)4, (1)(D), (1)(H), (1)(K), and (2)(A) were amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Section 3.09(2)(A)4 was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

3.10 **Height regulations**

- Maximum height Height restricted Principal Structures: The following height provisions apply
 to principal Structures in all Delistricts except for the P-I, Q-1, M-1 and M-2 Districts, where
 height regulations are specified in each respective Delistrict section:
 - (A) Overall maximum height (lowest exposure to highest peak), thirty-five (35) feet, for Setructures on a L4ot with an average width less than sixty-five (65) feet.
 - (B) Overall maximum height (lowest exposure to highest peak), forty-four (44) feet, for S-structures located on L-lots with an average width of at least sixty-five (65) feet. A Structure with a flat roof is limited to an overall maximum height of thirty-five (35) feet and subsection (C) below does not apply.

Commented [BA49]: Incorporate Advisory Committee recommendations to amend other height regulations to adapt to a new building footprint/bulk scheme. Relocated provisions from district sections to this general height section.

- (C) Maximum height from lowest exposure to highest eave, thirty-two (32) feet, for Setructures on Liots with an average width of at least sixty-five (65) feet.
- (2) Maximum Height Accessory Structures: The following height provisions apply to accessory

 Setructures in all Delistricts except for the FLC, FLP, A-T, A-B, H-G, P-I, Q-1, M-1 and M-2

 Districts, where height regulations are specified in each respective Delistrict section:
 - (A) Maximum overall height is limited to eighteen (18) feet, or
 - (B) The maximum overall height is limited to sixty (60) feet if the Setructure is used for farm or agricultural purposes in the AD-10, RRD-5, A-5, A-1, and P-I Districts and the R-1 District if designated in the Farmland Preservation County Development Plan category.
- (3) Provided a Sstructure or Bbuilding is located on a Llot that is at least sixty-five (65) feet in average width, the height may be increased by one (1) foot for each foot the Sstructure exceeds the Ooffsets and Ssetbacks, except for Ddecks and Ppatios, but not by more than ten (10) additional feet. The above provided height increase does not apply to Lots zoned R-1, R-2, R-3, or E-C.
- (1) In any district no building or structure shall hereinafter be creeted or structurally altered to a height in excess of that herein specified for the regulations of that district, except the maximum height of any structure or building may be increased by not more than ten (10) feet, provided all required offsets and setbacks are increased by one (1) foot for each foot which said building or structure exceeds the height limit in which the district it is located.
- (4) Exceptions: The following shall be exempt from the height regulations of all Delistricts.
 - (A) Chimneys and flues.
 - (B) Subject to approval of the Plan Commission; cooling towers, elevators, bulkheads, fire towers, monuments, stacks, tanks, water towers, ornamental towers, spires, wireless or broadcasting towers, masts, aerials, and necessary mechanical appurtenances.

(Section 3.10 was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

3.11 Area and Building Footprint regulations

- (1) Minimum Floor Aarea:
 - (A) Any Bbuilding intended in whole or part for single-family residential purposes shall provide a minimum overall Ffloor Aerea of eleven hundred (1,100) square feet sq. ft. with at least eight hundred fifty (850) square feet sq. ft. of Ffloor Aerea on the first floor. Minimum Ffloor Aerea shall be measured at each level from the outside edge of wall to outside edge of wall. Basements, exterior balconies, unenclosed Pporches, and Ggarages shall not be included in the minimum floor area calculation as hereinafter specified by the regulations for the district in which such building is located. Such minimums are stated in terms of the minimum total floor area required for a building and that portion of the total which must be provided on the first floor level. Such minimum total shall be increased by two hundred (200) square feet for any building not having a basement of at least three hundred (300)

Commented [BA50]: Modified minimum floor area regulations to be consistent in all districts and decrease minimum square footage requirements for multi-family units. Removed all references to floor area ratio because the regulation was replaced with footprint.

square feet in area.

- (B) Any Bbuilding intended in whole or part for multi-family residential purposes shall provide a minimum overall Ffloor Aarea (per unit) as follows:
 - Two-family Bbuildings (duplexes): Eight hundred fifty (850) square feet sq. ft. per unit.
 - 2. Multi-family Bbuildings that exceed two (2) units:
 - a. Six hundred (600) square feet-sq. ft. per one-bedroom unit.
 - b. Seven hundred (700) square feetsq. ft. per two-bedroom unit.
 - c. Eight hundred (800) square feetsq. ft. per three-bedroom unit.
 - An additional one hundred (100) square feet-sq. ft. for each additional bedroom.
- (B) The maximum total floor area of the buildings on a lot shall not exceed that permitted under the floor area ratio as hereinafter specified by the regulations for the district in which such building is located as noted below. The finished basement or exposed basement area used for living space shall not be computed in the maximum floor area ratio requirements but the floor area of an exposed basement may be used in computing the minimum floor area requirement. Garage space in an exposed basement is not required to be computed in the maximum floor area ratio.
- (C) Minimum required floor area shall be measured at each level from the outside edge of wall to outside edge of wall and, for purposes of computing total minimum floor area, shall not include attached or detached garages; other outbuildings; porches; or becoments

Exposed basements and the second floor of one and one half and two story residences may be included in computing total minimum floor area according to the following schedule:

- 1. That portion of the exposed basement of an exposed basement residence which has been designed as an integral part of the living area of the home, may be included in computing total minimum floor area when at least one side is completely exposed to grade level and access has been provided to the outside at grade level by means of at least one door, but said area does not have to be included in calculating the minimum floor area ratio requirements.
- 2. That portion of the second floor of one and one half and two story buildings which has a minimum distance between the ceiling face and the floor of six (6) feet shall be included in computing the total minimum floor area provided there is a permanent stairway leading from the first floor to the second floor. Where the floor to ceiling height is less than six (6) feet and the area is part of living space in the residence and does not include a closet, attic or similar storage area, said area shall be included in the minimum floor area computation (i.e., "splayed" or sloped ceiling).

- 3. In split level units, floor area shall be computed as follows:
 - a. If less than one half of the lower level(s) is above ground, such level shall be considered a basement and cannot be included in total floor area of the building unless such basement qualifies as an exposed basement Section in 3.11(1)(C)1 above.
 - b. If more than one half of the lower level(s) is above ground, such areas can be included in determining floor area. If there is no basement below this level(s), two hundred (200) square feet of floor area shall be required in addition to the floor area requirement of the zoning district. This required floor area shall be finished as an integral part of the dwelling unit within six (6) months of the date upon which the building permit is issued.
- The board of adjustment may grant an Sepecial Eexception to permit a Beuilding of less than the required minimum Feloor Aerea where such grant would not be contrary to the spirit or intent of this the Ordinance, and provided the proposed Beuilding would not be of such character or quality as to depreciate the property values of the surrounding area, and provided further than in no case shall a minimum floor area of less than one thousand (1,000) square feet be permitted.

(2) Lot size:

- (A) No Llot shall hereafter be created and no Beuilding shall be erected on a Llot of less land area or minimum average width than hereinafter specified by the regulations of the Delistrict in which such Beuilding is located except as may be provided in Subsection Sections 3.11 (2) (E), Section 3.06 (5) and 3.08 (7) (N) and 3.08(7)(P) of this Ordinance.
- (B) For the purpose of this Ordinance, the \underline{L} tot \underline{A} erea shall be measured from the \underline{B} base Seetback L1:ine.
- (C) A Llot shall be at least as wide as the specified minimum average width for a distance of at least one-half the length of the Llot.
- (D) No Lłot Aerea shall be reduced by any means so as to create a Llot of less than the required size or so that the existing- Oeffsets, Setbacks, Oepen Sepace, or Llot Aerea would be reduced below that required by the regulations for the Oefistrict in which such Llot is located except as provided by Section 3.06(5).
- (E) Where a Lłot has less area or width than required for the Delistrict in which it is located or frontage as specified in section 3.11(2)(A) and was of record at the time of the passage of this Ordinance (February 26, 1959), such Lłot shall be used for any purpose permitted in any such Delistrict, but not for residential purposes for more than one (1) family; provided; however, that building location, height regulations and area the maximum Beuilding Ffootprint regulations shall comply with requirements of the R-3 Residential District except where otherwise specified in other sections of this Ordinance.
- (F) Lots split by a Rroad (public or private): If a single Llot or multiple Llots are in the

Commented [BA51]: Removed this section from ordinance and specified provisions in each zoning district instead.

Commented [BA52]: Because setback and area relief is now provided throughout ordinance for all districts, this paragraph no longer needs to apply, with the exception of providing relief from the maximum building footprint regulations.

same ownership, but are split by a separately described public or private road, the following regulations apply:

- For a single Llot of Record (as defined in this Oerdinance), the acreage on both sides of the road right-of-way may be used for purposes of calculating minimum Llot Aerea, maximum accessory Beuilding Ffootprint, maximum overall Beuilding Ffootprint, and allowable Impervious Seurface, if applicable.
- For multiple Lłots of Record (as defined in this Oerdinance), the acreage
 on one side of the road right-of-way shall not be used to benefit the Llot on
 the other side of the road right-of-way for purposes of calculating minimum
 Lłot Aerea, maximum accessory Beuilding Feotprint, maximum overall
 Beuilding Feotprint, and allowable I impervious Seurface, if applicable.
- 3. For multiple Llots of Record in common ownership, an accessory Setructure may be constructed on one side of the road right-of-way without the benefit of a principal Setructure on the same side of the road right-ofway provided the following are met:
 - a. The Llots in common ownership are directly opposite each other for at least one half of the road frontage of one of the Llots.
 - A principal Sstructure must exist on the Llot owned in common on the opposite side of the road right-of-way.
 - A cCertified sSurvey mMap shall be prepared and approved by all
 reviewing entities restricting the Llots from being sold separately,
 unless the accessory Sstructure is removed.

(3) Substandard Lots:

- (A) A legally created Llot or parcel that met minimum area and minimum average width requirements when created, but is not at least twenty thousand (20,000) square feet sq. ft. in size and one hundred (100) feet ft. in average width, unsewered, or ten thousand (10,000) square feet sq. ft. in size and sixty-five (65) feet ft. in average width, sewered, may be used as a building site if all of the following apply:
 - The substandard Llot or parcel was never reconfigured or combined with another Llot or parcel by plat, survey, or consolidation by the owner into one property tax parcel, as described with a single legal description.
 - The substandard Llot or parcel has never been developed with one or more
 of its Setructures placed partly upon an adjacent Llot or parcel.
 - The substandard Llot or parcel is developed to comply with all other Oordinance requirements.
- (B) A substandard Llot that does not comply with subsection (A) above, may only be developed if a V+ariance is granted by the Board of Adjustment.

Such substandard lots shall be in separate ownership from abutting lots. If abutting

Commented [BA53]: This subsection was created in order to address lots that are split by a road, but in single ownership. The regulations specify how the lot/s can be used for building regulatory purposes.

Commented [BA54]: Matched proposed shoreland ordinance regulations which were modified per NR115.

lands and the substandard lot are owned by the same owner, the substandard lot shall not be sold or used without full compliance with the minimum lot area requirements of the R 3 Residential District or as close to that minimum as possible.

Commented [BA55]: Relocated this section below and matched language of shoreland ordinance (per NR115).

(3) Open space:

- (A) No building shall be creeted, structurally altered or placed on a lot so as to reduce the usable open area of such lot to less than that hereinafter specified by the regulations for that district except as provided by Section 3.06(5).
- (B) To be considered usable, such open area shall be readily accessible and of a size and shape which can be reasonably considered to provide for the amenities and necessities of light, air, play space, drying yard, garden, etc. Crop, pasture, and wooded land may be included in computing such open area.
- (C) No part of the open space provided for any building shall be included as part of the open space required for another building, except as hereinafter provided for in planned unit developments, Section 3.08(7)(P).
- (4) Accessory Buildings and Structures: The aggregate total Ffloor Aarea Building Footprint of any all Aaccessory Buildings on a Llot in any zoning district may not exceed 3% of the total area of the lot nor exceed the floor area ratio accessory building footprint limitations specified in the following table, with the exceptions listed below the table: requirements of the appropriate zoning district, except the 3% accessory building regulation may be exceeded in business and industrial districts when approved as a special exception by the Plan Commission and Zoning Agency. An attached garage shall not be included in this 3% limitation. Temporary structures must be included within these allowable square footages.
 - (A) Accessory Building Footprint Table:

Lot Area	Maximum Building Footprint
<14,000 sq. ft.	600 sq. ft.
14,000 sq. ft. or greater	750 sq. ft. or 2% of Llot Aarea, whichever is greater

In no case shall more than two accessory buildings be permitted unless approved by the Plan Commission with the following exceptions:

- (B) On parcels Lots of fifteen (15) acres or more in area, the accessory building areas footprint may be greater than the 3two percent (2%) limit when used solely for the pursuit of agriculture and where the Accessory Beuildings will house equipment as regulated in Section 3.12(3)(A), and when consistent with the floor area ratiomaximum overall Beuilding Ffootprint requirements of the Zoningthis Ordinance.
- (B)(C) Farm Ceonsolidation exception. Maximum accessory building footprint limitations shall be established by the Plan Commission and County Zoning Agency for Liots that are designated in the Farmland Preservation County Development Plan category that have been rezoned to the R-1 Residential District pursuant to Section 6.19.

In all Business and Industrial Districts, when approved as part of the plan of operation

Commented [BA56]: Removed regulations regarding open space because open space regulations are proposed to be removed from ordinance. Incorporated language of NR115.05(1)(a)3-substandard lots.

Commented [BA57]: Replaced 3% accessory building floor area ratio with a max. sq. ft. table based on lot size is easier to administer.

Commented [BA58]: Relocated language and modified to read more user friendly. See (E) below.

and site plan review, and where said buildings are used solely accessory to the principal use on said lot.

- (C)(D) Temporary Setructures and attached Ggarages shall not be included in calculating allowable accessory Benilding Ffootprint.
- (E) A Lot is limited to two (2) accessory buildings unless the Plan Commission has rendered a finding to allow more than two (2) accessory buildings in light of the provisions of Section 3(d)3.B. More than two (2) accessory buildings may also be permitted under the following circumstances:
 - On Lots of fifteen (15) acres or more in area and when used for Aagricultural
 Use and where the Aaccessory Babuildings will house equipment as regulated in Section 3.12(3), and when consistent with the maximum overall Babuilding Ffootprint requirements of this Ordinance.
 - 2. In all Business, Industrial, Public and Institutional, and Quarrying Districts, when approved by the Plan Commission and Zoning Administrator as part of the plan of operation and site plan review, and where said Bbuildings are used accessory to the Pprincipal Uuse on said Llot, and when consistent with the maximum overall Bbuilding Ffootprint requirements of this Ordinance.
 - On Lots which are the subject of a conditional use permit and as regulated by the conditional use permit, and when consistent with the maximum overall Bbuilding Ffootprint requirements of this Ordinance.
- (D) On parcels which are the subject of a conditional use permit and as regulated by the conditional use permit.
 - A. When a petitioner is proposing more square footage of accessory buildings than the 3% limit allows or as excepted above, the Board of Adjustment may grant a special exception to the above requirement in accordance with the procedure as outlined in Section 19 of this Ordinance. The petitioner must submit a current plat of survey by a registered surveyor indicating all existing buildings on the parcel, their location, total square footages and the number of stories in existing structures and proposed buildings. The Board of Adjustment may require a deed restriction to be recorded prior to issuance of the zoning permit, restricting the use of the oversized accessory buildings to uses accessory to the principal use of the premises and may not allow uses prohibited in the zoning district in which the building is located.
- (F) All Aecessory Beuildings shall be constructed in such a way that the exterior appearance is compatible with the design, style, architecture and appearance of the principal Setructures on the parcel. This determination shall be made by the local building inspector and the Zoning Administrator. In case of dispute, such questions shall be submitted to the Plan Committee and the Zoning Agency for review and approval in accordance with Section 3.04(3). This requirement does not apply to farming operations on more than thirty-five (35) acres.
- (G) In no case shall any Accessory Bouilding be used for purposes not allowed in the underlying zoning district or as may be authorized by a conditional use permit.
- (H) Where more than two such accessory buildings are proposed, the Plan Commission

shall review said structures in light of the provisions of Section 3.04(3) and render a decision to allow or disapprove said structure.

(5) Building Footprint (as defined in this Ordinance):

- A) Minimum Building Footprint: The Zoning Administrator may administratively approve a Bbuilding Ffootprint not to exceed eleven hundred (1,100) square feet-sq. ft. when application of Ooffsets and Seetbacks does not otherwise provide an eleven hundred -(1,100) square foot-sq. ft. Bbuilding Ffootprint. The Zoning Administrator is limited to providing Rroad Seetback and Wwetland Seetback relief only. The administratively approved Bbuilding Ffootprint shall not extend into the established road right-of-way or within Wwetland.
- (B) Maximum Building Footprint: The maximum Building Ffootprint shall not exceed the footprint standards specified by the regulations for the Ddistrict in which such Building is located, unless the provisions of Section 3.11(2)(E) are met.

(Sections 3.11(2)(E) and (4)3 were amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Section 3.11(2)(E) was amended by Enrolled Ordinance 160-03, effective 05-13-05.) (Section 3.11(4) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

3.12 Off_street parking

- (1) Spaces required: Any Bbuilding hereafter erected or structurally altered shall be provided with an off-street parking space not greater than five hundred (500) feet from the Pprincipal Utise. A parking space shall be considered to be nine (9) feet in width by not less than twenty (20) feet in depth for angled sixty-degree parking and not less than twenty-seven (27) feet in depth for ninety_degree parking, and there shall be at least sixteen (16) feet of width between opposite facing parking stalls for ingress and egress. The following schedule shall be utilized to determine the number of parking spaces for various uses allowed by this Ordinance:
 - (A) Two (2) spaces per dwelling unit: (Such dimensions as enumerated above, however, are not required for single_family detached housing);
 - (B) Auditoriums, churches, theaters, community centers and other places of public assembly: One (1) space per four (4) seats;
 - (C) Retail business establishments, resorts, Restaurants, taverns, clubs, etc: Seven (7) spaces per one thousand (1,000) square feet of primary Ffloor Aerea devoted to the Perincipal Uese of the property. This requirement does not apply to the area of the Beuilding utilized for storage purposes. No additional space will be required for such storage space;
 - (D) Wholesale and other general business establishments: One (1) space for each employee during any work shift;
 - (E) Office buildings: One (1) space for each three hundred (300) square feet of Ffloor
 - (F) Medical and dental clinics: Three (3) spaces for each doctor and one (1) space for each employee;

Commented [BA59]: Added building footprint provisions to replace floor area ratio and open space standards to simplify and ease building bulk regulations.

- Industrial buildings and warehouse buildings: One (1) space for each employee during any work shift;
- (H) Sanitariums, institutions, rest homes, nursing homes: One (1) space for each five (5) beds plus one (1) space for every three (3) employees;
- (I) Hospitals: One (1) space for each two (2) beds plus one (1) space for every three (3) employees;
- (J) Hotels and Mmotels: One (1) space for each guestroom plus one (1) space for every three (3) employees;
- (K) Colleges, vocational and night schools, secondary and elementary schools: One (1) space for each employee plus one (1) space for every two (2) students except that the requirement for parking at elementary schools may not include student parking. At secondary schools the number of stalls for student parking shall be determined by the administration of that school and appropriate provisions made consistent with the intent of this provision.
- (2) Residential parking: Parking of vehicles accessory to a residential use shall be limited to those actually used by the residents or for temporary parking for guests. Vans or pick-up trucks used for private and recreational use or a motor home (recreational vehicle) or one (1) van or pickup truck used in a business or trade or used for transportation to and from a place of employment of the occupant may be parked on a residential property as long as such use does not become a nuisance to the neighborhood.
- (3) Parking of trucks and equipment: No other vehicular equipment of a commercial or industrial nature, except as in [paragraph]subsection (2) above, shall be parked or stored for more than two (2) consecutive hours and four (4) cumulative hours during any twenty-four (24)-hour period on any Liot in any zoning district except business and industrial districts or as follows:
 - (A) Agricultural equipment (such as farm tractors, plows, farm plows, seeders, combines, cultivators, trucks owned and used by the farmer in the operation of his Efarm, etc.) used in a farm operation.
 - (B) One (1) panel, van, or pick-up truck used in the conduct of a conforming business activity being carried on in a residential or agricultural district. The Board of Adjustment may, if the need is evident, permit more than one (1) such vehicle if the Town Board and Planning Commission indicate it has no objection to the increase in the number of such vehicles. No limitation shall be placed on vans or pick-up trucks if they are used for private non-business or noncommercial recreational purposes.
 - (C) A conditional use permit pursuant to Section 3.08(7)(W) may be granted to permit the parking of commercial or industrial type vehicles in any zoning district except C-1 conservancy. In business and industrial districts where such vehicles are necessary to an otherwise permitted business or commercial use, a conditional use permit will not be required and there are no limitations as to the number of such vehicles which may be parked on the property except as may be hereinafter established under the provisions of the applicable zoning district.

- (4) <u>Surfacing</u>: Any off-street parking area, other than that provided for a <u>R</u>residence, having a capacity for more than four (4) vehicles shall be surfaced and maintained in a reasonable dustless condition.
- (5) <u>Screening</u>: Any off-street parking area, other than that provided for a <u>Residence</u>, which abuts or faces a <u>residence_residential</u> district shall provide a <u>Pelanting Screen</u>, landscaped fence, or wall, at least four (4) feet in height along the side abutting or fronting on a <u>residence_residential</u> district.
- (6) Offset: In any off-street parking area, other than that provided for a Residence, which abuts a residence residential district, no vehicle shall be allowed to park closer than ten (10) feet to the abutting residential L4ot L4ine.
- (7) <u>Setback</u>: No vehicle shall be parked closer than ten (10) feet to the \underline{B} -base \underline{S} -setback \underline{L} -line.
- (8) <u>Lighting</u>: Lights provided in any parking area shall be hooded or beamed so as not to create undesirable glare or illumination of adjacent residential property.

(Section 3.12(3)(C) was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

3.13 Off-street loading and unloading

- (1) Required: In any local business, general business, limited industrial or general industrial district an off-street loading space shall be provided, in addition to the defined off-street parking area, for every ten thousand (10,000) square feet or fraction thereof in excess of three thousand (3,000) square feet of building area, exclusive of storage areas, used for commercial purposes.
- (2) <u>Areas</u>: Each such loading space shall have an area at least ten (10) feet wide by forty-five (45) feet long and with a minimum of fourteen (14) feet height clearance.

3.14 **Signs**

- (1) <u>Use restricted:</u> In any <u>Delistrict</u>, no <u>Seigns</u> shall be permitted except as is hereinafter specified by the regulations for that <u>Delistrict</u>.
- (2) <u>Setbacks and Ooffsets</u>: In any <u>Delistrict</u>, no <u>Seign other than those permitted in a residence residential or agricultural district shall be permitted closer than twenty (20) feet to the <u>Bease Setback Leline</u> or to any other <u>Lelot Leline</u>, and any <u>Seign not directly related to the use of the premises on which it is located shall conform to the setback and offset requirements as would apply to a <u>Beauliding in that Delistrict</u>.</u></u>
- (3) <u>Hazards or nuisances prohibited</u>: No <u>S</u>sign, billboard, or other advertising media which creates a hazard or dangerous distraction to vehicular traffic, or a nuisance to adjoining residential property shall be permitted in any <u>D</u>elistrict.
- (4) <u>Heights</u>: No free standing <u>S</u>eign shall exceed twenty (20) feet in height from the ground and no <u>S</u>eign shall in any case exceed the maximum height limit for the <u>D</u>elistrict in which it is located.

3.15 Airport safety zone

- (1) Maximum height: No Bbuildings or objects of natural growth located within two (2) miles of the boundaries of any airport, landing field, or landing and take-off strip and within a band five hundred (500) feet on each side of the center line extended of any runway, shall hereafter be erected, altered or permitted to grow to a height above the elevation of the nearest point of such runway greater than one-fifteenth (1/15) of the distance from said point.
- (2) <u>Control of use</u>: No <u>B</u>building or land located within two (2) miles of the boundary of any airport, landing field, or landing and take-off strip shall be so used that by reason of the emission of smoke, gas or other emanation, it shall produce a hazard to the operation of aircraft.
- (3) Exceptions: The aforesaid regulation shall not-neither apply to growing field crops which are harvested at least once a year, nornet to fences not over five (5) feet high. [Cross reference - Waukesha County Airport Zoning Ordinance, App. C.]

3.16 Mobile homes and trailers

- (1) <u>Human habitation prohibited:</u> Except within an approved Mmobile Hhome Ppark or camp, no trailer or Mmobile Hhome shall be used for the purpose of human habitation, human Human habitation being is defined in this subsection as entering the mobile home for any purpose other than maintenanceMaintenance.
- (2) A permit for one (1) continuous six-month period allowing the human habitation of a <u>M</u>mobile <u>H</u>home on lands other than an approved <u>M</u>mobile <u>H</u>home <u>P</u>park may be granted by the Town Board provided:
 - (A) The habitation is accessory to the current construction of a principal <u>S</u>structure owned by the same person who is <u>the A</u>applicant for the permit.
 - (B) The waste disposal facilities and water supply facilities are approved by the Waukesha County Department of Parks and Land Use, Environmental Health Division.
- (3) <u>Storage prohibited</u>: No <u>M</u>mobile <u>H</u>home in excess of twenty-five (25) feet in length shall be located or stored on any <u>property Lot</u> except in an approved <u>M</u>mobile <u>H</u>home <u>P</u>park, unless completely enclosed in a <u>S</u>structure.
- (4) <u>Mobile Hhome Pparks</u>: Such uses shall not be permitted except in accordance with Section 3.08(7)(L)

(Section 3.16(2)B was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

3.17 Legal Nnon-conformity

(1) Existing use permitted: The existing lawful use of a Beuilding or premises at the time of the enactment of this Ordinance or any amendment thereto may be continued although such use does not conform with the provisions of this Ordinance for the Delistrict in which it is located, subject to conditions hereinafter stated.

Commented [BA60]: Provided additional regulatory relief for structures nonconforming to offset, road setback, wetland setback, footprint, boathouse standards and height.

- (2) Classification Legal Nonconforming Sstructures, classification and regulation: For the purposes of administration, legal non-conformity shall be classified and regulated as follows If a Structure is nonconforming to one (1) or more of the Ordinance requirements as listed in subsections (A) through (F) below, the requirements of all applicable subsections must be complied with.
 - (A) Nonconforming to Wetland Setback:
 - Structures within thirty-five (35) feet of a Wwetland. Such Sstructures are limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Sstructure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
 - 2. Structures thirty-five (35) ft.feet or greater from the Wwetland.
 - a. The portion of the Setructure that existed prior to [County Board approval date] is limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Setructure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
 - b. A Sstructure may be replaced or relocated provided the Building Ffootprint of the Sstructure is not increased, unless permitted in subsection d below; there is no other conforming location available to rebuild a Sstructure of the same Building Ffootprint, as determined by the Zoning Administrator; and, provided no portion of a relocated Sstructure is located any closer to the Wwetland than the closest point of the existing Sstructure.
 - A Sstructure, including a replaced or relocated Sstructure, may be expanded vertically, provided the height requirements of the this Oordinance are met.
 - d. A principal Setructure may be expanded laterally, provided the lateral expansion does not exceed two hundred (200) square feet over the life of the Setructure and provided no portion of the lateral expansion is located closer to the Wwetland than the closest point of the existing Setructure.
 - e. All other provisions of the this Oordinance shall be met.
 - (B) Nonconforming to Road Setback:

- Structures within twenty (20) feet of a Bbase Ssetback Lline (as established in Section 3.09(1)(A). Such Sstructures are limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Sstructure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
- Structures twenty (20) feet to within thirty-five (35) feet of a Base Setback
 Line (as established in Section 3.09(1)(A).
 - a. The portion of the Sstructure that existed prior to [County Board approval date] is limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than 50% of the exterior structural members over the lifetime of the Sstructure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
 - b. A Setructure may be replaced or relocated provided the Building Ffootprint of the Setructure is not increased, unless permitted below; there is no other conforming location available to rebuild a Setructure of the same footprint, as determined by the Zoning Administrator; and, provided no portion of a relocated Setructure is located any closer to the Bbase Seetback Line than the closest point of the existing Setructure.
 - A Setructure, including a replaced or relocated Setructure, may be expanded vertically, provided the height requirements of the this Oerdinance are met.
 - d. A principal Setructure may be expanded laterally, provided the
 lateral expansion does not exceed two hundred (200) square feet
 over the lifetime of the Setructure and provided no portion of the
 lateral expansion is located any closer to the Bbase Setback Line
 than the closest point of the existing Setructure
 - e. All other provisions of thisthe Oordinance shall be met.
- Structures thirty-five (35) feet or greater from a Base Setback Line (as
 established in Section 3.09(1)(A). All standards of subsection 2 above shall
 be complied with, except that lateral expansions of principal Setructures are
 not limited to two hundred (200) square feet in size over the lifetime of the
 Setructure.
- (C) Nonconforming to Offset:
 - Structures within five (5) feet of a side or rear lot line. Such Sstructures are limited to interior and exterior remodeling and repair, with exterior

remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Sstructure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.

- 2. Structures five (5) feet to ten (10) feet of a side or rear lot line.
 - a. The portion of the Structure that existed prior to [County Board approval date] is limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Structure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
 - b. Lateral expansions that do not exceed fifty percent (50%) of the
 Building Ffootprint of the existing Structure, over the lifetime of
 the Setructure and vertical expansions require a Sepecial
 Eexception from the Board of Adjustment. Lateral and vertical
 expansions shall not extend closer to a side or rear lot line than the
 closest point of the existing Structure.
 - c. All other provisions of the this Oordinance shall be met.
- 3. Structures greater than ten (10) feet from a side or rear lot line.
 - a. The portion of the Structure that existed prior to [County Board approval date] is limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Structure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
 - b. Lateral expansions that do not exceed fifty percent (50%) of the Building Ffootprint of the existing Structure, over the lifetime of the Structure and vertical expansions are permitted by right. Lateral and vertical expansions shall not extend closer to a side or rear lot line than the closest point of the existing Setructure.
 - c. Lateral expansions that exceed fifty percent (50%) of the Building

 Ffootprint of the existing Structure, over the lifetime of the

 Structure require a Sepecial Eexception from the Board of

 Adjustment. Lateral and vertical expansions shall not extend closer

to a side or rear lot line than the closest point of the existing Structure.

d. All other provisions of thethis Oerdinance shall be met.

(D) Nonconforming to Building Footprint:

- 1. If an existing Structure or Sstructures occupy a greater Building Footprint than allowable by this Oordinance, the portion of the Structure(s) that existed prior to [County Board approval date] is limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Sstructure(s). Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
- If the Structure, or a combination of Structures, exceeds the maximum allowable Building Footprint, no lateral expansions are permitted.
- If the Structure, or a combination of Structures, exceeds the maximum
 allowable Building Footprint, vertical expansions are limited to the area of
 allowable Building Footprint for the Sstructure(-/s).

For example, if a Structure has a Building Footprint of three thousand (3,000) square feet, whereas a Building Ffootprint of two thousand (2,000) square feet is the maximum allowed, the vertical expansion, cumulatively, shall not exceed two thousand (2,000) square feet.

- If the Structure is intended for residential purposes and does not meet the minimum required Building Footprint square footage for a principal Structure, the Structure shall not be reduced in size.
- 5. All other provisions of the this Oordinance shall be met.

(E) Nonconforming to Height:

- 1. The portion of the Structure that existed prior to [County Board approval date] is limited to interior and exterior remodeling and repair, with exterior remodeling and repair limited to less than fifty percent (50%) of the exterior structural members over the lifetime of the Structure. Maintenance, as defined in this Ordinance, is exempt from this provision. An improvement or structural repair of the exterior structural members includes the removal or replacement of foundations, rafters, trusses, exterior walls, or similar structural members.
- Any vertical expansion to a Structure nonconforming to height shall comply with the height requirements of thisthe Oordinance.
- (F) Building Footprint flexibility: The Zoning Administrator has the authority to administratively approve a Building Footprint not to exceed exeleven hundred

(1,100) square feet when application of Offsets and S-setbacks do not otherwise provide a minimum eleven hundred (1,100) square footeet Building Footprint. The Zoning Administrator is limited to providing Road and Wetland Setback relief only. The Building Footprint shall not extend into the established road right-of-way or within the fFloodplain or Wetland.

(A) Non conforming structures:

- No structure shall be modernized, expanded or enlarged except in conformity with the applicable district regulations if such total repairs exceed fifty (50) percent of the current fair market value.
- Where such structure is damaged beyond fifty (50) percent of its current fair market value, it shall not be restored except in conformity with the applicable district regulations.
- All non-conforming structures lying within floodplains shall be floodproofed.
- (B3) Regulation of Legal Non-conforming use-Use of structures Structures and land:
 - 4(A-) No such use shall be expanded or enlarged.
 - Upon petition to and approval of the County Zoning Agency, such use may be changed to another use provided the Zoning Agency determines that the new use would not result in a greater degree of non-conformity than the current use.
 - 3(C-) When any such use is discontinued for twelve (12) consecutive or eighteen (18) cumulative months during a three year period, any future use of the land or Setructure shall conform to the use regulations of the applicable Deistrict.
 - 4(D). When a structure which houses such non-conforming use is damaged to the extent of more than fifty (50) percent of its current fair market value, it shall not be restored for any use except in conformity with the applicable district regulations.

 Total structural repairs or alterations to a Setructure housing a Nonconforming Use shall not equal or exceed fifty percent (50%) of the equalized assessed value of the Setructure obtained from the County Real Property Tax Listing over the lifetime of the Setructure. At such time as cumulative structural repairs or alterations to such a Setructure equal or exceed fifty percent (50%) of the equalized assessed value of the Setructure, the use of the Setructure shall be converted to conform with the applicable district regulations or the Setructure shall be torn down.
 - Total structural repairs or alterations to a structure housing a
 non-conforming use shall not exceed fifty (50) percent of the equalized
 assessed valuation of the structure.
- (C4) Legal Non-conforming lotsLots: The size and shape of such Llots shall not be altered in any way which would increase the degree of such non-conformity to the applicable district regulations.
- (35) Conditional use status: Subject to the provisions of Section 3.08, conditional use status may be granted to existing Legal N-non-conforming U-uses upon petition of the owner where

such use is determined to be not adverse to the public health, safety, or welfare; would not conflict with the spirit or intent of <u>thisthe</u> Ordinance; or would not be otherwise detrimental to the community and particularly the surrounding neighborhood. Such conditional use status shall be granted only with the approval of the Plan Commission following a joint public hearing in the manner provided in Section 21.02(2).

3.18 Prior permit

- (1) <u>Construction permitted:</u> Nothing herein contained shall require any change in the plans, construction, size or designated use of any <u>B</u>+uilding or part thereof for which a building permit has been issued before the effective date of this Ordinance and the construction of which shall have been substantially started within six (6) months from the date of such permit.
- (2) Subsequently non-conforming: Any such use which does not conform to the use regulations of the Delistrict in which it is located shall, however, subsequently be considered a Legal Naon-conforming Uses.

3.19 Swimming Ppools, as defined in Section 2.02

- (1) <u>Use permitted</u>: Above and below ground <u>S</u>swimming <u>P</u>pools are permitted in any <u>D</u>district other than A-E or C-1 <u>D</u>districts, subject to the following:
 - (A) The pool must be intended to be used solely by the occupants of the Perincipal U+se of the property on which the pool is intended to be located, and their guests.
 - (B) Any pool, together with its surrounding walks, Ppatios, diving platforms, bathhouses and accessory Setructures, shall be so located that the parts of said complex are in conformity with the setback and offset requirements of the applicable Delistrict.
 - (C) Walls or fences of at least four (4) feet in height shall be provided around the immediate area of the pool to act as a deterrent for unsupervised children gaining access. Where the pool is an above ground pool, no additional fence or wall shall be required if the walls of the pool are at least four (4) feet above the grade of the land completely surrounding it and extending at least five (5) feet from the walls of the pool. If an access ladder is provided, it shall be so designed so that it can be locked, tipped or otherwise placed to prohibit access to the pool by children.
- (2) <u>Permit required</u>: No <u>S</u>-wimming <u>P</u>-pool shall be constructed unless a zoning permit has been issued pursuant to Section 3.03 of this Ordinance.

(The Title to Section 3.19 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

3.20 Guesthouses

(1) <u>Use permitted</u>: Guesthouses, as defined by this Ordinance, are permitted in any <u>D</u>elistrict in which a single family dwelling is permitted.

- (2) Permanent habitation prohibited: A Gguesthouse must be used only for occasional occupancy by guests of the owner, and shall not be leased or rented for human occupancy.
- (3) Accessory to a single-family dwelling: No Gguesthouse is permitted unless a single family dwelling is already present on the Llot. Only one (1) Gguesthouse per Llot is allowed.
- (4) Area requirements: No Gguesthouse is allowed unless the Llot upon which the Gguesthouse is to be located is at least double the minimum area and lot width requirements of the Delistrict. This requirement is intended to prevent the creation of a non-conforming lot in the event that the Gguesthouse is sold.
- (5) <u>Building location</u>: A <u>guesthouse Guesthouse</u> must be able to meet the minimum setback, <u>offset Offset</u> and <u>open spaceBuilding Footprint</u> requirements of the <u>Delistrict</u> in which it is located. This requirement is intended to prevent the creation of a non-conforming <u>S</u>structure in the event that the <u>guesthouse Guesthouse</u> is sold.
- (6) Floor area: The Ffloor Aerea of a Gguesthouse may be any size. In order to sell a Gguesthouse as a separate unit, its Ffloor Aerea must conform with the district regulations in which it is located.
- (7) Access provisions: In the event that a Genesthouse is sold as a parcel separate from the single family dwelling, there must be direct access to a public road. If this is impossible, the Plan Commission and County Zoning Agency may approve a private easement to a public road if the following requirements are met:
 - (A) The private easement is at least thirty-three (33) feet for one (1) Ffamily and sixty-six (66) feet for two (2) families.
 - (B) The creation of a private drive would not adversely affect existing or future development of the area.
 - (C) The private drive would insure safe and continuous access for public service vehicles; and those properties served by such easement.

SECTION 4 DISTRICTS

4.01 Establishment of districts

For the purpose of this Ordinance the county is hereby divided into zoning districts which shall be designated as follows:

C-1Conservancy District. C-1 Conservancy Overlay District. **FLC** Farmland Conservancy District. FLP Farmland Preservation District. Agricultural Business District. A-B A 0 Existing Agricultural Overlay District. A-T Agricultural Transition District. AD-10 Agricultural Density District. Mini-farm District. A-5

Commented [BA61]: Modified all district sections to include a reduced road setback for lots served by sewer or as approved as part of a new subdivision plat, specify wetland setback, make all districts consistent with minimum floor area regulations, replace floor area ratio with building footprint, and reference specific sewer reductions and the general provisions of section 3, which provide various modified regulations and exceptions.

EC	Environmental Corridor District.
EC	Environmental Corridor Overlay District.
A-1	Agricultural District.
A-la	Agricultural District.
HG	High Groundwater District.
A-2	Rural Home District.
A-3	Suburban Estate District.
RRD-5	Rural Residential Density District
R-1	Residential District.
R-la	Residential District.
R-2	Residential District.
R-3	Residential District.
P-I	Public and Institutional District.
B-1	Restricted Business District.
B-2	Local Business District.
B-3	General Business District.
B-4	Community Business District.
B-P	Mixed Use Business Park District.
Q-1	Quarrying District.
M-1	Limited Industrial District.
M-2	General Industrial District.

(Section 4.01 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

4.02 Zoning map

- (1) <u>Districts mapped</u>: The boundaries of said <u>Delistricts</u> are shown upon Sectional zoning maps of each of the towns of Waukesha County under the County Zoning Ordinance, which maps are made part of this Ordinance, and all the notations, references and other information shown thereon shall be as much a part of this Ordinance as if the matters and information set forth by said maps were all fully described herein. Said maps shall be kept on file in the offices of the County Zoning Agency and the copies attached hereto are correct only as of the date of publication and are for general informational purposes only. For the purpose of local administration, a copy of the appropriate Section map shall also be kept on file in the office of each Town.
 - (A) The A O agricultural overlay district is a special kind of zoning district established to provide for superimposing upon basic districts additional permissive uses and regulatory standards without disturbing the basic underlying district regulations. As a special district, the applicable procedures for mapping amendments are those found in Section 20, changes and amendments.
- (2) <u>Determination of boundaries</u>: District boundaries shall be determined by measurement from and as shown on the official zoning maps and in case of any questions as to the interpretation of such boundary lines, the Zoning Agency shall interpret the map according to the reasonable intent of this Ordinance.
 - (A) Unless otherwise specifically indicated or dimensioned on the maps, the district boundaries are normally Liot Lines; Section, quarter Section or sixteenth Section lines; or the center lines of Setreets, Highways, railways or alleys.
 - (B) The boundaries of the C-1 Conservancy and the FLC Districts, as drawn, are

intended to represent the edge of swamp, marsh, and floodland or the high water line along a stream or watercourse, and shall be finally determined by the actual conditions in each specific situation, provided, however, that along a stream or watercourse, such line shall not be less than one hundred (100) feet from the center of such stream or watercourse.

(Section 4.02(2)(B) was amended by Enrolled Ordinance 170-72, effective 12/31/15).

4.03 FIRST AMENDMENT PROTECTED ADULT-ORIENTED ESTABLISHMENTS

(1) FINDINGS OF FACT.

- (A) The Board finds that Adult-Oriented Establishments, as defined in this Oerdinance, require special zoning in order to protect and preserve the health, safety, and welfare of the County.
- (B) Based on its review of studies conducted in Phoenix, AZ, Garden Grove, CA, Los Angeles, CA, Whittier, CA, Indianapolis, IN, Minneapolis, MN, St. Paul, MN, Cleveland, OH, Oklahoma City, OK, Amarillo, TX, Austin, TX, Beaumont, TX, Houston, TX, Seattle, WA and the findings incorporated in <u>City of Renton v. Playtime Theaters, Inc.</u>, 475 U.S. 41 (1986), <u>Colman A. Young v. American Mini-Theaters, Inc.</u>, 427 U.S. 50 (1976), the Board finds that there is convincing evidence that the secondary effects of Adult-Oriented Establishments include an increased risk of prostitution, high-risk sexual behavior, crime, and other deleterious effects upon existing businesses and surrounding residential areas, and decreased property values.
- (C) The Board intends to control the impact of these secondary effects in order to protect the health, safety, and welfare of the citizenry; protect the citizens from increased crime; preserve the quality of life; preserve the property values and character of surrounding neighborhoods and areas.
- (D) It is not the intent of the Board to suppress any speech activities protected by the First Amendment, but to enact a content-neutral ordinance which addresses the secondary effects of Adult-Oriented Establishments while providing an outlet for First Amendment protected activities
- (E) In order to minimize and control the secondary effects of Adult-Oriented Establishments upon the County, it is the intent of the Board to prevent the concentration of Adult-Oriented Establishments within a certain distance of each other and within a certain distance of other specified locations which are incompatible with and would suffer from the secondary effects of Adult-Oriented Establishments.
- (F) Based upon its review of materials linking alcohol consumption and high-risk sexual behavior and materials linking alcohol consumption and crimes such as sexual assault, the Board finds that a geographic separation of Adult-Oriented Establishments from alcohol beverage licensed premises is warranted.
- (2) LOCATION OF FIRST AMENDMENT PROTECTED ADULT-ORIENTED ESTABLISHMENTS.

- (A) The First Amendment and other provisions of the United States Constitution, as interpreted by the United States Supreme Court and other courts, require that Adult-Oriented Establishments, as defined by this ordinance, are entitled to certain protections, including the opportunity to locate in shorelands and floodlands governed by this ordinance. Therefore, an Adult-Oriented Establishment shall be an allowed use in the A-B, B-4 and Q-1 zoning districts and shall be a prohibited use in any other zoning district. The Adult-Oriented Establishment may locate in the specified Delistricts only if an Adult-Oriented Establishment License has been granted by a town or municipality within the County which is subject to this ordinance, and all the requirements of this Section and the applicable zoning district's regulations are met.
- (B) Adult-Oriented Establishments shall be located at least 1,000 feet from:
 - 1. any residential district line, playground <u>L</u>lot <u>L</u>line, or public park <u>L</u>lot <u>L</u>line;
 - any <u>S</u>-structure used as a <u>R</u>-residence, place of religious worship, public or private school, or "Youth Facility" as defined in the County's Zoning Ordinance;
 - 3. any other Setructure housing an Adult-Oriented Establishment;
 - 4. any Setructure housing an establishment which holds an alcohol beverage license.
- (C) Distance requirements are to be measured in a straight line in any direction regardless of intervening Setructures, from the Setructure housing the Adult-Oriented Establishment to the residential district boundary lines, to the Let Letine of any Letitused for a park, playground, or any Setructure listed in subsection (2)(B)2 through 4 above.
- (D) The measurements from a <u>S</u>-structure shall be taken from the farthest point a <u>S</u>-structure extends in the direction of the measurement, including overhanging roofs or similar projections.
- (E) For Adult-Oriented Establishments located in conjunction with other Beuildings such as in a shopping center, and clearly separate from other establishments, measurements shall be taken from the boundaries of the space occupied by the Adult-Oriented Establishment.
- (F) For any Adult-Oriented Establishment located above ground level in a multi-story <u>S</u>-structure and clearly separate from other establishments within the <u>S</u>-structure, the distance measurements shall be taken from the ground floor public entrance/exit nearest the Adult-Oriented Establishment (excluding emergency exits).
- (G) A licensed Adult-Oriented Establishment is not disqualified from holding an Adult-Oriented Establishment License by the subsequent location of any of the establishments described in <u>subsection</u> (B), above, within <u>one thousand</u> (1,000) feet of the licensed premises after the grant or renewal of its license. This provision applies only to renewal of an existing license and does not apply when an application for a license is submitted after a license for that location has not been renewed or has been revoked.

SECTION 5 C-1 CONSERVANCY DISTRICT

5.01 Use regulations

- (1) Permitted Utses:
 - (A) Grazing.
 - (B) The harvesting of any wild crops such as marsh hay, ferns, moss, berries, tree fruits, and tree seeds
 - (C) Hunting and fishing unless prohibited by other o⊖rdinances or laws.
 - (D) Sustained Yyield Fforestry.
 - (E) Dams and hydro-electric power stations. Said uses must comply with the requirements of Section 6.14(₺5) if located within the FLC District.
 - (F) Telephone, telegraph and power transmission lines. Said uses must comply with the requirements of Section 6.14(E₅) if located within the FLC District.
 - (G) Non-residential buildings used solely in conjunction with the raising of waterfowl, minnows, and other similar animals or fish.
- (2) Specific prohibition: Filling or drainage of Wwetlands, removal of topsoil or peat, or damming or relocating of any watercourse shall not be permitted except with approval of the plan commission and zoning agency.
- (3) Area Regulations:

There are no specific minimum lot size requirements although conservancy/wetland zoned lands that lie within a larger parcel or tract of land, the remainder of which is zoned in any other $\underline{\mathrm{D}}$ elistrict shall have a minimum area required in that non-conservancy district.

(Section 5.01(1)(E) was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

 $(Section\ 5.01(1)(F)\ was\ amended\ by\ Enrolled\ Ordinance\ 170-72,\ effective\ 12/31/15.)$

(Section 5.01(1)(G) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

(Section 5.01(2) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

SECTION 5a C-1 CONSERVANCY OVERLAY DISTRICT

All parameters and requirements of Section 5 C-1 Conservancy District shall apply to lands mapped C-1 Conservancy Overlay District. The underlying base zoning district designation standards shall only be applicable if an in-field determination finds that all or a portion of a property within said overlay district is erroneously mapped. All references to the C-1 District or C-1 Conservancy District within this Ordinance shall also apply to the C-1 Conservancy Overlay District.

(Section 5a was created by Enrolled Ordinance 170-72, effective 12/31/15.)

SECTION 6 FLC FARMLAND CONSERVANCY DISTRICT

6.01 Purpose and intent

This $\underline{\mathbb{D}}$ -district is intended to apply to those areas that are designated on the Comprehensive Development Plan for Waukesha County for Farmland Preservation and which are presently in $\underline{\mathbb{A}}$ -agricultural $\underline{\mathbb{U}}$ -use by virtue of either cultivation, pasture or in some other way, and which if they were not being used for agricultural purposes would be classified as conservancy lands due to inherent wet soil characteristics and/or the presence of natural vegetation indicative of wet soils. The intent of the $\underline{\mathbb{D}}$ -district is to preserve and maintain $\underline{\mathbb{A}}$ -agricultural $\underline{\mathbb{U}}$ -uses on lands suited for such purposes. They often include lands poorly suited for urban or suburban development while being particularly well suited for some types of $\underline{\mathbb{A}}$ -agricultural $\underline{\mathbb{U}}$ -use.

In this $\underline{\mathbb{D}}$ district, $\underline{\mathbb{S}}$ structures related to farm operations, including existing dwellings, are deemed consistent with the purpose of this section where the location of $\underline{\mathbb{B}}$ buildings associated with the permitted agricultural operation is found to conform with health, sanitation and safety provisions of this and any other state regulation or local ordinance. Determination of such suitability shall be evidenced by on-site examination and evaluation. The intent for mapping purposes is that lands within this $\underline{\mathbb{D}}$ district shall have exhibited those $\underline{\mathbb{A}}$ egricultural $\underline{\mathbb{D}}$ esses in the past. It is not the intent of this section to promote or permit the conversion of $\underline{\mathbb{W}}$ evetlands. If a new $\underline{\mathbb{L}}$ tot of less than 35 acres is proposed and a portion of the lands to be included in the $\underline{\mathbb{L}}$ tot $\underline{\mathbb{A}}$ erea are zoned FLC District, said lands may only be included within the $\underline{\mathbb{L}}$ tot $\underline{\mathbb{A}}$ erea if the proposal complies with the siting, density, area, etc. parameters of the FLP District.

6.02 Use regulations: Permitted Uuses

- (1) Any uses and Setructures permitted in the C-1 Conservancy Deistrict and if located in a Wwetland, the provisions of Section 5 shall apply.
- (2) Agricultural Uses, as defined within this Ordinance, except Far and Ppig Farms and Ppoultry and/or egg production which require Conditional Use authorization pursuant to Section 6 C.4. Such uses shall not fill or convert Wwetlands or floodplains.
- (3) Agricultural Accessory Uses including existing single-family dwellings that existed on January 1, 2014 and shelters for housing animals that comply with Section 2.02 (12) of this Ordinance or permitted as an appurtenance to a Farm Residence, except that no Setructure shall be located in a Wwetland or upon lands not suited due to soil limitations.
- (4) Nurseries, greenhouses and hatcheries limiting the retail sales of such product to that which is produced by the farm operator, subject to review and approval of a Site Plan and Plan of Operation by the plan commission and the Zoning Administrator in accordance with Section 3.03(6) of this Ordinance.
- (5) Road-side \underline{S} stands, subject to the provisions of Section 6.14($\underline{B2}$)($\underline{5E}$).
- (6) Signs not to exceed forty (40) feet in area displaying the name of the Ffarm or farm organization.

6.03 Conditional uses

Conditional uses, as provided in Section $\frac{4(g)3.08(7)}{2}$ and listed below, and in accordance with the procedural requirements of Section $\frac{4(g)3.08(7)}{2}$ and the provisions of Section 6.15:

- (1) Landing Fields and Take Off Strips serving agricultural or municipal uses.
- (2) Animal Hospitals and Veterinarian Clinics; and Commercial Dog Kennels but only if they comply with the Farm Family Business provisions of ATCP 49.
- (3) Commercial Truck Parking, except that such use may be allowed but only if incidental to and compatible with the continued long term Angricultural Unse of the lands as determined by the Town Plan Commission and the County Zoning Administrator and comply with the Farm Family Business provisions of ATCP 49.
- (4) Fur Farms, Pig Farms, Creameries, Condensories, Commercial or Custom Grain Drying Operations and Poultry and/or Egg Production.
- (5) Existing non-metallic mineral extraction or Qquarrying (as defined in this Ordinance), except that such use may be allowed only if incidental to and compatible with the continued long term Aagricultural Uase of the lands which make up the major portion of lands in the FLC or FLP Districts (i.e., sand and gravel removal on non-productive lands, for example).
- (6) Private Clubs and Resorts (including commercial Behoarding Setables), except that such use may be allowed only if incidental to and compatible with the continued long term Aegricultural Uese of the lands (i.e., private hunt clubs during the non-growing season, for example).
- (7) Land Aaltering Aactivities in accordance with the requirements of Section 3.08(7)(AA), provided such activities do not negatively affect the long-term suitability of the lands for agricultural purposes.
- (8) Limited Family Businesses, as provided for and in accordance with all parameters of Section 3.08(7)(KK). Said uses must comply with the Farm Family Business provisions of ATCP 49
- (9) In-law <u>U</u>units, pursuant to Section 3.08(7)(Z), provided that the density requirements of the Farmland Preservation Plan are complied with.
- (10) Other uses, situations, or nonfarm type businesses not specifically provided for in this conditional use section and which may be determined to be acceptable under the provisions of Section 6.15 and in the judgment of the Town Plan Commission and County Zoning Agency, meet the intent of a conditional use as set forth in Section 3.08(1) and comply with the Farm Family Business provisions of ATCP 49, also referred to as an Unspecified Conditional Use in this Ordinance.

6.04 **Building location**

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, unless measured from a Local Road, in which case, the setback is (Thirty-five (35) feet minimum.
 - B) Additional regulations and exceptions from Section 3.09(1) apply.

- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- $(\frac{23}{})$ Offset:
 - (A) Twenty (20) feet minimum, unless otherwise excepted in this Ordinance.
 - (B) Buildings that house animals must be fifty (50) feet minimum.
 - (C) Additional regulations and exceptions from Section 3.09(3) apply.

6.05 **Height regulations**

- (1) Residential buildings:
 - (A) Residential Use Structure: Thirty five (35) feet maximum The regulations and

exceptions of Section 3.10(1) apply.

- (B) Accessory Building: Twenty (20) feet maximum.
- (2) <u>Farm buildings</u>:
 - (A) Sixty (60) feet maximum.
 - (B) Farm buildings may be increased to not more than one hundred (100) feet where the Rroad-setback, C-1 Conservancy and Wetland setback-Setbacks and offset Offset all equal or exceed the height of the structure.
- (3) Additional regulations and exceptions from (C) Refer to Section 3.10 of this Ordinance for additional height regulations apply.

6.06 Area regulations

- (1) Floor areaArea and Building Footprint: Minimum required for single family dwelling where permitted.
 - (A) Minimum Floor Area required for Single-Family Dwelling where permitted:
 - 1. First floor: Nine hundred (900)Eight hundred fifty (850) square feet.
 - 2. Total, one (1) family: One thousand Eleven hundred (1,100) square feet.
 - (B) Minimum and maximum parcel size: Parcel Size must comply with the parameters of Section 6.19.
 - (C) Maximum floor area ratioBuilding Footprint permitted: Ten percent (10%) percent, or eleven hundred (1,100) square feet, whichever is greater.

(D) Additional regulations and exceptions from Section 3.11 apply.

6.07 Rezoning lands out of the FLC District

- (1) Except as provided in Section 6(G)(2).07(2), lands may not be rezoned out of the FLC District unless the respective town and the County finds all of the following in writing, after public hearing, as part of the official record of the rezoning:
 - (A) The rezoned land is better suited for a use not allowed in the farmland preservation zoning district.
 - (B) The rezoning is consistent with any applicable comprehensive plan.
 - (C) The rezoning is substantially consistent with the Waukesha County Farmland Preservation Plan, which is in effect at the time of the rezoning.
 - (D) The rezoning will not substantially impair or limit current or future <u>A</u>agricultural <u>U</u>ase of other protected farmland.
- (2) Subsection 6(G)(1).07(1) does not apply to any of the following:
 - (A) A rezoning that is affirmatively certified by DATCP under Ch. 91 of State Statutes.
 - (B) A rezoning that makes the farmland preservation zoning ordinance map more consistent with the County Farmland Preservation Plan map, certified under ch. 91, Wis. Stats., which is in effect at the time of the rezoning.
- (3) By March 1 of each year, Waukesha County shall provide to DATCP a —report of the number of acres that Waukesha County has rezoned out of the FLC District during the previous year and a map that clearly shows the location of those acres.

(Section 6 was renamed as FLC Farmland Conservancy District and amended by Enrolled Ordinance 170-72, effective 12/31/15.)

SECTION 6.1 FLP FARMLAND PRESERVATION DISTRICT

(Section 6.1 was renamed to FLP Farmland Preservation District by Enrolled Ordinance 170-752, effective 12/31/15.)

6.11 Purpose and intent

The intent and purposes of the FLP Farmland Preservation District are:

- (1) To maintain highly productive agricultural lands in food and fiber production by effectively limiting encroachment of non-agricultural development and minimizing land use conflicts among incompatible uses.
- (2) To maintain a viable agricultural base and associated agricultural supportive uses.
- (3) To protect and preserve the rural landscape.

- (4) To implement the provisions of the Waukesha County Farmland Preservation Plan.
- (5) To comply with the provisions of the Wisconsin Farmland Preservation Law which permits eligible landowners to receive tax credits under Section 71 of the Wisconsin State Statutes.
- (6) To maintain a use that adds to the economic base of the County.

(Section 6.11 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.12 Lands to be included within the FLP Farmland Preservation District.

Lands that are to be included or mapped within the FLP District are limited to those lands that have been designated for farmland preservation in the adopted Waukesha County Farmland Preservation Plan.

(Section 6.12 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.13 Land Uses in the FLP Farmland Preservation District; General.

Only the following land uses are allowed in a Farmland Preservation District:

- (1) Uses allowed under Section 6.14 as a Permitted Use.
- (2) Uses allowed under Section 6.15 with a Conditional Use Permit.
- (3) Legal Nanconforming Uuses, subject to Wisconsin State Statutes.

(Section 6.13 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.14 Use Regulations: Permitted Uses

- Agricultural Uses as defined in this Ordinance except Fur and Ppig Farms and Ppoultry and/or egg production which require Conditional Use authorization pursuant to Section 6.15(3)(F) C.6.
- (2) Agricultural Accessory Uses as defined in this Ordinance and subject to the following requirements:
 - (A) Caretaker's quarters/living unit Farm Residence if the unit is within 200 feet of the existing cluster of farm buildings, is served by a common driveway, and is intended and necessary for the farm operation and provides a living unit or quarters for hired employees of the farming operation and their immediate Family. Only one Farm Residence is permitted on a Llot. An In-law Unit requires a conditional use permit.
 - (B) Home Oeccupations as regulated in Section 7.01(F6) of this Ordinance if said particular use complies with the farm family business provisions as specified by rule by the Wisconsin Department of Agriculture, Trade and Consumer Protection (DATCP).
 - (C) Private Hhobby Kkennels as regulated in Section 7.01(19) of this Ordinance if said particular use complies with the farm family business provisions as specified by rule

by DATCP.

- (D) Farm buildings housing animals, barnyards, and feedlots that are not located within a floodland, nor closer than one hundred (100) feet to any navigable water course, nor closer than one hundred (100) feet to an existing adjacent dwelling.
- (E) Roads-Side Stands.
 - Temporary <u>R</u>road-side <u>S</u>rtand structures shall be no more than 100 square feet in size.
 - 2. Off-street parking for a minimum of five (5) vehicles must be provided and there shall be no parking within the right-of-way of the public road.
 - 3. No such stand shall be closer than thirty (30) feet to the <u>B</u>base <u>S</u>setback <u>L</u>line or closer than twenty (20) feet to any <u>L</u>lot <u>L</u>line.
 - 4. Only produce and farm products can be displayed for sale.
 - Road-side Setands with a permanent Beuilding shall require Site Plan and Plan of Operation approval in accordance with Section 3.03(6) of this Ordinance and shall comply with all size and locational requirements of the zoning district in which a stand is located.
- (F) Nurseries, orchards, greenhouses/Hhorticulture/floriculture, viticulture, apiculture, forestry, and hatcheries limiting the retail sales of such product to that which is produced on the premises by the farm operator. Commercial or wholesale nurseries must obtain Site Plan/Plan of Operation in accordance with the requirements of Section 3.03(6).
- (G) Signs not to exceed forty (40) feet in area displaying the name of the Ffarm or farm organization.
- (3) Agriculture-related uses as defined in this Ordinance and subject to the requirements of Chapter 91 of the Wisconsin Statutes and subject to the review and approval of a Site Plan and Plan of Operation by the Plan Commission and the Zoning Administrator in accordance with Section 3.03(6) of this Ordinance.
- (4) Pre-existing Nonfarm Residences that existed as of January 1, 2014 and Farm Residences that existed as of May 31, 2015.
- (5) A transportation, communication, utility (electric, gas, telephone, cable, fiber optic, water, sewer, etc.) transmission, distribution, or pipeline, drainage, or other use that is required under state or federal law to be located in a specific place or that is authorized to be located in a specific place under a state or federal law that pre-empts the requirement for a Conditional Use Permit for that use as outlined in Section 6.15(€3)(3C) below.
- (6) Legal N=non-conforming U=uses.
- (7) Other uses identified by DATCP rule and which are deemed consistent with the stated purpose and intent of this District subject to approval of the Town Plan Commission and the Zoning Administrator. The Zoning Administrator shall make a determination as to whether such uses must obtain Conditional Use approval for unspecified uses.

(Section 6.14 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.15 Use Regulations: Conditional Uses

- (1) Conditional uses as provided for in Section 3.08 and Section 6.15(€3) and pursuant to the procedural requirements of Section 3.08, and if all of the following apply:
 - (A) The use and its location in the FLP District are consistent with the purposes and intent of the FLP District.
 - (B) The use and its location in the FLP District are reasonable and appropriate, considering alternative locations, or are specifically approved under state or federal law
 - (C) The use is reasonably designed to minimize the conversion of land, at and around the site of the use, from Aagricultural Uase or Oppen Space use.
 - (D) The use does not substantially impair or limit the current or future Agricultural Utse of surrounding parcels of land that are zoned for or legally restricted to Agricultural Utse.
 - (E) Construction damage to land remaining in <u>A</u>*gricultural <u>U</u>*se is minimized and repaired to the extent feasible.
 - (F) The use does not conflict with surrounding land uses.

The following additional standards apply to Non-Metallic Mineral Extraction or Quarrying Conditional Use requests:

- (G) The operation complies with Subchapter I of Chapter 295, Wisconsin Statutes, and rules promulgated under that subchapter, with applicable provisions of local ordinances under Wis. Stat. § 295.13 or Wis. Stat. § 295.14 (including all applicable provisions of this Ordinance), and with any applicable requirements of the Department of Transportation concerning the restoration of nonmetallic mining sites.
- (H) The owner agrees to restore the land to ∆agricultural Uase, consistent with any required reclamation plan, when extraction is completed.
- (I) The requirements of 3.08(7)(S) of the Ordinance shall be met.
- (2) Prior to the issuance of a Conditional Use Permit for an approved Conditional Use in the FLP District, any requirements listed for an individual Conditional Use under Section 3.08(7), in Section 6.15 of the FLP District, or imposed as part of the Conditional Use approval must first be satisfied.
- (3) The list of Conditional Uses that may be applied for within the FLP District is as follows:
 - (A) Government, nonprofit community uses, institutional, <u>B</u>-buildings for religious assembly, cemeteries and mausoleums for the burial of human remains only, and other <u>P</u>-public and <u>S</u>-semi-public <u>B</u>-buildings and uses – as defined in this Ordinance.

- (B) Non-Metallic Mineral Extraction or Quarrying (as defined in this Ordinance), except that such use may be allowed only if incidental to and compatible with the continued long term Aegricultural Uesse of the lands (i.e., sand and gravel removal on non-productive lands, for example).
- (C) Transportation, communication, utility (electric, gas, telephone, cable, fiber optic, water, sewer, etc.) transmission, distribution, or pipeline, drainage, or other uses not allowed as a Permitted Uuse in Section 6.14(E5) above and in accordance with Chapter 91 of the Wisconsin Statutes.
- (D) Animal Hospitals and Veterinarian Clinics; and Commercial Dog Kennels but only if they comply with the Farm Family Business provisions of ATCP 49.
- (E) Commercial Truck Parking, except that such use may be allowed but only if incidental to and compatible with the continued long term Aagricultural Uase of the lands as determined by the Town Plan Commission and the County Zoning Administrator and comply with the Farm Family Business provisions of ATCP 49.
- (F) Fur Farms, Pig Farms, Creameries, Condenseries, Commercial or Custom Grain Drying Operations and Poultry and/or Egg Production.
- (G) Landing Fields and Take Off Strips serving agricultural or municipal uses.
- (H) Private Clubs and Resorts (including commercial Beharding Setables), except that such use may be allowed only if incidental to and compatible with the continued long term Aagricultural Uase of the lands (i.e., private hunt clubs during the nongrowing season, for example).
- (I) Land <u>A</u>eltering <u>A</u>ectivities in accordance with the requirements of Section 3.08(7)(AA), provided such activities do not negatively affect the long-term suitability of the lands for agricultural purposes.
- (J) Limited Family Businesses, as provided for and in accordance with all parameters of Section 3.08(7)(KK). Said uses must comply with the Farm Family Business provisions of ATCP 49.
- (K) In-law Umnits, pursuant to Section 3.08(7)(Z), provided that the density requirements of the Farmland Preservation Plan are complied with.
- (L) Other uses, situations, or nonfarm type businesses not specifically provided for in this conditional use section and which may be determined to be acceptable under the provisions of Section 6.15 and in the judgment of the Town Plan Commission and County Zoning Agency, meet the intent of a conditional use as set forth in Section 3.08(1) and comply with the Farm Family Business provisions of ATCP 49, also referred to as an Unspecified Conditional Use in this Ordinance.

(Section 6.15 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.16 **Building Location**

Residential use structures must comply with the requirements of Section 6.19 and <u>S</u>etructures are subject to the following locational requirements:

(1) Road Setback:

(A) Residential Use Structure: ThirtyFifty (50) five (35) feet minimum, unless

measured from a Local Road, in which case, the setback is thirty-five (35) feet minimum.otherwise

in this Ordinance.

(B) Accessory or Farm Building: Fifty (50) feet minimum unless measured from a

Local Road, in which case, the setback is tarbirty-five (35) feet minimum, unless

excepted in this Ordinance.

———Buildings

that house animals must be fifty (50) feet minimum.

(C) Additional regulations and exceptions from Section 3.09(1) apply.

(2) Wetland Setback:

(A) Seventy-five (75) feet minimum.

(B) Additional regulations and exceptions from Section 3.09(2) apply.

 $(\frac{23}{})$ Offset:

(A) Residential Use Structure: Twenty (20) feet minimum, unless otherwise

excepted in this Ordinance.

(B) Accessory or Farm Building: Twenty (20) feet minimum, unless otherwise

excepted in this Ordinance. Buildings that house animals must be fifty (50) feet minimum.

(C) Additional regulations and exceptions from Section 3.09(3) apply.

(3) <u>C-1 Conservancy Setback</u>: Seventy-five (75) feet, unless otherwise excepted in this Ordinance.

(Section 6.16 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.17 **Height Regulations**

(1) Residential buildings:

(A) Residence: Thirty five (35) feet maximum The regulations and

exceptions of Section 3.10(1) apply.

- (B) Accessory: Twenty (20) feet maximum.
- (2) Farm buildings:
 - (A) Sixty (60) feet maximum.
 - (B) Farm buildings may be increased to not more than one hundred (100) feet where the <u>Rroad Setback, C-lWetland setbackSetback</u>, and <u>offset Offset</u> all equal or exceed the height of the <u>structure</u>Structure.
- (3) Refer to Additional regulations and exceptions from Section 3.10 of this Ordinance for additional height regulations apply.

(Section 6.17 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.18 Area and Building Footprint Regulations

- (1) Floor area, mMinimum Floor Area required for Single-family Dwelling, where permitted:
 - (A) First Floor: Eight hundred fifty (850) square feet.

(A)(B) Total: Eleven hundred (1,100) square feet. Minimum first floor—nine hundred (900)

square feet. Total floor area—one thousand—one hundred (1,100)

square feet.

- (2) <u>Maximum floor area ratio</u>Building Footprint permitted: Ten <u>percent</u> (10%) percent, or eleven hundred (1,100) square feet, whichever is greater.
 - (3) Additional regulations and exceptions from Section 3.11 apply.

(Section 6.18 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.19 New Residences and Lots

New Residences and new Laots or parcels of less than thirty-five (35) acres shall be prohibited on lands zoned FLP District and shall only be authorized if in accordance with the following requirements:

(1) Rezoning required. New Residences and new Lats or parcels of less than thirty-five (35) acres in area are not permitted within the FLP District without the benefit of rezoning. If a new Residence or Lator of less than thirty-five (35) acres is proposed for lands currently zoned FLP District, the land must first be rezoned to the R-1 Residential District where farm or Neonfarm Residences are a Permitted Uese. Lands to be rezoned must comply with the density parameters of the Comprehensive Development Plan for Waukesha County that are described in detail in Section 6.19(B2) below. Prior to submitting an application to rezone lands currently zoned FLP District, petitioners shall participate in a concept review meeting to be held with the respective town Planner and Waukesha County Planning & Zoning Staff to discuss proposed density and lot siting and compliance with the below stated requirements of this section.

If a Lłot of less than 35 acres is permitted via the rezoning process, the remnant lands can be less than 35 acres in area provided that a deed restriction is recorded against said lands prohibiting construction of Residences or nonfarm buildings.

New Nonfarm Residences must also comply with the standards set forth in Chapter 91 of the Wisconsin Statutes.

- (2) <u>Density.</u> A maximum density of one (1) dwelling unit per thirty-five (35) acres shall be permitted for lands designated for Farmland Preservation on the adopted Comprehensive Development Plan for Waukesha County. Existing dwelling units and land divisions that have taken place after the dates specified below shall be used in computing available density. If part of a parcel is within the County's shoreland jurisdictional area, the entire property's acreage, number of existing dwelling units and prior land divisions from <u>P</u>parent Parcels shall be considered in determining available density.
 - (A) Density Considerations- land divisions after January 1, 1997: New Lates or parcels of less than 35 acres that were created from a Parent Parcel or Parcels that comprised a Farm, as it existed on January 1, 1997, and that were located on lands designated "Agricultural Preservation" or "Farmland Preservation" at the time of land division on the Comprehensive Plan for Waukesha County, shall be counted in determining the available density or "development rights" Development Rights remaining for a Farm as it was configured on May 31, 2015. The number of available Development Rights shall be reduced by one Development Fight for each such Late that was created after January 1, 1997. Farm boundaries, as of May 31, 2015, have been mapped on the "Farm Tracking Unit" layer on the Waukesha County GIS website in order to make available density information readily available. Density tracking is further described in Section 6.19(B)(4).

Example: 105 acre Ffarm comprised of two parcels in the same ownership.

<u>Step 1- 35 Acre Density Calculation</u> = 105 acres/35 = 3 (Maximum number of dwelling units before consideration of existing dwelling units and recent land divisions).

Step 2- Account for existing dwelling units and land divisions that created parcels of less than 35 acres after January 1, 1997: The Ffarm contains one house. (counts as one dwelling unit) and a Ltot of less than 35 acres was split from the Ffarm by Certified Survey Map in 2001 (counts as second available dwelling unit) = total of 2.

Step 3- Subtract total of Step 2 from Step 1 to adjust for existing dwelling units and parcels of less than 35 acres created since January 1, 1997. (3 minus 2= 1).

Summary- Available dwelling units/Development R#ights: Farm is entitled to one additional dwelling unit or D\(\frac{1}{2}\)evelopment R#ight.

(B) Density Exception for Legal Lots of Record that existed on May 31, 2015: Existing legal L₁ots of R₂ecord as of May 31, 2015 that are less than thirty-five (35) acres in size shall be entitled to one (1) dwelling unit if a dwelling unit does not already exist on the parcel, with the following exceptions:

- If new Lłots or dwelling units have been created from a Pparent Pparcel or
 Ffarm after 1997 without the benefit of a comprehensive development plan
 amendment from the Farmland Preservation category to another appropriate
 land use category, and thirty-five (35) acre density cannot be maintained
 with the addition of another dwelling unit, then no additional dwelling units
 are permitted.
- If a prior imposed rezoning condition, deed restriction, conveyance, or some other official action prohibiting future land splits or dwelling units exists, then no additional dwelling units shall be permitted on said existing legal <u>L</u>lot of <u>R</u>+ecord.
- (C) Review of Land Divisions. All land divisions, including transfers of adjacent land, that are proposed in towns that are subject to the Waukesha County Zoning Code and involve land that is in the planned "Farmland Preservation" category of the Comprehensive Development Plan for Waukesha County shall be reviewed and approved by the respective town and Waukesha County, regardless of whether the parcel contains shoreland jurisdiction, so that Development Plan density compliance can be ensured and tracked over time.

Each <u>Rresidence</u> that is permitted shall be placed on a separately described parcel created in conformance with the town and County Comprehensive Development Plans, the Farmland Preservation Plan, the minor land division regulations of the town in which they are located, this Ordinance, and the Waukesha County Shoreland Floodland Subdivision Control Ordinance (Appendix D), as applicable.

(D) <u>Density Tracking</u>. Available density or dwelling units are tracked by a mapping layer on the Waukesha County Geographic Information System. Each Ffarm consisting of one or more Ceontiguous parcels that were owned by a common owner or owners as of May 31, 2015 have been assigned a "Farm Ttacking Uenit" name and number. Farm Tracking Units have been created to track the number of Liots or dwelling units (Delevelopment Reights) that a Ffarm or farm owner is entitled to when applying the density considerations of Section 6.19(B)(1) and (2)(A) & (B).

Each time that a new dwelling unit or Lłot is created in the future, in accordance with the standards of Section 6.19, the Farm Tracking Unit data will be updated on the Waukesha County GIS. In addition, a deed restriction must be recorded against the land to disclose the remaining density available to a given Farm Tracking Unit.

(E) <u>Density Transfer</u>. Transfer of density rights from one Farm Tracking Unit to another Farm Tracking Unit or property must be approved by the respective town and Waukesha County Zoning Administrator and will be tracked on the Farm Taracking Uanit Waukesha County GIS layer. A deed restriction must be recorded against the land to disclose the density transfer.

(3) Siting Standards.

Lands that are zoned FLP but that are proposed to be rezoned to the R-1 District to accommodate new N+nonfarm R-residences must comply with the following siting standards. Compliance with siting standards shall be considered by the town and Waukesha County as part of the rezoning review process.

- (A) New <u>R</u>residences or <u>L</u>lots shall be located on uncultivated lands to the greatest extent practicable.
- (B) New Residences or Lators shall be clustered together to the greatest extent practicable.
- (C) New Residences or Letots shall be located on non-prime (non-Class I and II) soils to the greatest extent practicable.
- (D) New Residences or Liots may be permitted within upland Environmental Corridor areas that are zoned FLP District with an EC Overlay District designation provided that the area to be disturbed is rezoned to the R-1 District and provided that the respective town and County have made a determination that alternative building sites located outside of the Eenvironmental Ceorridor and cultivated lands are not available. If such a determination is made, the maximum area of Environmental Corridor disturbance shall be 15,000 square feet per Liot, inclusive of drive areas, septic sites, building sites and any other area to be disturbed. In addition, any authorized disturbance within the Environmental Corridor shall comply with County Comprehensive Development Plan recommendations which call for no more than one dwelling unit per five acres of upland area. A deed restriction shall be recorded in the office of the Register of Deeds identifying and describing the permitted area of Environmental Corridor disturbance prior to Zoning Permit issuance.
- (E) Lots shall be located near existing R-oads to the extent practicable with consideration of the above stated criteria.
- (4-) Lot Size requirements for Lots created by rezoning from the FLP District to the R-1 District
 - (A) Minimum parcel size, one (1) acre.
 - (B) Minimum average width for parcels, one hundred and fifty (150) feet.
 - (C) Maximum parcel size, three (3) acres, except as may be provided in Section 6.19(£5) below for those residual existing dwellings and parcels that result due to Farm Consolidation.
- (5-) Lot Size for Farm Consolidations created by rezoning from the FLP District to the R-1 District
 - (A) Minimum parcel size, one (1) acre.
 - (B) Minimum average width: One hundred and fifty (150) feet.
 - (C) Maximum parcel size, five (5) acres.

(Section 6.19 was created by Enrolled Ordinance 170-72, effective 12/31/15.)

6.19a. Rezoning Land Out of the FLP District

- (1) Except as provided in Section 6.19a(2), lands may not be rezoned out of the FLP District unless the respective town and the County finds all of the following in writing, after public hearing, as part of the official record of the rezoning:
 - (A) The rezoned land is better suited for a use not allowed in the farmland preservation zoning district.
 - (B) The rezoning is consistent with any applicable comprehensive plan.
 - (C) The rezoning is substantially consistent with the County Farmland Preservation Plan, which is in effect at the time of the rezoning.
 - (D) The rezoning will not substantially impair or limit current or future Angricultural Unse of other protected farmland.
- (2) Subsection 6.19a(1) does not apply to any of the following:
 - (A) A rezoning that is affirmatively certified by DATCP under Ch. 91 of State Statutes.
 - (B) A rezoning that makes the farmland preservation zoning ordinance map more consistent with the County Farmland Preservation Plan map, certified under ch. 91, Wis. Stats., which is in effect at the time of the rezoning.
- (3) By March 1 of each year, Waukesha County shall provide to DATCP a report of the number of acres that Waukesha County has rezoned out of the FLP District during the previous year and a map that clearly shows the location of those acres.

(Section 6.19a was created by Enrolled Ordinance 170-72, effective 12/31/15.)

SECTION 6.2 A-B AGRICULTURAL BUSINESS DISTRICT

6.21 Purpose

The primary purpose of this $\underline{\mathbb{D}}$ district is to maintain, encourage and promote agriculturally related business endeavors on appropriate lands within the community. Such endeavors properly located and regulated serve to support and enhance the viability of agriculture as an economic activity.

For mapping purposes, it! is the intent of this Ordinance that suitable areas be described to provide for buffering from adjacent uses and that the minimum size of any proposed establishment of the A-B Delistrict be five (5) acres in extent. Existing uses which may come under the A-B Aegricultural Beusiness Delistrict shall be considered on a case_-by_-case basis and may be less than five (5) acres, with the plan commission making a determination as to compatibility with the existing site and the surrounding or adjacent uses.

6.22 Permitted Uuses

All the following uses permitted by right in the A-B Agricultural Business District are subject to Site Plan and Plan of Operation approval of the plan commission and zoning administrator:

(1)A. Warehousing, transfer and transport services of agricultural commodities.

- (2)B- Horticultural services, including the retail sale of nursery landscape material and other agricultural crops and related commodities.
- (3)C. Feed milling operations.
- (4)D. Agricultural machinery sales and services.
- (5)E. Cheese factories.
- (6) F. Bulk milk collection, storage and distribution facilities.
- (7)G. Veterinarian services.
- (8)H. Custom grain drying.
- (9)1. Poultry and/or egg production.
- (11)K. Any other use consistent with stated intent of this Delistrict subject to approval of the plan commission and zoning administrator.

(Section 6.22 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

6.23 Conditional uses

Conditional uses as provided in Sections 3.08(7)(A), 3.08(7)(D), 3.08(7)(E), 3.08(7)(F), 3.08(7)(G), 3.08(7)(I), 3.08(7)(J), 3.08(7)(K), 3.08(7)(K), 3.08(7)(K), 3.08(7)(K), 3.08(7)(K), 3.08(7)(K), 3.08(7)(K), and 3.08(7)(K).

6.24 Building locations

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.

(23) Offset:

- (A) Buildings used for commercial purposes which include the housing of <u>L</u>tivestock, one hundred (100) feet minimum unless adjacent <u>D</u>district is the FLP, A-B, A O or FLC <u>D</u>districts, in which case twenty (20) feet minimum shall apply.
- (B) Buildings used for commercial purposes not involving livestock housing or animal waste storage, ten (10) feet minimum.
- (C) The integrated site plan will relate B-buildings, parking areas and any loading dock facilities that may be necessary and accessory to the use and shall be governed by suitable contemporary design criteria.
- (D) Additional regulations and exceptions from Section 3.09(3) apply.

(Section 6.24(2)(A) was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.25 Height regulations

- Principal Bbuilding: Thirty-five (35) feet maximumThe regulations and exceptions of Section 3.10(1) apply.
- (2) Accessory Bbuilding: Sixty (60) feet maximum, except that both Perincipal and Accessory Bbuildings may be increased to more than one hundred (100) feet when the Road and Wetland setback Setbacks and offset Offset equals or exceeds the height of the structure Structure.
- (3) Additional regulations and exceptions from Section 3.10 apply.

6.26 Area regulations

- (1) Floor area Area and Building Footprint: Minimum required.
 - (A) Minimum Floor Area required for residential purposes Single-family Dwelling: Nine hundred (900) square feet per dwelling unit.
 - 1. First floor: Eight hundred fifty (850) square feet.
 - 2. Total: Eleven hundred (1,100) square feet.
 - (B) Maximum floor area ratioBuilding Footprint: Fifty percent (50%) percent of the site, or eleven hundred (1,100) square feet, whichever is greater.
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) <u>Lot size</u>:
 - (A) Minimum area: Five (5) acres, unless the plan commission determines that an existing use or a smaller parcel is appropriate and consistent with Section 6.21.
 - (B) Minimum average width, three hundred (300) feet.

SECTION 6.3 A-O EXISTING AGRICULTURAL OVERLAY DISTRICT

6.31 Purpose

The purpose of this district is to allow for the continued agricultural use of land while recognizing that other land uses of a rural or semi-rural nature other than farming or agricultural may be needed in the general area. It is anticipated that the assignment of this overlay district to specific parcels of land will provide a greater degree of freedom for farm operators and for town plan commissions, town boards and the county zoning agency in dealing with situations where present owners are committed to continuing the agricultural use and the potential of incompatibility is present. The basic intent of the district is similar to that upon which conditional uses in this Ordinance are premised. This district will grant the uses permitted in the FLP district as well as the uses of the underlying basic district. (Reserved)

(Section 6.31 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

SECTION 6.4 A-T AGRICULTURAL TRANSITION DISTRICT

6.41 Purpose and intent

This Delistrict is intended to reflect the transitional nature of lands that are currently in agricultural or open space use, but are planned for and are likely to be developed for other land uses over time.

(Section 6.41 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

$6.42\,$ Land to be included with A-T Agricultural Transition District

- (1) Lands used for agricultural purposes.
- (2) Vacant lands consisting of fallow or natural resource lands.

(Section 6.42 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.43 Use regulations: Permitted Uuses

Any Ppermitted Uuse as described in the A-1 Agricultural District.

(Section 6.43 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.44 Conditional uses

Conditional uses as provided in Sections 3.08(7) A, AA, B, D, E, F, G, I, K, KK, Q, R, S, T W, X, Y and Z.

(Section 6.44 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

Commented [BA62]: There are no zoned A-O lands within the zoning code jurisdictional limits.

6.45 Building location

- (1) Road Setback:
 - (A) Residential Use Structure: <u>Fifty (50) feet minimum, unless measured from a Local Road, in which case, the setback is t</u>Thirty-five (35) feet minimum, <u>unless otherwise excepted in this Ordinance</u>.
 - (B) Accessory or Farm Building: Fifty (50) feet minimum, unless measured from a Local Road, in which case, the setback is tThirty-five (35) feet minimum, unless otherwise excepted in this Ordinance. Buildings that house animals must be fifty (50) feet minimum.
 - (C) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- (23) Offset:
 - (A) Residential Use Structure: Twenty (20) feet minimum, unless otherwise excepted in this Ordinance.
 - (B) Accessory or Farm Building: Twenty (20) feet minimum, unless otherwise excepted in this Ordinance. Buildings that house animals must be fifty (50) feet minimum.
 - (C) Additional regulations and exceptions from Section 3.09(3) apply.
- (3) <u>C 1 Conservancy Setback:</u> Seventy five (75) feet, unless otherwise excepted in this Ordinance. All accessory buildings must be seventy five (75) feet minimum.

(Section 6.45 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.46 **Height regulations**

(1) Residential buildings:

(A) Residence: Thirty five (35) feet maximum The regulations and

exceptions of Section 3.10(1) apply.

(B) Accessory: Twenty (20) feet maximum.

- (2) <u>Farm buildings</u>:
 - (A) Sixty (60) feet maximum.
 - (B) Farm buildings may be increased to not more than one hundred (100) feet where the

109

Effective 05-xx-2016

roadRoad and Wetland setbacks, C. 1 setback, and offset Offset all equal or exceed the height of the structure.

(3) Refer to Additional regulations and exceptions from Section 3.10 of this Ordinance for additional height regulationsapply.

(Section 6.46 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.47 Area regulations

- (1) Minimum Floor Aarea, minimum required for Single-family Dwelling:
 - (A) Minimum fFirst floor: nine Eight hundred fifty (900850) square feet.
 - (B) Total: floor area one thousand and one Eleven hundred (1,100) square feet.
- (2) <u>Maximum floor area ratioBuilding Footprint permitted</u>: Ten (10) percent (10%), or eleven hundred (1,100) square feet, whichever is greater.
- (3) Additional regulations and exceptions from Section 3.11 apply.

(Section 6.47 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

6.48 Lot size

- (1) <u>Minimum parcel size</u>: Twenty (20) acres.
- (2) <u>Minimum average width</u>: Three hundred (300) feet.

(Section 6.48 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

SECTION 6.5 AD-10 AGRICULTURAL DENSITY-10

6.51 General Regulations regulations

- (1) Purpose and Intent: The purpose of this ten (10)-acre density zoning Ddistrict is to allow for agricultural and rural use of lands to continue while also allowing for clustered development on lands located in rural or semi-rural areas. Additional stated purposes of the Ddistrict are as follows:
 - (A) Promote the preservation of the rural character of the towns by encouraging farm fields, pastures, orchards, and natural Oopen Sepaces to be retained either as Ceommon Oopen Sepaces, or as part of a farm operation.
 - (B) ATo achieve the optimum residential environment while recognizing the rural character of towns. The density transfer technique is designed to permit variable lot sizes in the utilization of the most desirable terrain for housing sites while encouraging preservation of natural resource lands and agricultural lands.
 - (C) This Delistrict allows for the transfer of residential Delevelopment Regists from one area of a parcel to another area of a parcel, thereby allowing an increase in density

Commented [BA63]: Removed the preservation of prime Ag soil requirement.

of development on suitable lands for development in exchange for establishing the preservation of natural resource or agricultural lands known as "preserved lands".

- (2) Review of Proposed Development: Where a development is to occur involving the establishment of "preserved lands," approval by the Plan Commission and the County Zoning Agency shall be required. The development proposed shall conform to the following standards:
 - (A) The shape and arrangement of preserved lands shall be approved by the Plan

 Commission and County Zoning Agency pursuant to the requirements of the AD-10

 District.
 - (B) Lands zoned AD-10 that are proposed to be developed via subdivision plat must be developed in a conservation design format, as detailed in the County Development Plan. Subdivisions shall provide Ceommon Oopen Sepace and conserve natural resource lands in accordance with the guidelines of the County Development Plan relative to development of Rural Development Areas and the Rural Density Conservation Design criteria.
 - (C) The preserved lands shall be retained in one of the following manners:
 - A deed restriction or covenant recorded with the Waukesha County Register
 of Deeds so noting that part or all of the Deevelopment Registres have been
 utilized for the subject land. No additional Deevelopment Registres would
 accrue to that site until such time as it could be served with municipal sewer
 and a zoning change is approved by the Town and County in accordance
 with adopted local and County Land Use Plans.
 - 2. All lot owners within the developed area for which the preserved lands are protected could own an undividable interest in said preserved land.

 Development of those lands may not occur until such time as sewer is available and a zoning change is approved by the Town and County in accordance with adopted local and County Land Use Plans.
 - The preserved lands may be retained in public ownership if a town or the County is willing to accept a dedication or acquire the lands.
 - (D) On a Lot which is zoned AD-10, the development density shall not exceed ten (10) acres for each dwelling unit.
 - (E) In order to preserve the rural character as well as the efficiency and safety of existing road systems, lands to be developed via subdivision plat shall have Llots clustered on interior subdivision streets to minimize Llots being accessed from existing arterials or roadways by individual driveway accesses. The goal of this provision is to encourage grouping of Llots on an interior street which will then access the existing road system.
 - (F) Any land claimed in addition to the actual described residential lots, for credit toward meeting the density factor requirement, shall have its status permanently established and guaranteed either by dedication to the public, by appropriate covenants running with the lands, or by conveyance of agricultural easements. Such covenants and easements shall be recorded in the office of the Register of Deeds and

shall restrict the property against any development or use except as is consistent with its preservation as agricultural land or as a form of Ceommon Oopen Sepace unless sewer becomes available, and the zoning of the property is changed in accordance with adopted local and County Land Use Plans. The preserved land status of any Lot shall be indicated on the official zoning map.

(G) In addition to requiring an appropriate Oθpen Sepace or an agricultural easement on the transferring lands in favor of the town and/or county, covenants shall be placed onin the title of each dwelling unit, giving the owner enforceable rights to prevent the future development of the transferring lands until such time as sewer is available and the subject property is rezoned to allow additional development.

(3) Use Regulations: Permitted Uses:

- (A) Residential:
 - 1. Single-family uses.
 - Duplexes pursuant to issuance of a conditional use permit as required by Section 3.08(7)(N) and compliance with the minimum Floor Area and Building Footprint requirements contained herein.
- (B) Agricultural or Farm Uses on Lots having a minimum of five (5) acres, except on Lots having less than five (5) acres one (1) horse shall be allowed on Lots having a minimum of three (3) acres and there may be one (1) additional horse for each additional one (1) acre thereafter. The keeping of hogs, male goats or Ffur-bearing Aenimals shall not be permitted on less than twenty (20) acres. Those practicing Agricultural or Farm Uses under this section must comply with standard manure disposal practices.
- (C) Accessory Unses and Buildings normally associated with an agricultural operation including Ggarages, stables, and poultry houses. Buildings used for housing animals shall maintain a minimum Onffset of fifty (50) feet from all adjacent Llot Llines.
- (D) Signs:
 - Sign not to exceed twelve (12) square feet in area displaying the name of the Ffarm or farm organization.
 - 2. Subdivision signs in accordance with the sign provisions of this Ordinance.
- (E) Wholesale nurseries, greenhouses and hatcheries, subject to review and approval of a Site Plan and Plan of Operation by the plan commission and the Zoning Administrator in accordance with Section 3.03(6) of this Ordinance.
- (F) Roadside Sstands subject to the following:
 - 1. Off-street parking for a minimum of five (5) vehicles must be provided.
 - 2. No such stands shall be closer than thirty (30) feet to the Bbase Seetback

Lline or closer than twenty (20) feet to any Llot Lline.

- (G) Home Oeccupation and Perofessional Oeffices as regulated herein.
- (H) Hobby Kkennels as regulated in Section 7.01(9).
- (A) Purpose and Intent: The purpose of this zoning district is to protect and encourage the preservation of Prime Agricultural tillable land, (U.S.D.A. Class I and II soils) in minimum twenty (20) acre contiguous areas, to discourage residential development on agriculturally productive and environmentally sensitive areas, provide for some marketability of such lands, to encourage more economical use of lands suited to limited and controlled residential development by permitting more intensive use of such lands without changing the overall rural character of the Town or population density of the Town as set forth in the adopted Land Use Plan. Additional stated purposes of the district are as follows:
 - 1. To transfer residential density opportunities to promote the preservation of the rural character of the Town by encouraging farm fields, pastures, orchards, and natural open spaces to be retained either as common open spaces, or as part of a farm operation known as "agricultural preserved land".
 - 2. To achieve the optimum residential environment while recognizing the rural character of the Town. The density transfer technique is designed to permit variable lot sizes in the utilization of the most desirable terrain for housing sites while encouraging preservation of prime agricultural tillable lands worthy of such preservation.
 - 3. This district encourages the transfer of residential development rights from one area of a parcel to another, from one tract of land to another, and from the RRD 5, AD 10, HG and C 1 districts thereby allowing the increase in density of development on suitable lands for development in exchange for establishing the preservation of more desirable agriculturally productive lands known as "agricultural preserved lands."
 - 4. The transfer of development rights may only take place between the RRD 5, the AD 10, C 1 and HG districts, except that only a maximum of 20% of the transferring land zoned C 1 Conservancy may be counted toward the overall density to be provided for the receiving land.
- (B) Review of Proposed Development Where a development is to occur involving the transfer of development rights and establishment of "preserved lands", approval by the Town Planning Commission and the County Zoning Agency shall be required. The development proposed shall conform to the following standards:
 - 1. The shape and arrangement of preserved lands designated for agricultural use should be consistent with practical requirements for an agricultural activity, and be of a justifiable value for farm use, or as a contribution to the goal of preserving the rural environmental character. The preserved areas must be at least twenty (20) acres of contiguous area, not necessarily on the same parcel, and consist of U.S.D.A. Class Prime or statewide classified Agricultural soils unless a local Land Use Plan has been adopted which further limits the classification to a specific classification of soils, and be tillable without the necessity of removing mature vegetation.
 - Only 20% of the C-1 zoned areas may be used when calculating the overall density. Where
 more than 50% of the site is zoned in the C-1 category, only that amount of acreage up to the

50% amount may be used in the above calculation for purposes of computing allowed density. Where the calculation results in a fraction of .5 or greater, the density may be "rounded up". This rule shall apply only when a local Land Use Plan has been adopted and specifically addresses the issue of crediting such areas for development purposes.

EXAMPLE: 100 acres	— Tract of Land	
	90 acres	Zoned C 1
	10 acres	Zoned AD 10
50% of 90 acres = 45 acres		
20% of 45 acres = 9 acres		
Total qualifying area considered for	= 19 acres	
Density limits	_	
Number of dwelling units allowed	= 1.9 rounded up to 2.	

- 3. The preserved lands shall be retained in one of the following manners:
 - A. Development would occur at the allowable densities with the larger parcels having the building site outside of the agriculturally significant and tillable area and the open area or agricultural lands (preserved lands) could be owned and retained by the party transferring the rights and would be protected through a deed restriction or covenants recorded with the Waukesha County Register of Deeds so noting the part that development rights have been utilized for the subject land. No additional development rights would accrue to that site until such time as it could be served with municipal sewer and a zoning change is approved by the Town and County in accordance with an adopted local Land Use Plan.
 - B. All lot owners within the developed area for which the preserved lands are protected could own an undividable interest in said preserved land. Development of those lands may not occur until such time as sewer is available and a zoning change is approved by the Town and County in accordance with an adopted local Land Use Plan. This can be accomplished without requiring a conditional use for a Planned Unit Development.
 - C. The preserved lands, when noted in the adopted Park and open Space Plan, may be retained in public ownership.
- 4. On a parcel which is zoned AD 10, the development density shall not exceed ten (10) acres for each dwelling unit with credit for the C-1 zoned lands in accordance with Section 6.51(B)2.
- In order to encourage development in areas designated for residential growth on an adopted local Land Use Plan, development rights may be transferred from this zoning district (AD 10) to an RRD 5 district at a rate of 1.2 dwelling units per ten (10) acres.
- 6. In order to preserve the rural character as well as the efficiency and safety of existing road systems, the inappropriate development of lots strung out along such roads with individual driveway accesses from each lot will be minimized. The goal of this provision is to encourage grouping of lots on an interior street which will then access the existing road

system.

- For the purpose of transferring residential development rights, the petitioner shall provide documentation at the time of submittal of the preliminary plat indicating that he is the owner of the subject property or has the authority under the terms of a written contract (offer to Purchase), to make commitments on the transferring land.
- No building intended in whole or part for residential use shall be erected or relocated unless the lot on which it is located meets the required density factor, or has allocated to it, through the transfer program, sufficient additional preserved lands to meet the required density factor for the district in which it is located. Where the total area, or the prorated factor involved includes more than one zoning district, the density factor, as calculated using the entire project, shall apply.
- Any land claimed in addition to the actual described residential lots, for credit toward meeting the density factor requirement, shall have its status permanently established, and guaranteed, either by dedication to the public, or by appropriate covenants running with the lands, in conveyance of agricultural easements. Such covenants and easements shall be recorded in the office of the Register of Deeds and shall restrict the property against any development or use except as is consistent with its preservation as agricultural land or as a form of common open space unless sewer becomes available, and the zoning of the property is changed in accordance with the adopted local Land Use Plan. The preserved land status of any parcel shall be indicated on the official zoning map.
- In addition to requiring an appropriate open space or an agricultural easement on the transferring lands in favor of the town and/or county, covenants shall be placed in the title each dwelling unit, giving the owner enforceable rights to prevent the future development of the transferring lands until such time as sewer is available and the subject property is rezoned to allow additional development.

<u>Use Regulations:</u>					
(1)	Permitted Uses:				
	A	Residential			
		1. Single family uses.			
		2. Only a duplex as a two family residential use pursuant to issuance of a conditional use permit pursuant to Section 3.08(7)(N) and compliance with the floor area requirements contained herein.			
	B	Ordinary farm uses, including dairy, livestock, poultry raising, raising of crops, an truck farming on parcels having a minimum of five (5) acres and subject to the requirements of Section 8.01(1)(A).			
	C.	Accessory uses and buildings normally associated with an agricultural operation including garages, stables, and poultry houses, buildings used for housing animals shall maintain a minimum offset of fifty (50) feet from all adjacent lot lines.			

Signs:

- Sign not to exceed twelve (12) square feet in area displaying the name of the farm or farm organization. Subdivision signs in accordance with the sign provisions of this Ordinance. Wholesale nurseries, greenhouses and hatcheries. Roadside stands subject to the following: Offstreet parking for a minimum of five (5) vehicles shall be permitted. No such stands should be closer than thirty (30) feet to the base setback line or closer than twenty (20) feet to any lot line. Home occupation and professional offices as regulated herein. Hobby kennels as regulated in Section 7.01(I). (Section 6.51(A)3 was amended by Enrolled Ordinance 170-72, effective 12-31-15.) (Section 6.51(A)4 was amended by Enrolled Ordinance 159-69, effective 1-17-05.) (Section 6.51(A)4 was amended by Enrolled Ordinance 170-72, effective 12-31-15.) (Section 6.51(B)2 was amended by Enrolled Ordinance 170-72, effective 12-31-15.) (Section 6.51(B)4 was amended by Enrolled Ordinance 170-72, effective 12-31-15.) (Section 6.51(C)(1)A was amended by Enrolled Ordinance 161-13, effective 09/04/06.) 6.52 **Building** Location **Location** Setback: Fifty (50) feet minimum. Offset: Twenty (20) feet minimum. (2)(1) Road Setback: Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.

Thirty-five (35) feet minimum if the Lot is part of a sSubdivision recorded

Thirty-five (35) feet minimum if the Lot is served by sewer.

Additional regulations and exceptions from Section 3.09(1) apply.

after October 1, 2016.

(3) Offset: (A) Twenty (20) feet minimum Additional regulations and exceptions from Section 3.09(3) apply. 6.53 Height Regulations: The regulations and exceptions of Section 3.10 apply. (1) Principle structure: Thirty-five (35) feet maximum. (2) Accessory Buildings: Farm buildings: Sixty (60) feet maximum. Other accessory buildings: Fifteen (15) feet maximum. 6.54 Area Regulations (1) Floor Area and Building Footprint: (A) Minimum Floor Area for Single-family Dwelling: First floor: Eight hundred fifty (850) square feet. Total: Eleven hundred (1,100) square feet. (B) Two family: Minimum required Ffloor Aarea per Ffamily - Eight hundred fifty (850) square feet per unit. Maximum Building Footprint: Fifteen percent (15%), or eleven hundred (1,100) square feet, whichever is greater. (D) Additional regulations and exceptions from Section 3.11 apply. Floor area: Single family residential: Minimum required first floor—Nine hundred (900) square feet. Total: Fifteen hundred (1,500) square feet. Two family: Minimum required first floor Seven hundred and fifty (750) square feet. Total per family: Fourteen hundred (1,400) square feet. C. Maximum floor area ratio: 15%. (2) Lot size: (A-) Minimum required area - one (1) acre.

Minimum average width - one hundred and fifty (150) feet.

(B)-

- (3) Open space: Thirty thousand (30,000) square feet.
- (43) Density Division Standards-and Lot Size: Development shall not exceed one (1) dwelling unit per ten (10) acres.
 - A. On a parcel which is zoned AD 10, it may be developed at no more than a ten (10) acre density per dwelling unit and no individual lot may be less than one (1) acre nor have less than a minimum average width of one hundred and fifty (150) feet and on open space of thirty thousand (30,000) square feet per family.
 - 1. Only 20% of the C 1 or A E zoned areas may be calculated in the overall density. Where more than 50% of the site is zoned in the C 1 or A E categories, only that amount of acreage up to the 50% amount may be used in the above calculations for purposes of computing allowed density.
 - Residential development shall be allowed on non-prime agricultural soils, (U.S.D.A. Class III and below) and non-tillable or mature vegetated areas consisting of Class I and II soils, unless prime agricultural soils are less than twenty (20) contiguous acres.
 - All farm fields which must be preserved are those which are a minimum of twenty (20) acres in contiguous area and consist of U.S.D.A. Class I and II prime agricultural tillable soils. The twenty (20) acre minimum area must be on the subject parcel or contiguous to prime agricultural tillable areas on an adjacent parcel.
 - B. In any RRD 5 zoned district, development shall occur at a 1.2 dwelling units per ten (10) acres of AD 10 zoned land.
 - Only 20% of the C-1 zoned areas may be calculated in the overall density. Where more than 50% of the site is zoned in the C-1 category, only that amount of acreage up to the 50% amount may be used in the above calculations for purposes of computing allowed density.
 - In the RRD 5 Residential district, development shall only be allowed on non-prime agricultural soils, (U.S.D.A. Class III and below) or Class I and II soils which are not tillable because of natural vegetation, unless prime agricultural soils are less than twenty (20) contiguous acres.
 - 3. All farm fields in the RRD-5 district which must be preserved are those areas which are a minimum of twenty (20) acres in contiguous area and consist of U.S.D.A. Class I and II prime agricultural soils and are tillable. The twenty (20) acre minimum area may be on the subject parcel or contiguous to prime agricultural areas on an adjacent parcel.

(Section 6.54(B)1 was amended by Enrolled Ordinance 170-72, effective 12-31-15.)

SECTION 6.6 A-5 MINI-FARM DISTRICT

6.61 Intent and Purpose

This District is intended to provide for very low-density single-family residential development and the conversion of older farm dwellings to two-family units in predominantly rural areas in order to maintain, to some degree, the agricultural character of the property. These lands are best suited for small farm units, i.e., truck farms, horse farms, hobby farms, orchards and other similar agriculturally-related activities and usually contain a predominance of U.S.D.A. defined statewide significant category soils or prime category soils on parcels which do not qualify for agricultural preservation zoning or in areas which have an existing pattern of scattered or low-density residential development. Such a Delistrict is intended to be used to implement the County or Regional Land Use Plan category entitled "other Agricultural or Rural Land".

6.62 Use Regulations

- (1) <u>Permitted Uses:</u>
 - (A) Any use permitted in the A-1 Agricultural District.
 - (B) Two-family uses in converted farm dwellings existing on the date of adoption of this Ordinance (February 26, 1959) subject to issuance of a Conditional Use Permit contained in Section 3.08(7)(N).
- (2) Permitted Accessory Uses:

Any of those Aaccessory Uases in the EC Environmental Corridor District.

6.63 Building Location

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions for setbacks when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Llot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Llot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.

Setback: Fifty (50) feet minimum.

- (23) Offset:
 - (A) Thirty (30) feet minimum.
 - (B) Not less than fifty (50) feet from an adjacent property line for any Beuilding housing Livestock, Ppoultry or other animals. This does not include doghouses.

(C) Additional regulations and exceptions from Section 3.09(3) apply.

(Section 6.63(2)(B) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

6.64 Height Limitations: The regulations and exceptions of Section 3.10 apply.

- (1) Principal Building: Thirty five (35) feet maximum.
- (2) Accessory Building:
 - (A) Farm: Sixty (60) feet maximum
 - (B) Other: Fifteen (15) feet maximum.

(Section 6.64(1) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

6.65 Area Regulations

- (1) Floor Area and Building Footprint:
 - (A) <u>Minimum Floor Area required for Single-family Dwelling</u>:
 - (1.) First floor: Nine-Eight hundred fifty (900850) square feet.
 - (2.) Total: Fifteen-Eleven hundred (1,500100) square feet.
 - (B) Maximum F.A.R.Building Footprint permitted: Ten percent (10%), or eleven (1,100) square feet, whichever is greater.
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) <u>Lot Size</u>:
 - (A) Minimum area: Five (5) acres.
 - (B) Minimum average width: Three hundred (300) feet.
- (3) Open Space: Four (4) acres.

SECTION 6.7 EC ENVIRONMENTAL CORRIDOR DISTRICT

6.71 **Purpose and Intent**

The EC Environmental Corridor District, as mapped or intended to be mapped, includes non-wetland/floodplain Primary and Secondary Environmental Corridors and Isolated Natural Resource Areas as defined in this Ordinance, and is intended to be used to preserve, protect, enhance, and restore significant woodlands, upland wildlife habitat areas, scenic overlooks, slopes exceeding twelve (12) percent (12%), and upland wooded areas, while also affording an opportunity to use the site for limited residential

Section 6 120

Effective 09-09-2014

purposes, in concert with the goal and intent of the Regional Land Use Plan, Comprehensive Development Plan for Waukesha County, or locally adopted plan, which recommends that residential densities in such areas not exceed one unit per five (5) acres for all parcels which lie entirely within the Eenvironmental Ceorridor. Where questions arise as to the exact location or boundary of an Eenvironmental Ceorridor, the extent and location of such corridors shall be refined and finally determined by infield investigation by the Zoning Administrator or his/her designee, and a notation shall be made on the District Zoning Map of the Waukesha County Zoning Code indicating that such a determination has been made for future reference and map amendment purposes.

6.72 Use Regulations

- (1) <u>Permitted Uses:</u>
 - (A) Any uses permitted in the C-1 Conservancy District except that, whenever possible, pasturing and grazing of Livestock shall be located outside of the Eenvironmental Ceorridor.
 - (B) Single family dwellings.
 - (C) Keeping of Ppoultry and Livestock on not less than five (5) acres of land where there shall be no more than one (1) head of Livestock or twenty (20) Ppoultry for the first three (3) acres of land, and one (1) additional head of Livestock or twenty (20) additional Ppoultry for each additional one (1) acre of land thereafter. The keeping of hogs, male goats or Ffur-bearing Animals shall not be permitted.
 - (D) The following \underline{A} accessory \underline{B} buildings and uses, subject to the conditions specified:
 - 1. Private Ggarages, when located on the same lot, and not involving the conduct of a business; provided, however, that no Pprivate Ggarage shall be erected unless that Pprincipal Bbuilding to which such garage is an Accessory Uuse has been erected or is to be erected simultaneously with said garage.
 - Quarters for household or farm employees; provided, however, that such quarters shall be occupied only by individuals employed full time on the premises and their families.
 - Stables, barns, or poultry houses, which house <u>L</u>ivestock or <u>P</u>poultry, shall not be less than fifty (50) feet from an adjacent property line.
 - (E) A \underline{S} sign in accordance with Section 7.01(1)(G).
 - (F) Hobby \underline{K} kennel in accordance with Section 7.01(1)(I).
 - (G) Guesthouses are prohibited in the EC Environmental Corridor District.
 - (H) The establishment and enhancement of public parks and recreation areas, wilderness or walk-in unimproved boat access sites, natural and outdoor education areas, historic and scientific areas, wildlife refuges, game preserves, and wildlife habitat areas, provided that any tree and vegetation removal and subsequent restoration done in the EC Environmental Corridor District and any improvements and/or construction shall be approved by the County Zoning Administrator before

beginning any development activities. Vegetative restoration may be allowed within the corridor for the purpose of improving wildlife habitat or to otherwise enhance wildlife values provided all necessary permits are obtained and said activities shall only be approved after review and approval and issuance of all permits, as required. Roads and trails to service the recreational and wildlife areas, etc. may be permitted, but said R-roads and trails may not include vegetation removal or other construction activity within the corridor without obtaining all approvals, as required.

6.73 **Building Location**

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Section 3.09(1) for additional regulations and exceptions.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
- (B) Section 3.09(2) for additional regulations and exceptions. Setback: Fifty (50) feet minimum.
- $(\frac{23}{})$ Offset:
 - Thirty-five (35) feet minimum. In the case of existing legal ||Legal nNnon-conforming principal or accessory structures Structures that are less than the required thirty-five (35) foot minimum, an extension or addition may be allowed closer than thirty-five (35) feet as long as said extension or addition does not extend or encroach closer to the Seide Lhot Lhine than the existing structure Structure to which it is attached, at its closest point as measured in this Ordinance, and in no case shall be less than twenty (20) feet unless a Special Exception is granted by the Board of Adjustment to allow such extension or addition; and with the requirement that all of the disturbance regulations of Section 6.7 of this Ordinance be met as applicable.
 - (B) Section 3.09(3) for additional regulations and exceptions.
- 6.74 **Height Regulations.** The regulations and exceptions of Section 3.10 apply.
 - Principal Building: Thirty five (35) feet maximum.
 - (2) Accessory Building:

- (A) Farm: Sixty (60) feet maximum.
- (B) Other: Fifteen (15) feet maximum.

6.75 Area Regulations

- (1) Floor Area and Building Footprint:
 - (A) <u>Minimum Floor Area Rrequired for Single-family Dwelling</u>:
 - 1. First floor: Eight hundred and fifty (850) square feet.
 - 2. Total: Eleven hundred (1,100) square feet.
 - (B) Maximum F. A. R. Building Footprint P-permitted: Lots that are less than two (2) acres in area are restricted to a maximum F. A. R. Building Footprint of fifteen (15)seventeen and one half percent (17.5%) percent, or eleven (1,100) square feet, whichever is greater, unless preservation of Ggreen S-pace limitations are more restrictive.
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) Lot size and Density:
 - (A) Minimum area: The overall density of parcels lying entirely within the Eenvironmental Ceorridor shall be not greater than one (1) dwelling unit per five (5) acres of corridor area, with no Lłot Aerea being less than two (2) acres in size. On parcels which contain area outside of the Eenvironmental Ceorridor or partially within the Eenvironmental Ceorridor and in a zoning category requiring less than a five (5) acre Lłot, the five (5) acre density requirement shall not apply and the Lłot can be the size required for that adjacent zoning category, as determined by the Zoning Administrator, as long as any Lłand Aeltering Aectivity and/or building envelopes are located outside of the corridor area and appropriately restricted as such on the face of the Certified Survey Map, Subdivision Plat or other document approved by the Waukesha County Park and Planning Commission or the Zoning Administrator and recorded in the office of the Register of Deeds. The overall goal of this requirement is to obtain a maximum density of building activity within the Eenvironmental Ceorridor of not more than one (1) dwelling unit for each five (5) acres of Eenvironmental Ceorridor lands.
 - (B) Lands which lie within a larger parcel or tract of land, the remainder of which is zoned either FLP Farmland Preservation District or FLC Farmland Conservancy District, shall have a minimum (gross) parcel size of thirty-five (35) acres.
- (3) Preservation of Open-Green Space:
 - (A) For parcels lying entirely within an EC Environmental Corridor District, no open space regulation shall apply. However, tThe maximum area of disturbance in the EC Environmental Corridor District for all Lłand Aeltering Aectivities and vegetative removal, including building sites, septic areas, and drive areas, shall be the greater of fifteen thousand (15,000) square feet or fifteen (15)-percent (15%) of a parcel's

area, up to a maximum of thirty-two thousand six hundred seventy (32,670) square feet, and a deed restriction shall be recorded in the office of the Register of Deeds describing the permitted area of disturbance at the time of Zoning Permit issuance.

B) For parcels which lie partially within and partially outside of the EC Environmental Corridor District, the area of disturbance as described in subssection 3(A) above shall be limited to that area outside of the EC Environmental Corridor District unless otherwise permitted by a building envelope on a certified survey map, subdivision plat, or other document, or unless the developable area of a parcel (that area that is not constrained by zoning district setback and offset requirements and that is located outside of the EC Environmental Corridor District) is less than fifteen thousand (15,000) square feet or is less than the area that is equal to fifteen (15%) percent (15%) of the area of a parcel, up to a maximum of hirty-two thousand six hundred seventy (32,670) square feet.

If the developable area on a Lat is less than the above specified thresholds, a maximum area of disturbance within the EC Environmental Corridor District, as described in subsection 3(A) above, up to the amount of area needed to achieve the greater of a fifteen thousand (15,000) square foot developable area or a developable area of fifteen (15%) of the area of the parcel, up to a maximum of 32,670 square feet of disturbance area, as described in Section 3(A) above, may be permitted by the Zoning Administrator provided a deed restriction is recorded in the office of the Register of Deeds describing and authorizing the area of disturbance. The maximum area of disturbance within the Eenvironmental Ceorridor portion of such a Lat shall be determined by calculating the available developable area that is located outside of the Eenvironmental Ceorridor and subtracting the available developable area from the above described fifteen thousand (15,000) square foot or fifteen percent (15%) threshold.

(4) <u>Tree and Vegetation Cutting and Removal:</u>

(A) All tree and native brush and understory vegetation cutting and removal within the EC Environmental Corridor District shall require a Zoning Permit, in accordance with Section 3.03 of this Ordinance, prior to said activities commencing, with the following exceptions:

The cutting or removal of four (4) or fewer dead, dying or diseased trees from a single property within a one-year time period, the removal of invasive species, or the removal of vegetation necessitated by extension of utilities to public or private property shall not require a Zoning Permit. In addition, the Zoning Administrator may waive Zoning Permit requirements for tree cutting or vegetation removal in the event of widespread storm damage or for the cutting of trees that present a safety hazard.

(B) Tree and vegetation cutting or removal is regulated in order to protect natural beauty and wildlife habitat and to prevent erosion. Except for those activities conducted in accordance with the provisions of Section 6.75(3) above, tree and vegetation cutting and removal shall be limited to the cutting and removal of dead, dying, and diseased trees or vegetation; the cutting and removal of invasive species; or the cutting and removal of trees and vegetation related to the implementation of a forest management plan approved by the Zoning Administrator or his/her designee. Cutting and removal activities must demonstrate enhancement of the

Eenvironmental Ceorridor. The Zoning Administrator may consult with natural resource experts at the Southeastern Wisconsin Regional Planning Commission or other governmental agencies to determine the appropriateness of the proposed cutting or removal activities and to solicit recommendations regarding any required re-planting or restoration requirements in order to ensure that the project does not have an adverse impact on the natural environment.

(Section 6.7 was amended by Enrolled Ordinance 169-46, effective 09-09-2014.)

(Section 6.75(2)(B) was amended by Enrolled Ordinance 170-72, effective 12-31-15.)

SECTION 6.8 EC ENVIRONMENTAL CORRIDOR OVERLAY DISTRICT

All parameters and requirements of Section 6.7 EC Environmental Corridor District shall apply to lands mapped EC Environmental Corridor Overlay District. If an in-field determination finds that all or a portion of a property within said overlay district is erroneously mapped, the field determined boundaries shall immediately become subject to the applicable district regulations, Lands with an underlying zoning designation of FLP Farmland Preservation District shall comply with the more restrictive parameters of the FLP District but shall be allowed limited disturbance within EC areas if authorized in accordance with Section 6.19(€3)(4D). All references to the EC District or EC Environmental Corridor District within this Ordinance shall also apply to the EC Environmental Corridor Overlay District.

(Section 6.8 was created by Enrolled Ordinance 170-72, effective 12-31-15.)

SECTION 7 A-1 AGRICULTURAL DISTRICT

7.01 Permitted Uuses

- (A1) Any use permitted in the HG High Groundwater District.
- (<u>B2</u>) One <u>Single</u>-family <u>dD</u> welling.
- (G) General farming on not less than five (5) acres of land, including the keeping of Ppoultry and Livestock, except that the keeping of hogs, male goats or Ffur-bearing Amimals shall not be permitted on less than twenty (20) acres. The Zoning Administrator, upon recommendation of the Town Plan Commission, may grant a waiver for the cultivation of lands on parcels smaller than five (5) acres if a determination is made that said use will not negatively affect surrounding property owners.
- (<u>D4</u>) Horticulture, including greenhouses and nurseries.
- (<u>E5</u>) The following <u>A</u>accessory <u>B</u>buildings, subject to the conditions specified:
 - (A)1. Private <u>General grands</u> when located on the same lot, and not involving the conduct of a business. No <u>General grands</u> shall be erected until its <u>P</u>principal <u>B</u>building is present or under construction.
 - (B)2. Quarters for household or farm employees, provided, however, that such quarters shall be occupied only by those individuals employed by the Farm or household.

125

- 3. Private boat houses providing no human habitation is permitted. Only one (1) boathouse per lot is allowed.
- 4(C)- Stables, barns, or poultry houses, which house Livestock or Ppoultry, shall not be less than fifty (50) feet from an adjacent property line.
- (F6) Home Oeccupations and Perofessional Oeffices as defined in this Ordinance, when incident to the residential use and when situated in the same dwelling, subject to the following conditions:
 - (A)1. No nameplate exceeding three (3) square feet in area shall be permitted.
 - (B)2. Such Haome Oeccupation or Pprofessional Oeffice shall not occupy more than twenty (20) percent (20%) of the Ffloor Aarea of the dwelling.
 - (C)3. Such Hhome Oeccupation shall not employ more than one (1) person not a resident on such Llot.
 - (<u>D</u>)4. Adequate off-street parking facilities are provided adjacent to the <u>B</u>building housing such occupation or office.
 - (E)5. Such Ppermitted Uese shall not include the conduct of any retail or wholesale business on the premises, nor the removal of sand, gravel or stone for commercial purposes.
 - (F)6. Such use shall not include the use of any machinery, tools or appliances which can reasonably be construed as creating a nuisance to surrounding property owners.
 - G Such use conducted in an attached garage or Accessory Building requires a
 Conditional Use to be granted in accordance with Section 3.08(7)(KK) of this
 Ordinance.
- (G7) Signs pertaining to the lease or sale of a Bbuilding or land provided such Signs do not exceed twenty (20) square feet in area. Signs displaying the name of the owner or occupant and trespass warning signs are permitted provided they are no greater than six (6) square feet in area.
- (H8) (Repealed by Enrolled Ordinance 159-69, effective 1-17-05.)
- (49) Hobby Kkennel accessory to an otherwise Ppermitted Uuse provided such use has the specific approval of the town plan commission and will not adversely affect the use of adjacent lands as may be determined by findings of the town plan commission. The proposed use of parcels in such a manner shall be made by written notice to land owners within one hundred (100) feet of the subject property and in any case to land owners immediately adjacent and across the Street from such use by first class mail from the town plan commission prior to the meeting at which the town plan commission will consider approval of such use. The town plan commission may require such measures or provisions by the Applicant as it may deem necessary to provide adequate protection of surrounding property. The town may deny the right to a Habobby Kkennel on the basis of a finding that such a use would be incompatible and a possible nuisance to surrounding uses and not in the public interest. Any person aggrieved by a decision of the plan commission relative to this

Commented [BA64]: Removed boathouse provision because there are no structures that would meet the definition of a boathouse in the general zoning code.

Commented [BA65]: Added language consistent with shoreland ordinance. This section refers the reader to the Limited Family Business CU section.

provision may appeal such decision to the board of adjustment for review and determination as provided for in Section 19 of this Ordinance. Where two (2) or fewer dogs are kept, such use shall be considered accessory to the Perincipal Uese and shall not require special approval by the plan commission. In any case, if the keeping of any number of dogs accessory to the Perincipal Uese becomes a nuisance to the neighborhood as may be determined by the town plan commission or town board, such use shall be terminated or the nuisance abated. Where necessary, the town plan commission or town board may take appropriate steps to abate such nuisance.

(Section 7.01(A) was amended by Enrolled Ordinance 170-72, effective 12-31-15.) (Section 7.01(H) was repealed by Enrolled Ordinance 159-69, effective 1-17-05.) (Sections 7.01(C) and 7.01(E)4 were amended by Enrolled Ordinance 161-13, effective 09/04/06.) (Section 7.01(C) was amended by Enrolled Ordinance 170-72, effective 12-31-15.) (Section 7.01(I) was amended by Enrolled Ordinance 162-48, effective 10-9-07.)

7.02 Building location

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - 1. Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- (1) Setback: Fifty (50) feet minimum.
- (23) Offset:
 - (A) Twenty (20) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(3) apply.
- 7.03 Height regulations: The regulations and exceptions of Section 3.10 apply.
 - (1) <u>Principal building</u>: Thirty five (35) feet maximum.
 - (2) <u>Accessory buildings:</u>

- (A) <u>Farm</u>: Sixty (60) feet maximum.
- (B) Other: Fifteen (15) feet maximum.

7.04 Area regulations

- (1) Floor area Area and Building Footprint:
 - (A) <u>Minimum Floor Area required for Single-family Dwelling</u>:
 - 1. <u>First floor</u>: <u>Nine-Eight</u> hundred <u>fifty</u> (900850) square feet.
 - 2. <u>Total, one (1) family</u>: One thousand one Eleven hundred (1,100) square feet.
 - (B) Maximum F. A. R. Building Footprint permitted: Ten (10) percent (10%), or eleven hundred (1,100) square feet, whichever is greater.
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) <u>Lot size</u>:
 - (A) Minimum area: Three (3) acres.
 - (B) <u>Minimum average width</u>: Two hundred (200) feet.
- (3) Open space: Two (2) acre minimum per family.

SECTION 7a A-la AGRICULTURAL DISTRICT

7a.01 Use regulations

Permitted Uuses: Any use as permitted and regulated in A-1 Ddistrict.

7a.02 Building location

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:

(A) Seventy-five (75) feet minimum. (B) Additional regulations and exceptions from Section 3.09(2) apply. Setback: Fifty (50) feet minimum. (23) Offset: (A) Twenty (20) feet minimum. (B) Additional regulations and exceptions from Section 3.09(3) apply. 7a.03. Height regulations: The regulations and exceptions of Section 3.10 apply. Principal building: Thirty five (35) feet maximum. Accessory buildings: (A) Farm: Sixty (60) feet maximum. Other: Fifteen (15) feet maximum. 7a.04 Area regulations (1) Floor area Area and Building Footprint: Minimum Floor Area required for Single-family Dwelling: First floor: Nine-Eight hundred fifty (900850) square feet. 1. 2. Total, one (1) family: One thousand one Eleven hundred (1,100) square feet. (B) Maximum F.A. R. Building Footprint permitted: Ten (10) percent (10%), or eleven (1,100) square feet, whichever is greater. Additional regulations and exceptions from Section 3.11 apply. (C) (2) Lot size: (A) Minimum area: One (1) acre. Minimum average width: One hundred fifty (150) feet. Open space: Thirty thousand (30,000) square feet minimum per family. SECTION 7b HG HIGH GROUNDWATER DISTRICT

7b.01 Purpose and intent

This Delistrict is intended to apply to those lands that are mapped as having hydric soil conditions

129

(depth to groundwater of one foot or less) according to the Soil Survey of Milwaukee and Waukesha Counties published by the USDA Soil Conservation Service. Many of these lands contain Wwetlands and floodplains and, accordingly, are mapped with a C-1 Conservancy Overlay District designation. Other lands with such soil conditions are presently in Agricultural Uwse by virtue of either cultivation, pasture or in some other way, and which if they were not being used for agricultural purposes would be classified as conservancy lands due to inherent wet soil characteristics and the presence of natural vegetation indicative of wet soils.

The intent of the $\underline{\mathbb{D}}$ -district is to preserve and maintain agricultural or open space uses on lands suited for such purposes. These lands are generally poorly suited for urban or suburban development, while lands outside of $\underline{\mathbb{W}}$ -wetlands are typically better suited for some type of $\underline{\mathbb{A}}$ -egricultural $\underline{\mathbb{U}}$ -use. In this $\underline{\mathbb{D}}$ -district, $\underline{\mathbb{S}}$ -structures related to farm operations, including existing dwellings, are deemed consistent with the purpose and intent of this section where the location of $\underline{\mathbb{B}}$ -buildings associated with the permitted agricultural operation are found to conform with health, sanitation and safety provisions of this and any other state regulation or local ordinance. The intent for mapping purposes is that lands within this $\underline{\mathbb{D}}$ -district shall have exhibited $\underline{\mathbb{A}}$ -agricultural $\underline{\mathbb{U}}$ -uses in the past. It is not the intent of this section to promote or permit the conversion of $\underline{\mathbb{W}}$ -wetlands. Lands mapped in this $\underline{\mathbb{D}}$ -district are typically in the Planned "Other Open Lands to be Preserved" or "Environmental Corridor" comprehensive development plan categories.

7b.02 Use regulations: Permitted <u>U</u>uses

- Any uses and Setructures permitted in the C-1 Conservancy District and, if located in a Wwetland, the provisions of Section 5 must be met.
- (2) Ordinary Ffarm Unses, including dairying, Livestock, poultry raising, and truck farming.
- (3) Accessory <u>U</u> uses within <u>B</u> buildings normally associated with permitted agricultural operations including existing single-family dwellings, shelters for housing animals, except that no Setructure shall be located upon lands not suited due to soil limitations.
- (4) Nurseries, commercial greenhouses, and hatcheries limiting the retail sales of such product to that which is produced by the farm operator, subject to review and approval of a Site Plan and Plan of Operation by the plan commission and the Zoning Administrator in accordance with Section 3.03(6) of this Ordinance.
- (5) Roadside Setands as outlined in Section 6.14(B)(5) of this Ordinance.
- (6) Signs not to exceed forty (40) feet in area displaying the name of the Ffarm or farm organization.

7b.03 Conditional uses

Conditional uses as provided in Section 3.08(7)(A), (AA), (D), (G), (K), (Q), (R), (W), (Z).

7b.04 **Building location**

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:

- Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
- 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
- (B) Additional regulations and exceptions from Section 3.09(1) apply.

Road Setback:

- (A) Residential: Fifty (50) feet minimum, unless otherwise excepted in this Ordinance.
- (B) Other: Fifty (50) feet minimum, unless otherwise excepted in this Ordinance.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- (23) Offset:
 - (A) Residential: Twenty (20) feet minimum, unless otherwise
 - excepted in this Ordinance.
 - (B) Other: Twenty (20) feet minimum, unless otherwise

excepted in this Ordinance. Buildings that house animals must be fifty (50) feet minimum.

- (C) Additional regulations and exceptions from Section 3.09(3) apply.
- (3) C. 1 Conservancy Setback

Seventy-five (75) feet, unless otherwise excepted in this Ordinance. All accessory buildings must be seventy five (75) feet minimum.

7b.05 Height regulations

- (1) Principal buildingBuilding: Thirty five (35) feet maximumThe regulations and exceptions of Section 3.10(1) apply.
- (2) <u>Accessory building</u>Building: Twenty (20) feet maximum.
- (3) Refer to Additional regulations and exceptions from Section 3.10 of this Ordinance for additional height regulations apply.

7b.06 Area regulations

- (1) <u>Floor-Minimum Floor area Area, minimum required for Single-family Dwelling:</u>
 - (A) Minimum fFirst floor: nine Eight hundred fifty (900850) square feet.

- (B) Total:—one thousand one Eleven hundred (1,100) square feet.
- (2) Maximum floor area ratioBuilding Footprint permitted: Ten (10) percent (10%), or eleven hundred (1,100) square feet, whichever is greater.
- (3) <u>Minimum parcel size</u>: Five (5) acres, except that for HG lands that lie within a larger parcel or tract of land, the remainder of which is zoned in any other <u>Delistrict</u>, said parcel shall comply with the minimum (gross) parcel size requirement of that non HG district.
- (4) Additional regulations and exceptions from Section 3.11 apply.

7b.07 **Determination of boundaries**

Where on-site evaluation of soil conditions by a certified soil scientist reveals that soils mapped by the USDA as being hydric are found to be mis-mapped, the lands zoned HG District shall immediately become subject to the district regulations of the zoning district that is mapped on the balance of the property. If no other zoning district has previously been established on another part of the parcel, the lands shall be zoned as used administratively by the Waukesha County Zoning Administrator. If any such lands are part of an Eenvironmental Ceorridor, Wwetland or floodplain, the respective EC Environmental Corridor District Overlay or C-1 Conservancy Overlay shall continue to apply to said lands.

(Section 7b was created by Enrolled Ordinance 170-72, effective 12-31-15.)

SECTION 8 A-2 RURAL HOME DISTRICT

8.01 Use regulations

- (1) <u>Permitted U+ses</u>:
 - (A) Any use permitted in the A-1 Agricultural District, except that the keeping of Ppoultry or Livestock shall not be permitted on any Liot less than three (3) acres. There shall be no more than one (1) head of Livestock or twenty (20) Ppoultry for the first three (3) acres of land. There may be one (1) additional head of Livestock or twenty (20) additional Ppoultry for each additional one (1) acre of land. All lands to be utilized for the keeping of Livestock or Ppoultry must be under the same ownership or additional leased lands may be used to increase the maximum permitted Livestock or Ppoultry if contiguous to the owners' property. Where such use lawfully existed prior to the date of this Ordinance, such use may be continued subject to the limitations regulating non-conforming use as regulated in Section 3.17(2)(B) of this Ordinance.
 - (B) Nurseries and greenhouses for the private and exclusive use of the dwelling occupant are permitted.

(Section 8.01(1)(A) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

8.02 Building location

(1)	Road Setback:		
	(A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:		
	1. Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.		
	2. Thirty-five (35) feet minimum if the Lot is served by sewer.		
	(B) Additional regulations and exceptions from Section 3.09(1) apply.		
(2)	Wetland Setback:		
	(A) Seventy-five (75) feet minimum.		
	(B) Additional regulations and exceptions from Section 3.09(2) apply.		
Setba	<u>k</u> : Fifty (50) feet minimum.		
(2 3)	Offset:		
	(A) Thirty (30) feet minimum.		
	(B) Additional regulations and exceptions from Section 3.09(3) apply.		
Height r	egulations: The regulations and exceptions of Section 3.10 apply.		
(1)	Principal building: Thirty five (35) feet maximum.		
(2)	Accessory buildings: Fifteen (15) feet maximum.		
Area reg	ulations		
(1)	Floor area Area and Building Footprint:		
	(A) <u>Minimum Floor Area required for Single-family Dwelling</u> :		
	1. <u>First floor</u> : <u>Nine-Eight</u> hundred <u>fifty</u> (900850) square feet.		
	2. <u>Total</u> : One thousand five Eleven hundred (1,500100) square feet.		
	(B) <u>Maximum F. A. R. Building Footprint permitted</u> : Ten (10) percent (10%), or eleven hundred (1,100) square feet, whichever is greater.		
	(C) Additional regulations and exceptions from Section 3.11 apply.		
(2)	Lot size:		

(A) <u>Minimum area</u>: Three (3) acres.

- (B) <u>Minimum average width</u>: Two hundred (200) feet.
- (3) Open space: Two (2) acres minimum per family.

SECTION 8a A-3 SUBURBAN ESTATE DISTRICT

8a.01 Use Regulations – Permitted Uses

Any use as permitted in the A-2 Rural Home District.

(Section 8a.01 was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

8a.02 Building location

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.

Setback: Fifty (50) feet minimum.

- $(\frac{23}{})$ Offset:
 - (A) Twenty-five (25) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(3) apply.

8a.03 Height regulations: The regulations and exceptions of Section 3.10 apply.

- (1) Principal building: Thirty five (35) feet maximum.
- (2) Accessory buildings: Fifteen (15) feet maximum.

8a.04 Area regulations

- (1) Floor area Area and Building Envelope Footprint:
 - (A) <u>Minimum Floor Area required for Single-family Dwelling:</u>
 - 1. First floor: Nine-Eight hundred fifty (900850) square feet.
 - 2. <u>Total</u>: One thousand five Eleven hundred (1,500100) square feet.
 - (B) Maximum F. A. R. Building Footprint permitted: Ten (10) percent (10%), or eleven hundred (1,100) square feet, whichever is greater.
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) Lot size:
 - (A) Minimum area: Two (2) acres.
 - (B) Minimum average width: One hundred seventy-five (175) feet.
- (3) Open space: Seventy five thousand (75,000) square feet minimum per family.

SECTION 8b RRD-5 RURAL RESIDENTIAL DENSITY DISTRICT 5

8b.01 General Regulations

- Purpose and intent: The purpose of this five (5) -acre density zoning district is to allow for agricultural and rural use of lands to continue while also allowing for clustered development on lands located in rural or semi-rural areas. Additional stated purposes of the Ddistrict are as follows:
 - (A) Promote the preservation of the rural character of the towns by encouraging farm fields, pastures, orchards, and natural Oopen Sepaces to be retained either as Ceommon Oopen Sepaces, or as part of a farm operation.
 - (B) ATo achieve the optimum residential environment while recognizing the rural character of towns. The density transfer technique is designed to permit variable lot sizes in the utilization of the most desirable terrain for housing sites while encouraging preservation of natural resource lands and agricultural lands.
 - (C) This Deistrict allows for the transfer of residential Deevelopment Reights from one area of a parcel to another area of a parcel, thereby allowing an increase in density of development on suitable lands for development in exchange for establishing the preservation of natural resource or agricultural lands known as "preserved lands".
- (2) Review of Proposed Development: Where a development is to occur involving the establishment of "preserved lands," approval by the Plan Commission and the County Zoning Agency shall be required. The development proposed shall conform to the following standards:

Commented [BA66]: Removed the preservation of prime Ag soil requirement.

- (A) The shape and arrangement of preserved lands shall be approved by the Plan

 Commission and County Zoning Agency pursuant to the requirements of the RRD-5

 District.
- (B) Lands zoned RRD-5 District that are proposed to be developed via subdivision plat must be developed in a conservation design format, as detailed in the County Development Plan. Subdivisions shall provide Ceommon Oopen Sepace and conserve natural resource lands in accordance with the guidelines of the County Development Plan relative to development of Rural Development Areas and the Rural Density Conservation Design criteria.
- (C) The preserved lands shall be retained in one of the following manners:
 - 1. A deed restriction or covenant recorded with the Waukesha County Register of Deeds so noting that part or all of the Development Rrights have been utilized for the subject land. No additional Development Rrights would accrue to that site until such time as it could be served with municipal sewer and a zoning change is approved by the Town and County in accordance with adopted local and County Land Use Plans.
 - All lot owners within the developed area for which the preserved lands are
 protected could own an undividable interest in said preserved land.
 Development of those lands may not occur until such time as sewer is
 available and a zoning change is approved by the Town and County in
 accordance with adopted local and County Land Use Plans.
 - The preserved lands may be retained in public ownership if a town or the County is willing to accept a dedication or acquire the lands.
- (D) On a parcel which is zoned RRD-5, the development density shall not exceed five (5) acres for each dwelling unit.
- (E) In order to preserve the rural character as well as the efficiency and safety of existing road systems, lands to be developed via subdivision plat shall have Llots clustered on interior subdivision streets to minimize Llots being accessed from existing arterials or roadways by individual driveway accesses. The goal of this provision is to encourage grouping of Llots on an interior street which will then access the existing road system.
- (F) Any land claimed in addition to the actual described residential lots, for credit toward meeting the density factor requirement, shall have its status permanently established, and guaranteed, either by dedication to the public, or by appropriate covenants running with the lands, inby conveyance of agricultural easements. Such covenants and easements shall be recorded in the office of the Register of Deeds and shall restrict the property against any development or use except as is consistent with its preservation as agricultural land or as a form of Ceommon Oopen Sepace unless sewer becomes available, and the zoning of the property is changed in accordance with adopted local and County Land Use Plans. The preserved land status of any parcel shall be indicated on the official zoning map.
- (G) In addition to requiring an appropriate Oopen Sepace or an agricultural easement on

the transferring lands in favor of the town and/or county, covenants shall be placed into the title of each dwelling unit, giving the owner enforceable rights to prevent the future development of the transferring lands until such time as sewer is available and the subject property is rezoned to allow additional development.

- (3) Use Regulations: Permitted Uses:
 - (A) Residential:
 - 1. Single-family uses.
 - Duplexes pursuant to issuance of a conditional use permit as required by Section 3.08(7)(N) and compliance with the minimum Ffloor Aarea and Bbuilding Ffootprint requirements contained herein.
 - (B) Agricultural or Ffarm U+ses on parcels having a minimum of five (5) acres, except on parcels having less than five (5) acres one (1) horse shall be allowed on parcels having a minimum of three (3) acres and there may be one (1) additional horse for each additional one (1) acre thereafter. The keeping of hogs, male goats or Ffur-bearing A+mimals shall not be permitted on less than twenty (20) acres. Those practicing A+gricultural or Ffarm U+ses under this section must comply with standard manure disposal practices.
 - (C) Accessory Uses and Bbuildings normally associated with an agricultural operation including garages, stables, and poultry houses. Buildings used for housing animals shall maintain a minimum Ooffset of fifty (50) feet from all adjacent Liot Lines.
 - (D) Signs:
 - Sign not to exceed twelve (12) square feet in area displaying the name of the Ffarm or farm organization.
 - 2. Subdivision signs in accordance with the sign provisions of this Ordinance.
 - (E) Wholesale nurseries, greenhouses and hatcheries, subject to review and approval of a Site Plan and Plan of Operation by the plan commission and the Zoning Administrator in accordance with Section 3.03(6) of this Ordinance.
 - (F) Roadside Sstands subject to the following:
 - 1. Off-street parking for a minimum of five (5) vehicles must be provided.
 - No such stands shall be closer than thirty (30) feet to the Bbase Seetback
 Line or closer than twenty (20) feet to any Llot Lline.
 - (G) Home Ooccupation and Pprofessional Ooffices as regulated herein.
 - (H) Hobby Kkennels as regulated in Section 7.01(9).
- (1) Purpose and Intent: The purpose of this zoning district is to allow the development of land at densities not greater than one (1) unit for each five (5) acres on all non prime agricultural

areas, in order to encourage the preservation of Prime Agricultural tillable land, (U.S.D.A. Class I and II soils) to discourage residential development on environmentally sensitive areas, provide some marketability for such lands, and to encourage a more economical use of land which is suited to residential development by permitting more intensive use of such lands without changing the overall rural character of the Town and the population density of the Town as set forth in the adopted Land Use Plan. Further, only 20% of the lands in the C-1 Conservancy District may be used when calculating the allowable living units.

This district encourages the transfer of residential development rights from one area of a parcel to another, and from one tract of land to another, thereby increasing the density of development in exchange for establishing the preservation of other lands as "agricultural preserved lands."

- (A) <u>Development Goals</u>: The stated intent of the density regulations where preserved lands will be established can be implemented in the following manner:
 - Development would occur at five (5) acre densities with the buildable parcels having the building site outside of the prime agricultural tillable area and the open area transferring lands) would be retained through a deed restriction or covenants with no development rights until such time as it could be served with municipal sewer and a zoning change is approved by the Town and County Boards, in accordance with the adopted local Land Use Plan.
 - All lot owners would own an undividable interest in the large open space
 area with development rights transferred and only to be developed at such
 time as sewer is available and a zoning change is approved by the Town and
 County Boards in accordance with the adopted local Land Use Plan.
 - 3. The land owner or his heirs and assign who sold the development rights could retain those lands with the original farmstead; however, no development rights of that parcel beyond those available under this provision would be allowed to be transferred until such time as sewer became available and rezoning of the parcel is approved by the Town and County Board in accordance with the adopted Local Land Use Plan.
- (B) Preservation of Rural Character: A basic goal of this density transfer technique is to promote the preservation of the rural character of the Town by encouraging farm fields, pastures and orchards and natural open spaces to be retained, either as common open spaces or as part of a farm operation under the "preserved land" category.
- (C) Preservation of Agricultural Lands: The shape and arrangement of preserved lands designated for agricultural use should be consistent with practical requirements for an agricultural activity and be of justifiable value for farm use or as a contribution to the goal of preserving the rural environmental character. The preserved areas must be at least twenty (20) acres of contiguous area, not necessarily on the same parcel, and consist of U.S.D.A. Class I and II soils for prime agricultural use, and be tillable without the necessity of removing mature vegetation.
- (D) Relationship of Development to Agricultural Area: Consideration shall be given as to whether the development plans for roads, building sites and preserved agricultural

areas is based upon the careful consideration of the most appropriate relationship to the existing terrain conditions, suitable capacity for onsite sewage disposal systems, provisions for storm water drainage and retention, the potential impact upon surrounding areas, the size, location and the agricultural viability of the agricultural lands being preserved.

(E) Access to Town and County Roads: In order to preserve the rural character, as well as the efficiency and safety of existing road systems, it will be required to minimize the development of lots strung out along such roads with individual driveway accesses from each lot. One goal of density control is to encourage the grouping of lots on interior streets which will access the existing road system.

(2) Principles and Guidelines:

- (A) The portion of a tract of land from which development rights are transferred is hereby termed the "transferring land", and the tract to which the additional dwelling unit development potential is added is termed the "receiving land."
- (B) The transfer of development rights may only take place between RRD 5, the AD 10, HG High Groundwater and C 1 Conservancy Zoning Districts except that only a maximum of 20% of the transferring land zoned C-1 Conservancy/Wetland may be counted towards the overall density to be provided for the receiving land. Where more than 50% of the site is zoned in the C 1 category, only that amount of acreage up to the 50% amount may be used in the above calculations for density purposes.
- (C) For the purpose of transferring residential development rights, the petitioner shall provide documentation at the time of submittal of the preliminary plat indicating that he is an owner of the subject property or has the authority under the terms of a written contract (Offer to Purchase) to make commitments on the transferring land.
- (D) In addition to requiring an appropriate open space or an agricultural easement on the transferring lands in favor of the Town and/or County, covenants shall be placed in the title of each dwelling unit, giving the owner enforceable rights to prevent the future development of the transferring lands until such time as sewer is available and the subject property is rezoned to allow additional development.
- (E) This zoning category is designed to control the intensity of use in relationship to the natural, physical and ecological characteristics of the land, to implement the local Land Use Plans, allow development where soils can accommodate sewage disposal systems, discourage intense development where there is an inability to provide appropriate municipal services, basic economic factors and achievement of the desirable residential and environmental character and preservation of prime agricultural tillable areas consisting of U.S.D.A. Class I and II soils on a minimum of twenty (20) acres of contiguous area. To achieve the optimum residential environment in a rural character for the Town, the density technique is designed to permit variable lot sizes in the utilization of the most desirable terrain for housing sites while encouraging the preservation of prime agricultural tillable lands and lands worthy of such preservation.
- (F) The density factor is expressed in terms of the amount of gross land area required for each dwelling unit. Such gross area includes the area of the lots and any other lands preserved in agricultural use where those areas are termed "preserved lands."


The minimum lot size is expressed in terms of minimum area, and average width for the actual privately owned lot intended as the home site.

- (G) No building intended in whole or part for residential use shall be erected or relocated unless the lot on which it is located meets the required density factor or has allocated to it through the transfer program, sufficient additional preserved lands to meet the required density factor for the district in which it is located. Where "transferred lands" are to be established, no more than 20% of the total for computation may be in the C-1 Conservancy Zoning District and in accordance with Section 6.51(B) 2 of this Ordinance. Where the total area (or the pro-rated factor) involved includes more than one zoning district, the overall density factor shall apply. In any such case involving the establishment of "preserved lands" approval by the plan commission and the zoning agency shall be required, pursuant to the criteria and development goals set forth herein.
- (H) Any land claimed in addition to the actual described residential lots for credit toward meeting the density factor requirement shall have its status permanently established and guaranteed either by dedication to the public or by appropriate covenants running with the lands in conveyance of agricultural easements, such covenants and easements shall restrict the property against any development or use, except as is consistent with its preservation as agricultural land, or as a form of common open space, unless sewer becomes available and the zoning of the property is changed in accordance with the adopted local Land Use Plan. The preserved land status of any parcel shall be indicated on the official zoning map.

(3) Use Regulations

(1) Permitted Uses:

- (A) Single family uses and not more than one two family residential dwelling (duplex) pursuant to issuance of a conditional use permit under Section 3.08(7)(N).
- (B) Ordinary farm uses, including dairy and livestock, poultry raising, raising of crops, and truck farming or parcels having a minimum of five (5) acres.
- (C) Accessory uses and buildings normally associated with an agricultural operation, including garages, stables and poultry houses. Buildings used for housing of animals shall maintain a minimum offset of fifty (50) feet from all adjacent lot lines.
- (D) <u>Signs</u>:
 - Signs not to exceed twelve (12) square feet in area, displaying the name of the farm or farm organization.
 - Subdivision signs, in accordance with the sign provisions of the Ordinance.
- (E) Wholesale nurseries, greenhouses and hatcheries.



(1)	Principal structure: Thirty five (35) feet maximum.
(2)	Accessory buildings:
	— (A) <u>Farm Building</u> : Sixty (60) feet maximum.
	— Other Accessory Building: Fifteen (15) feet maximum.
8b.04 Area R	egulations
(1)	Floor area Area and Building Footprint:
	(A) Minimum required Floor Area for Single-family Dwelling:
	1. <u>first First floor</u> : Nine Eight hundred fifty (85900) square feet.
	1-2. <u>Total one family</u> : Fifteen-Eleven hundred (1,500100) square feet.
	(B) <u>Two family minimum required first floor:</u> Seven hundred and fifty (750) square feet. Total per family: Fourteen hundred (1,400) square feet.
	(CB) Maximum floor area ratioBuilding Footprint: Fifteen percent (15%), or eleven hundred (1,100) square feet, whichever is greater.
	(C) Additional regulations and exceptions from Section 3.11 apply.
(2)	Lot size:
	(A) Minimum: one (1) acre.
	(B) Minimum average width: one hundred and fifty (150) feet.
(3)	Open space: Thirty thousand (30,000) square feet per family.
(4 <u>3</u>)	Density Division Standard: Development shall not exceed one (1) dwelling unit per five acres.
	(A) For parcels less than twenty (20) acres in size, the property must be developed in accordance with one of the two following methods:
	1. The land may be divided into parcels with five (5) acre minimum lot size only if the parcel contains no prime tillable land or the prime farmland of the subject parcel is not contiguous to other prime farmland on an adjace parcel which would meet the twenty (20) acre minimum size.
	2. The land may be developed at a five (5) acre overall density, as long as more than one (1) living unit for each five (5) acres would be allowed a
	142 Effective 05-xx-2016

the prime tillable area is preserved where it is contiguous to an adjacent parcel where the prime agricultural area is a minimum size of at least twenty (20) acres.

- (B) Parcels greater than twenty (20) acres in size must conform to the following standards:
 - 1. They must be developed at no more than a five (5) acre density, taking into account only 20% of any C-1 Conservancy zoned lands where more than 50% of the site is zoned C-1, only the amount of acreage up to the 50% amount may be used in the calculation of allowable density.
 - Residential development would be allowed only on non-prime agricultural soils (U.S.D.A. Class III and below) which are tillable.
 - 3. All farm fields which must be preserved, are those areas which are a minimum of twenty (20) acres in contiguous area and consist of U.S.D.A. Class I and II prime agricultural soil and are tillable. The twenty (20) acre minimum area may be on the subject parcel or contiguous to prime agricultural areas on an adjacent parcel.

(Section 8b.04(4)(B)1 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

(Section 8b.04(4)(B)1 was amended by Enrolled Ordinance 170-72, effective 12/31/15.)

SECTION 9 R-1 RESIDENTIAL DISTRICT

9.01 Use regulations

- (1) <u>Permitted Uuses:</u>
 - (A) Any use as permitted in the A-2 Rural Home District.
 - (B) The keeping of usual household pets and Hhobby Kkennels but not including the operation of a Ceommercial Kkennel unless a conditional use permit is obtained.

(Section 9.01(1)(A) was amended by Enrolled Ordinance 161-13, effective 09/04/06.)

9.02 Building location

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.

143

Effective 05-xx-2016

		(B) Additional regulations and exceptions from Section 3.09(1) apply.		
	(2)	Wetland Setback:		
(A) Seventy-five (75) feet minimum.				
		(B) Additional regulations and exceptions from Section 3.09(2) apply.		
	Setbac	<u>k:</u> Fifty (50) feet minimum.		
	(2 3)	3) Offset:		
		(A) Twenty (20) feet minimum, unsewered.		
		(B) Fourteen (14) feet minimum, sewered.		
		(C) Additional regulations and exceptions from Section 3.09(3) apply.		
9.03	Height r	egulations: The regulations and exceptions of Section 3.10 apply.		
	(1)	Principal building: The maximum height of a residential structure shall meet the following requirements: (A) A point measured from the lowest exposed point of the structure to the highest floor line shall not exceed 27 feet, and (B) A point measured from the lowest exposed point of the structure to any eave shall		
		not exceed 36 feet, and		
		(C) A point measured from the lowest exposed point of the proposed structure to the highest point of any roof shall not exceed 46 feet, and		
		(D) On waterfront lots, no building or structure shall contain more than three (3) stories when viewed from the waterfront.		
	(2)	Accessory buildings: Eighteen (18) feet maximum.		
	(Section	9.03 was amended by Enrolled Ordinance 160-03, effective 05/13/05.)		
9.04	Area reg	ulations		
	(1)	Floor area Area and Building Footprint:		
		(A) Minimum Floor Area required for Single-family Dwelling:		
		1. <u>First floor</u> : <u>Nine-Eight</u> hundred <u>fifty (900850)</u> square feet.		
		2. Total: One thousand three Eleven hundred (1,300100) square feet.		

(B)

Maximum F. A. R. Building Footprint permitted: Fifteen (15) Seventeen and one

half percent (17.5%), or eleven hundred (1,100) square feet, whichever is greater-

- (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) <u>Lot size</u>:
 - (A) <u>Minimum area</u>: One (1) acre, thirty percent (30%) reduction if sewered.
 - (B) <u>Minimum average width</u>: One hundred fifty (150) feet, thirty percent (30%) reduction if sewered.
- (3) Open space: Thirty thousand (30,000) square feet minimum per family.

(Section 9.04(1)(B) was amended by Enrolled Ordinance 169-46, effective 09/09/14.)

SECTION 9a R-1a RESIDENTIAL DISTRICT

9a.01 Use regulations

Any use as permitted and regulated in the R-1 \underline{D} district.

9a.02 Building location.

- Road Setback:
 - A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- (3) Offset:
 - (A) Twenty (20) feet minimum, unsewered.

- (B) Fourteen (14) feet minimum, sewered.
- (C) Additional regulations and exceptions from Section 3.09(3) apply.
- (1) <u>Setback</u>: Fifty (50) feet minimum.
- (2) Offset: Twenty (20) feet minimum.

9a.03 Height regulations: The regulations and exceptions of Section 3.10 apply.

- (1) <u>Principal building: The maximum height of a residential structure shall meet the following requirements:</u>
 - (A) A point measured from the lowest exposed point of the structure to the highest floor line shall not exceed 27 feet, and
 - (B) A point measured from the lowest exposed point of the structure to any eave shall not exceed 36 feet, and
 - (C) A point measured from the lowest exposed point of the proposed structure to the highest point of any roof shall not exceed 46 feet, and
 - (D) On waterfront lots, no building or structure shall contain more than three (3) stories when viewed from the waterfront.
- (2) <u>Accessory buildings</u>: Eighteen (18) feet maximum.

(Section 9a.03 was amended by Enrolled Ordinance 160-03, effective 05/13/05.)

9a.04 Area regulations.

- (1) Floor area Area and Building Footprint:
 - (A) <u>Minimum Floor Area required for Single-family Dwelling</u>:
 - 1. <u>First floor</u>: <u>Nine-Eight</u> hundred <u>fifty</u> (900850) square feet.
 - 2. <u>Total</u>: One thousand five Eleven hundred (1,500100) square feet.
 - (B) Maximum F. A. R. Building Footprint permitted: Fifteen (15) Seventeen and one half percent (17.5%), or eleven hundred (1,100) square feet, whichever is greater.
 - (C) Section 3.11 for additional regulations and exceptions.
- (2) <u>Lot size</u>:
 - (A) Minimum area: One (1) acre, thirty percent (30%) reduction if sewered.
 - (B) <u>Minimum average width</u>: One hundred fifty (150) feet, thirty percent (30%) reduction if sewered.

(3) Open space: Thirty thousand (30,000) square feet minimum per family.

(Section 9a.04(1)(B) was amended by Enrolled Ordinance 169-46, effective 09/09/2014.)

SECTION 10 R-2 RESIDENTIAL DISTRICT

10.01 Use regulations.

Permitted U+ses: Any use as permitted in the R-1 Residential Delistrict.

10.02 Building location.

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions for setbacks when measured from a Local Road:
 - 1. Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- (3) Offset:
 - (A) Twenty (20) feet minimum, unsewered.
 - (B) Fourteen (14) feet minimum, sewered.
 - (C) Additional regulations and exceptions from Section 3.09(3) apply.
- (1) <u>Setback</u>: Fifty (50) feet minimum.
- (2) Offset: Twenty (20) feet minimum.
- 10.03 Height regulations: The regulations and exceptions of Section 3.10 apply.
 - (1) <u>Principal building</u>: The maximum height of a residential structure shall meet the following requirements:
 - (A) A point measured from the lowest exposed point of the structure to the highest floor

line shall not exceed 27 feet, and

(B) A point measured from the lowest exposed point of the structure to any eave shall not exceed 36 feet, and

(C) A point measured from the lowest exposed point of the proposed structure to the highest point of any roof shall not exceed 46 feet, and

(D) On waterfront lots, no building or structure shall contain more than three (3) stories when viewed from the waterfront.

(2) Accessory buildings: Eighteen (18) feet maximum.

(Section 10.03 was amended by Enrolled Ordinance 160-03, effective 05/13/05.)

10.04 Area regulations.

- (1) Floor area Area and Building Footprint:
 - (A) <u>Minimum Floor Area required for Single-family Dwelling</u>:
 - 1. <u>First floor</u>: <u>Nine-Eight</u> hundred <u>fifty (900850)</u> square feet.
 - 2. <u>Total</u>: One thousand two Eleven hundred (1,200100) square feet.
 - (B) Maximum F. A. R. Building Footprint permitted: Fifteen (15) Seventeen and one half percent (17.5%), or eleven hundred (1,100) square feet, whichever is greater.
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) <u>Lot size</u>:
 - (A) <u>Minimum area</u>: Thirty thousand (30,000) square feet, thirty percent (30%) reduction if sewered.
 - (B) Minimum average width: One hundred twenty (120) feet, thirty percent (30%) reduction if sewered.
- (3) Open space: Twenty-five thousand (25,000) square feet minimum per family.

SECTION 11 R-3 RESIDENTIAL DISTRICT

11.01 Use regulations.

- (1) <u>Permitted U+ses</u>:
 - (A) Any use as permitted in the R-2 Rresidential Delistrict.
 - (B) Multiple family dwellings, pursuant to Section 3.08(7)(N).

11.02 Building location.

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Section 3.09(2) for additional regulations and exceptions.
- (3) Offset:
 - (A) Twenty (20) feet minimum, unsewered.
 - (B) Fourteen (14) feet minimum, sewered.
 - (C) Additional regulations and exceptions from Section 3.09(3) apply.
- (1) <u>Setback</u>: Fifty (50) feet minimum.
- (2) Offset: Twenty (20) feet minimum.
- 11.03 **Height regulations**—: The regulations and exceptions of Section 3.10 apply.
 - (1) Principal building: The maximum height of a residential structure shall meet the following requirements:
 - (A) A point measured from the lowest exposed point of the structure to the highest floor line shall not exceed 27 feet, and
 - (B) A point measured from the lowest exposed point of the structure to any eave shall not exceed 36 feet, and
 - (C) A point measured from the lowest exposed point of the proposed structure to the highest point of any roof shall not exceed 46 feet, and
 - (D) On waterfront lots, no building or structure shall contain more than three (3) stories

when viewed from the waterfront

(2) Accessory buildings: Eighteen (18) feet maximum.

(Section 11.03 was amended by Enrolled Ordinance 160-03, effective 05/13/05.)

11.04 Area regulations.

- (1) Floor area Area and Building Footprint:
 - (A) <u>Minimum Floor Area required for Single-family Dwelling</u>:
 - 1. <u>First floor</u>: Eight hundred fifty (850) square feet.
 - 2. <u>Total</u>: One thousand one Eleven hundred (1,100) square feet.
 - (B) Maximum F. A. R. Bbuilding Ffootprint permitted: Fifteen (15) Seventeen and one half percent (17.5%), or eleven hundred (1,100) square feet, whichever is greater.
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) Lot size:
 - (A) <u>Minimum area</u>: Twenty thousand (20,000) square feet, thirty percent (30%) reduction if sewered.
 - (B) <u>Minimum average width</u>: One hundred twenty (120) feet, thirty percent (30%) reduction if sewered.
- (3) Open space: Fifteen thousand (15,000) square feet minimum per family.

SECTION 12 P-I PUBLIC AND INSTITUTIONAL DISTRICT

12.01 Intent of district.

This Delistrict is intended to provide for those uses which serve a public need and/are principally of an institutional, educational, medical, or governmental nature (whether public or privately owned and either "for profit" or "not for profit") and serving a public need, (but not including the operation of a bar, Restaurant, or recreational facility as a commercial enterprise) unless authorized as a Conditional Use under Section 3.08(7)(Q) and 3.08(7)(U). Group homes as regulated by Statute, shall not be included as they are either allowed in other Delistricts or regulated pursuant to Section 3.08.

12.02 Permitted Uuses.

The following uses are permitted by right subject to review and approval of the Site Plan and Plan of Operation by the plan commission and the zoning administrator:

(1). Hospitals and clinics or rehabilitation facilities or centers.

150

Effective 05-xx-2016

- (2). Nursing home.
- (3). Schools.
- (4)- Mental health or substance abuse treatment, training, or counseling or rehabilitation facilities.
- (5)- Residential treatment, training or education facilities.
- (6). Municipal buildings.
- (7). Museums.
- (8)- Police and Fire stations.
- (9). Libraries.
- (10)- Penal reform institutions.
- (11). Military installations.
- (12)- Public service yards.
- (13): Publicly owned and operated parks, recreational uses, golf courses, and open space uses.
- (14). Other similar uses as determined by the plan commission and zoning administrator.

(Section 12.02 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

12.03 Permitted Accessory Uses.

- (1): Garages and <u>B</u>buildings for storage of vehicles and/or equipment, which is used in conjunction with the operation of a <u>P</u>permitted <u>U</u>+se.
- (2): Residential quarters used for other than a <u>Ppermitted Unse</u> under Section 12.02 shall be occupied only by individuals employed full-time on the premises and their families.
- (3): Stables, barns, or poultry houses provided that no Bbuilding which houses said Livestock or Ppoultry is closer than one hundred (100) feet to any Liot Line.
- (4). Horticulture, including greenhouses and nurseries and to the extent associated with an otherwise Ppermitted U+se, retail fruit and vegetable stands.
- (5): Signs displaying the name of the institution or facility provided they are no greater than fifty (50) square feet in area.
- (6)- Parking in accordance with Section 3.12.
- (7). Satellite dishes or other communication equipment apparatus.
- (8)- Temporary Uses: Lands and Beuildings within the Delistrict may be used on a temporary basis for private and commercial uses usually not more than 1 week in duration. Such uses might consist of carnivals, rental of said Beuildings for private gatherings, use of Beuildings for temporary commercial displays or trade fairs and similar functions for the purpose of fundraising or other special and unique events in conjunction with the Permitted Uese. Approval must be granted by the town board and the zoning administrator for such temporary use and subject to any condition that may be imposed.

(Section 12.03 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

12.04 Building Location:

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a <u>Local Road:</u>
 - 1. Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.

Setbacks Fifty (50) feet minimum.

- (2) Shore-Wetland Setback:-
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- (3) Conservancy Setback Seventy five (75) feet minimum.
- (4<u>3</u>) <u>Offset:</u>
 - (A) Principal Building -Fifty (50) feet minimum.
 - (B) Accessory Building Thirty (30) feet minimum.
 - (C) Additional regulations and exceptions from Section 3.09(3) apply.

(Section 12.04 was amended by Enrolled Ordinance 167-24, Section 1, effective 07-24-2012.)

12.05 Height Regulations.

- (1) Principal Buildings: —The regulations and exceptions of Section 3.10(1) applyThirty five (35) foot maximum, unless fire and emergency apparatus adequate to service a taller Bbuilding is available to service the Bbuilding on the subject parcel and verification of each apparatus² availability from the community providing the fire and emergency services to or for the subject parcel is filed with the Town Building Inspector and the County Zoning Administrator prior to the issuance of a Zoning Permit, in which event the maximum height of a Pprincipal Bbuilding on the subject parcel shall be the maximum height which such available apparatus can service (but such maximum height shall not be greater than sixty (60) feet).
- (2) <u>Farm Buildings</u> Sixty (60) feet maximum.
- (3) <u>Accessory Buildings</u> Twenty (20) feet maximum.
- (4) Additional regulations and exceptions from Section 3.10 apply.

(Section 12.05 was amended by Enrolled Ordinance 167-24, Section 2, effective 07-24-2012.)

152

12.06 Area Regulations.

No minimum required. The use will dictate the size of the parcel. However, no more than $\underline{sixty\ percent}$ (60%) of the subject parcel shall be of $\underline{Iimpervious\ \underline{S}}$ surfaces, consisting of roof tops, paved or gravel surface parking or service areas, and $\underline{forty\ percent}$ (40%) of the subject parcel shall be in vegetative cover or tillable soil

SECTION 13 B-1 RESTRICTED BUSINESS DISTRICT

13.01 Use regulations.

- (1) Permitted Uuses:
 - (A) Any use as permitted in the R-3 Residential Delistrict.
 - (B) The following retail or customer service establishments of a restrictive nature provided the location, building and Site Plan and Plan of Operation have been submitted to, and approved by, the plan commission and zoning administrator as being in keeping with the character of the surrounding residential area.
 - 1. Boarding or Llodging Hhouses.
 - Delicatessen.
 - Florist shop.
 - 4. Funeral home.
 - Gift shop.
 - 6. Interior decorator.
 - 7. Professional Ooffice or studio.
 - 8. Tea room or \underline{R} restaurant provided no liquor is served.
 - Tourist <u>H</u>home.
 - Any similar use subject to the approval of the plan commission and zoning administrator.
 - (C) Signs, subject to the following conditions:
 - 1. No \underline{S} sign shall exceed twelve (12) square feet in area.
 - No free standing Seign shall exceed ten (10) feet in height from the ground, and no Seign attached to a building shall project above an eave, cornice, or top parapet line of said building.
 - 3. Only one (1) <u>S</u>sign shall be permitted for any such <u>P</u>permitted \underline{U} use.
 - 4. No <u>S</u>sign shall include illuminating devices or be constructed of illuminated material, or be specifically illuminated, except by properly shielded cover or back lighting of a nonintermittent type on an opaque background, such source of light not to be more than two (2) feet from the vertical face to be illuminated.

 $(Section\ 13.01(1)(B)\ was\ amended\ by\ Enrolled\ Ordinance\ 159-69,\ effective\ 1-17-05.)$

153

<u>(1)</u>	Road Setback:				
	(A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:				
	 Thirty-five (35) feet minimum if the Lot is part of a subdivision record after October 1, 2016. 				
	2. Thirty-five (35) feet minimum if the Lot is served by sewer.				
	(B) Additional regulations and exceptions from Section 3.09(1) apply.				
<u>(2)</u>	Wetland Setback:				
	(A) Seventy-five (75) feet minimum.				
	(B) Additional regulations and exceptions from Section 3.09(2) apply.				
<u>(3)</u>	Offset:				
	(A) Twenty (20) feet minimum, unsewered.				
	(B) Fourteen (14) feet minimum, sewered.				
	(C) Additional regulations and exceptions from Section 3.09(3) apply.				
(1)	Setback: Fifty (50) feet minimum.				
(2)	Offset: Twenty (20) feet minimum.				
13.03 Height	regulations:- The regulations and exceptions of Section 3.10 apply.				
(1)	Principal building: Thirty five (35) feet maximum.				
(2)	Accessory buildings: Fifteen (15) feet maximum.				
13.04 Area r	egulations.				
(1)	Floor areaArea and Building Footprint:				
	(A) Minimum Floor Area required for residential purposes Single-family Dwelling				
	1. First floor: Nine Eight hundred fifty (900850) square feet.				
	2. Total , one (1) family : One thousand Eleven hundred (1,000100) square				

154

Effective 05-xx-2016

- (B) <u>Maximum F. A. R. Building Footprint permitted</u>: Twenty (20) percent (20%), or eleven hundred (1,100) square feet, whichever is greater.
- (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) <u>Lot size</u>:
 - (A) <u>Minimum area</u>: Twenty thousand (20,000) square feet, thirty percent (30%) reduction if sewered.
 - (B) Minimum average width: One hundred twenty (120) feet, thirty percent (30%) reduction if sewered.
- (3) Open space: Fifteen thousand (15,000) square feet minimum per family.

SECTION 14 B-2 LOCAL BUSINESS DISTRICT

14.01 Use regulations.

- (1) <u>Permitted Uuses</u>:
 - (A) Any use as permitted in the B-1 Restricted Bousiness Delistrict.
 - (B) Any of the following retail and customer service establishments, providing the location, building and Site Plan and Plan of Operation are submitted to and approved by the plan commission and the zoning administrator:
 - 1. Art shop.
 - 2. Appliance store.
 - 3. Bakery (not over ten (10) employees).
 - 4. Barber shop.
 - 5. Beauty shop.
 - 6. Bank or savings and loan office.
 - 7. Clinic.
 - 8. Clothing or dry goods store.
 - 9. Confectionery store.
 - 10. Drug store.
 - 11. Furniture store.
 - 12. Book or stationery store.
 - 13. Fruit and vegetable market.
 - 14. Grocery or other food products store.
 - 15. Hardware store.
 - 16. Ice cream store.
 - 17. Jewelry store.
 - 18. Meat and fish market.
 - Music and radio store.
 - 20. News-stand.
 - 21. Notion or variety shop.
 - 22. Parking lot.
 - 23. Pharmacy.

- 24. Radio and television sales and repair shop.
- 25. Photographer.
- 26. Restaurant.
- 27. Shoe store.
- 28. Soda fountain.
- 29. Tailor or dressmaking shop.
- 30. Telegraph and telephone office and telephone exchange.
- 31. Utility company office.
- Any similar use subject to the approval of the plan commission and zoning administrator.
- (C) Garages for storage of vehicles used in conjunction with the operation of the business.
- (D) Signs, subject to the following conditions:
 - 1. No <u>S</u>sign shall exceed forty (40) square feet in area.
 - 2. Illuminated <u>S</u>signs shall not exceed twenty (20) square feet.
 - 3. Signs shall be limited to one (1) <u>S</u>sign per store side of building.
 - 4. No free standing Seign shall exceed twenty (20) feet in height from the ground, and no attached Seign shall be higher than four (4) feet above the top of the roof line or in any case exceed thirty-five (35) feet in height.

(Section 14.01(1)(B) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

14.02 Building location.

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.

Setback: Fifty (50) feet minimum.

- (23) Offset:
 - (A) <u>Buildings used solely for commercial purposes</u>: Ten (10) feet minimum.

	(B)	Buildings used in whole or part for residence-residential purposes: Twenty (20) feet			
		minimum, unsewered and fourteen (14) feet, sewered.			
	<u>(C)</u>	Additional regulations and exceptions from Section 3.09(3) apply.			
14.03 Height	regulat	ions:- The regulations and exceptions of Section 3.10 apply.			
(1)	Principal building: Thirty five (35) feet maximum.				
(2)	Accessory buildings: Fifteen (15) feet maximum.				
4.04 Area re	omilatio	ns			
(1)	Ü	area Area and Building Footprint:			
` '	(A)	Minimum Ffloor Aarea required for residence Single-family Dwellingpurposes:			
		1. <u>Buildings used solely for residence purposes:</u>			
		(a1) <u>First floor</u> : <u>Nine-Eight</u> hundred <u>fifty</u> (900850) square feet.			
		(b2) <u>Total</u> : One (1) family: One thousand Eleven hundred (1,000 100) square feet			
		2. <u>Buildings used for both residence and business purposes:</u> Nine hundred (900) square feet per family.			
	(B)	Maximum F. A. R. Building Footprint permitted: Fifty (50) percent (50%).			
	<u>(C)</u>	Additional regulations and exceptions from Section 3.11 apply.			
(2)	Lot size:				
	(A)	<u>Minimum area</u> : Twenty thousand (20,000) square feet, thirty percent (30%) reduction if sewered.			
	(B)	<u>Minimum average width</u> : One hundred twenty (120) feet, thirty percent (30%) reduction if sewered.			
(3)	Open	space: Fifteen thousand (15,000) square feet minimum per family.			
ECTION 15	5 B-3 G	ENERAL BUSINESS DISTRICT			
5.01 Use reg	ulation	S.			
(1)		itted U u ses:			
(1)	· /				
	(A)	Any use as permitted in the B-2 \underline{L} -local \underline{B} -business \underline{D} -district, except that residential use shall be permitted only in conjunction with or accessory to an otherwise \underline{P} -permitted \underline{U} -use.			
		157 Effective 05-xx-2016			

- (B) The following business and trades of a more general nature, normally serving a larger trade area, providing the location, building and Site Plan and Plan of Operation are submitted to and approved by the plan commission and zoning administrator:
 - 1. Wholesalers and distributors.
 - Theaters, <u>De</u>ance <u>Healls</u>, <u>Aercades</u>, video game parlors and other amusement places.
 - Used car lots.
 - 4. Dry cleaning and dying establishments.
 - 5. New and used automobile sales rooms and lots, sale of snowmobiles, personal watercraft, boats and marina equipment along with repair and service shops for such equipment, storage yards and garages for said equipment, vehicles and supplies, but not including the storage and/or sale of junked or wrecked equipment or parts.
 - 6. Printing and publishing houses.
 - 7. Dairies and bottling plants.
 - 8. Laundries.
 - Lockers and cold storage plants.
 - 9-10. A Building, or portion thereof, or a Building designed with self-contained units, which is leased by the owner for storage.
 - 40-11. Any similar use subject to the approval of the plan commission and zoning administrator.
- (C) Signs, billboards and other similar advertising media.

(Section 15.01(1)(B) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.02 Building location.

- (1) Road Setback:
 - (A) Fifty (50) feet minimum, with the following exceptions when measured from a Local Road:
 - Thirty-five (35) feet minimum if the Lot is part of a subdivision recorded after October 1, 2016.
 - 2. Thirty-five (35) feet minimum if the Lot is served by sewer.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.

Setback: Fifty (50) feet minimum.

Commented [BA67]: Modified language to be consistent with shoreland ordinance.

(23)	Offset

- (A) <u>Buildings used solely for commercial purposes</u>: Ten (10) feet minimum.
- (B) <u>Buildings used in whole or part for residence residential purposes</u>: Twenty (20) feet minimum, <u>unsewered and fourteen (14) feet minimum</u>, <u>sewered</u>.
- (C) Additional regulations and exceptions from Section 3.09(3) apply.
- 15.03 Height regulations: The regulations and exception of Section 3.10 apply.
 - (1) Principal building: Thirty five (35) feet maximum.
 - (2) Accessory buildings: Fifteen (15) feet maximum.

15.04 Area regulations.

- (1) Floor area Area and Building Footprint:
 - (A) Minimum Floor Area required for residence-Single-family Dwellingpurposes: Nine hundred (900) square feet per family.
 - 1. First floor: Eight hundred fifty (850) square feet.
 - 2 Total: Eleven hundred (1,100) square feet.
 - (B) <u>Maximum F. A. R. Building Footprint permitted</u>: Fifty (50)-percent (50%).
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) <u>Lot size</u>:
 - (A) Minimum area: Twenty thousand (20,000) square feet, thirty percent (30%) reduction if sewered.
 - (B) Minimum average width: One hundred twenty (120) feet, thirty percent (30%) reduction if sewered.
- (3) Open space: Fifteen thousand (15,000) square feet minimum per family.

SECTION 15.1 B-4 COMMUNITY BUSINESS DISTRICT

15.11 Statement of Intent.

This Delistrict is intended to provide for individual or large groups of retail and customer service retail in a "shopping center setting." The intent is to designate those uses on a predetermined land use plan. This District must be located within one (1) mile of a major highway interchange or at or near the intersection of two (2) major Heighways. The District is designed for convenience or one-stop shopping and is intended to serve the entire community.

15.12 Review Process.

The plan commission and zoning administrator must review and approve building plans and a Site Plan and Plan of Operation for each building proposal or change in use in order to achieve a satisfactory relationship between the <u>Ppermitted Uuse</u>, its operating characteristics, the arterial highway system, and adjacent uses.

(Section 15.12 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.13 Permitted Principal Uses.

- A.(1) <u>Permitted Principal Uses</u>: The following retail establishments, selling of and storing of only new merchandise.
 - 4.(A) Art, dance, music teaching studios or other similar uses.
 - 2.(B) Architects, engineers or other Perofessional Ooffices.
 - 3.(C) Bakery goods stores.
 - 4.(D) Banks, savings and loan association and other financial institutions.
 - 5.(E) Barber and beauty shops.
 - 6.(F) Candy, confectionery stores.
 - 7.(G) Clothing stores.
 - 8.(H) Delicatessens.
 - 9.(I) Dentist, physician or other similar professional health offices.
 - 10.(J) Drugstores.
 - 11.(K) Dry cleaning pick-up and delivery establishments.
 - 12.(L) Retail florists.
 - 13.(M) Fruit stores.
 - 14.(N) General public bookstores.
 - 15.(O) Gift stores.
 - 16.(P) Grocery stores.
 - 17.(Q) Hardware stores, paint or decorating stores.
 - 18.(R) Hobby shops.
 - 19.(S) Meat, fish, or poultry markets.
 - 20.(T) Optical stores.
 - 21.(U) Packaged beverage stores.
 - 22.(V) Photo and film pick-up stores.
 - 23.(W) Shoe repair shops.
 - 24.(X) Shoe stores.
 - 25.(Y) Soda and ice cream stores.
 - 26.(Z) Sporting goods stores.
 - 27.(AA) Tobacco stores.
 - 28.(AB) Variety stores.
 - 29.(AC) Vegetable stores.
 - 30.(AD) Video stores.
 - 31.(AE)Department stores.
 - 32.(AF)—Cafes or Rrestaurants.

B.(2) Permitted Accessory Uses:

4.(A) Garages for storage of licensed vehicles used in conjunction with the operation of a

business

- 2.(B) Off_street parking and loading areas.
- C(3) Off-street Parking and Loading Areas: Provided detailed site plans, including landscaping and buffering, are submitted to and approved by the plan commission and zoning administrator. Front, rear and side yard paved setbacks shall not be less than ten (10) feet. Shared drives and shared parking areas may be allowed among adjacent properties where appropriate and practical through the use of cross-easements or other internal linkages between the properties with approval of the plan commission and zoning administrator.
- D.(4) Signs: Allowed by conditional use to evaluate size, orientation and compatibility with the entire site. Landscape and site plans for the Seigns must be submitted to, reviewed and approved by the plan commission and zoning agency.

(Sections 15.13(C) and (D) were amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.14 Permitted Conditional Uses

Any use similar in character to the Ppermitted \underline{U} asses listed above conducted as a retail business on the premises, catering to the general public and compatible to the character of adjacent areas. Additionally, only the following uses are permitted conditional uses:

- A.(1) Fast food establishments.
- B.(2) Service stations.
- \bigcirc . Home improvements stores.
- D-(4) Communications facilities, including antenna masts and satellite dish antennas located in the rear yard and roof-mounted satellite dish antennas and roof-mounted solar collectors on the roof of the principal Setructure, provided a registered engineer shall certify that the Setructure is adequate to support the load. All such facilities shall be screened from view with the facility and screening approved by the plan commission and zoning agency.
- **E.**(5) Entertainment facilities.
- F.(6) Hospitals and health care facilities.
- G.(7) All uses operated greater than 16 hours per day.
- H.(8) Limited outside storage or display.

(Section 15.14D was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.15 Prohibited Uses.

- 1.(1) Any new residential dwellings.
- 2.(2) Car, truck and trailer sales lots new and used.
- 3.(3) Outside bulk sales, bulk storage or bulk display of materials or products.
- 4.(4) Drive-in theaters.

15.16 Height Regulations: The regulations and exceptions of Section 3.10 apply.

- 1. No principal structure shall exceed thirty-five (35) feet in height.
- 2. No accessory structure shall exceed fifteen (15) feet in height.

15.17 Lot Area, Frontage, and Yard Regulations.

- 1.(1) Lot Size Unsewered:
 - (a)(A) Total site may not be less than ten (10) acres with out-lots being created by a PUD.
 (b)(B) When an unsewered Ltot is created, the plan commission and zoning administrator may require the principal Setructure on the Ltot to be arranged and dimensioned so as to allow further division of the parcel at such time as sewer becomes available.
- 2.(2) Lot Size Sewered:
- (a)—Free-standing building sites shall have a minimum lot size of 20,000 square feet.
- 3-(3) Lot Width (out-lots): Free-standing building sites shall have a minimum average width of one hundred twenty (120) feet (sewered) and two hundred forty (240) feet (unsewered).
- 4.(4) Front YardRoad Setback:
 - (A) ____All <u>BbuildingsStructures</u> shall be located not less than fifty (50) feet from any street or highway right-of-way.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- 5.(5) Side Yard Setback:
 - (A) Shall All Structures shall have a minimum Opffset of ten (10) feet; however, the plan commission and zoning administrator may require a greater Opffset to accommodate future expansion of the a Beuilding or future paved driveway access to the rear of the a buildingBuilding.
 - (B) Additional regulations and exceptions from Section 3.09(3) apply.
- 6.(6) Rear Yard Setback:
 - (A) Shall All Structures shall have a minimum Oeffset of twenty-five (25) feet.
 - (B) Additional regulations and exceptions from Section 3.09(3) apply.
- 7.(7) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- 7(8). Floor Area: Initial construction proposed on each Lator shall be a minimum of five thousand (5,000) square feet.

8(9). Floor Area RatioBuilding Footprint:

- (aA) Maximum of thirty percent (30%), unsewered.
- (bB) Maximum of fifty percent (50%), sewered.
- (eC) Not more than sixty-five percent (65%), unsewered or seventy percent (70%), sewered of any Ltot shall be covered with Bbuildings, surfaced pavement, parking, loading areas, or other covering materials which are impervious to surface absorption.

(Sections 15.17(1) and (5) were amended by Enrolled Ordinance 159-69, effective 1-17-05.)

SECTION 15.2 BP-MIXED USE BUSINESS PARK DISTRICT.

15.21 Statement of Intent.

- (1)A. This Delistrict is to be used as an implementation tool for the municipality's adopted Master Plan where it designates specific types of limited office, professional services, retail, business uses, and light industrial uses free of outside storage or display, serving the adjacent industrial and business uses in larger communities. These uses may occur on individual sites or as part of a planned larger development. This District can only be located within one mile of a freeway interchange or at an intersection of two state trunk highways and be used only where specific types of uses are designated on a locally adopted Master Plan.
- (2)B. The plan commission and zoning administrator shall review and consider for approval a building plan and a Site Plan and Plan of Operation for each Beuilding or use proposal to determine if the proposed development complies with the locally adopted plan. The review shall be required to achieve a satisfactory relationship between the Ppermitted Uese, its operating characteristics, the arterial highway system and adjacent uses such as retail, residential, customer service, business park and light industrial.

(Section 15.21B was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.22 Permitted Principal Uses.

- A(1). Permitted Principal Uses: The following Perincipal Uses are permitted provided the building plan and a Site Plan and Plan of Operation have been submitted to and approved by the plan commission and zoning administrator. Development prior to sewers being installed in the area is contingent upon the ability of each use to obtain the necessary sanitary septic system approvals from the proper authorities.
 - L(A) Community and customer service establishments including eating and drinking establishments, overnight lodging, and indoor commercial recreational facilities such as bowling alleys, physical fitness salons and theaters. Such establishments may not be located adjacent to or opposite a residential district (as designated in the Master Plan) and must be within one thousand (1,000) feet of a state trunk highway except as identified by Section 15.23 of this Ordinance.

- 2-(B) Offices for the professions, business and utilities, studios, health care facilities and clinics (not providing for overnight stay).
- 3-(C) Automobile Drive-thru facilities such as financial services, fast food establishments, provided the service rendered or product sold is provided to each customer while they remain in or near their cars and provided to one or a few vehicles at a time (as contrasted with an outdoor theater where all cars are serviced at once). Such facilities must be located within one thousand (1,000) feet of a state trunk highway.
- 4.(D) Laboratory, research and servicing operations. Servicing operations shall not be for general retail or public consumption but limited to the servicing of the specific product manufactured or assembled at that site.
- 5-(E) Trades or light industrial operations of limited intensity, including manufacturing, assembly, fabrication, and processing operations, warehousing (on parcels greater than three (3) acres), wholesaling, and distribution operations, except as otherwise prohibited.
- B-(2) Permitted Accessory Uses: The following Accessory Uses are permitted provided the building or structure plan and a Site Plan and Plan of Operation have been submitted to and approved by the plan commission and zoning administrator
 - 4-(A) Garages attached to the principal Setructure for storage of vehicles used in conjunction with operation of the business.
 - 2.(B) Off-street parking and loading areas, provided detailed site plans, including landscaping and buffering, are submitted to and approved by the plan commission and zoning administrator. Front, rear and side yard paved setbacks shall be not less than ten (10) feet. Shared drives and shared parking areas among adjacent properties where appropriate and practical are desirable through the use of crosseasements or other internal linkages between properties.
 - 3-(C) Communications facilities, including antenna masts and satellite dish antennas located in the rear yard and roof-mounted solar collectors on the roof of the principal Setructure, provided a registered engineer shall certify that the Setructure is adequate to support the load. All such facilities shall be screened from view with the facility and screening approved by the plan commission and zoning administrator. Screening shall be required for any satellite dish exceeding 24 inches in size and where more than one exists per property.
 - 4.(D) Bus or taxi shelters or waiting areas.

(Section 15.22 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.23 Permitted Conditional Uses.

Only the following conditional uses may be permitted provided the building plan and a Site Plan and Plan of Operation have been submitted to and approved by the plan commission and zoning agency:

1.(1) Child care facilities not accessory to a principal office use.

- (2)2. Cooling towers, silos or other similar uses accessory to the permitted Pprincipal Utses.
- 3.(3) Automobile service and fuel stations.
- 4.(4) Restaurants to be located within <u>one thousand (1,000)</u> feet of any residential area designated on the Master Plan.
- 5-(5) Fuel or vehicle repair stations serving trucks other than company motor vehicles. Such facilities shall not be located within one thousand (1,000) feet of a residential area designated on the Master Plan unless having direct access to a state trunk highway.
- 6.(6) Any outdoor recreation involving night operation with limitations on hours of operation.
- 7.(7) Retail stores and shops located beyond one thousand (1,000) feet of a state trunk highway.
- 8.(8) Retail uses operated more than sixteen (16) hours per day.
- 9.(9) Health care facilities providing for overnight stays.
- 10.(10) Commercial vehicle terminals with roadway access to a state trunk highway.

(Section 15.23 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.24 Prohibited Uses.

- 4-(1) Offensive Uses. No uses shall be permitted or maintained which, when conducted under adequate conditions and safeguards in compliance with the provisions of this Chapter and any additional conditions or requirements prescribed by the plan commission and zoning administrator, are or may become hazardous, noxious or offensive due to emission or odor, dust, smoke, cinders, gas, fumes noise, vibrations, beat frequency, refuse matter, watercarried waste or fugitive lighting.
- 2.(2) Specific Prohibited Uses. The following uses are specifically prohibited:
 - a.(A) Truck or trailer sales.
 - b.(B) New and used car lots.
 - e.(C) Car wash facilities.
 - **d.**(D) Bulk sales, storage or display of lumber.
 - e.(E) Outdoor displays or storage of materials.
 - **f.**(F) Drive-in theaters.
 - g.(G) Mobile Hhome sales, service or campgrounds.
 - H.(H) Recreational vehicle, all terrain vehicle or outdoor recreational vehicle sales and service.
 - i.(I) Junkyards or wrecking yards.
 - j-(J) Refining of petroleum or its products.
 - **k**(K) Petroleum storage yards, not including petroleum storage accessory to a permitted conditional use.
 - **!.(L)** Animal reduction facilities.
 - m.(M) Forges.
 - n.(N) Foundries.
 - (O) Garbage or medical incinerators.

- p.(P) Rubbish storage or transfer station.
- **q.**(Q) Slaughterhouses.
- F.(R) Stockyards.
- s.(S) Tanneries.
- **EUI** Bulk storage of salt, fertilizer, or similar materials; explosives, gasoline or other petroleum products in excess of 50,000 gallons, and grease.
- **u.**(U) Storage of radioactive materials.
- Manufacturing or processing of ammonia, asbestos, asphalt, cement, chlorine, cold tar, creosote, explosives, fertilizer, glue, gypsum, insecticides, poison, pulp, proxylin, radium and radioactive materials.
- w.(W) Outside product or equipment testing.
- *****-(X) Mini-warehouses or multi-tenant storage.
- 3.(3) <u>Dwellings</u>: No new dwellings or <u>R</u>residences of any kind.

(Section 15.24(1) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

- 15.25 **Height Regulations:** The regulations and exceptions of Section 3.10 apply.
 - 1. No principal structure shall exceed thirty-five (35) feet in height.
 - 2. No accessory structure shall exceed fifteen (15) feet in height.
- 15.26 Lot Area, Frontage, and Yard Regulations.
 - 1.(1) Lot Size Unsewered:
 - (aA) Building site shall have a minimum lot size of <u>forty thousand (40,000)</u> square feet.
 - (bB) When an unsewered Liot is created, the plan commission and zoning administrator may require the principal Setructure on the Liot to be arranged and dimensioned so as to allow further division of the parcel at such time as sewer becomes available.
 - 2.(2) Lot Size Sewered:

Building sites shall have a minimum lot size of <u>twenty thousand (20,000)</u> square feet.

- 3-(3) Lot Width: Building sites shall have a minimum average width of one hundred twenty (120) feet (sewered) and two hundred forty (240) feet (unsewered).
- 4.(4) Front-Road Yard-Setback:
 - (A) All <u>BbuildingsStructures</u> shall be located not less than fifty (50) feet from any street or highway right-of-way. Signs not less than twenty (20) feet from any street or highway right-of-way.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- 5.(5) Side Yard Setback:
 - (A) Shall-All Structures shall have a minimum Ooffset of ten (10) feet; however, the

plan commission and zoning administrator may require a greater Oeffset to accommodate future expansion of the a Beuilding or future paved driveway access to the rear of the a Beuilding.

- (B) Additional regulations and exceptions from Section 3.09(3) apply.
- 6.(6) Rear yard Yard Setback:
 - (A) All Structures sShall have a minimum Ooffset of twenty-five (25) feet.
 - (B) Additional regulations and exceptions from Section 3.09(3) apply.
- (7) Wetland Setback:
 - (A) Seventy-five (75) feet minimum setback.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- 7(8)- Floor Area: Initial construction proposed on each lot Lot shall be a minimum of five thousand (5,000) square feet.
- 8(9)Floor Area RatioBuilding Footprint and Impervious Surface: Maximum of thirty percent (30%). In addition, no more than sixty-five percent (65%) of any Ltot shall be covered with Beuildings, surface pavement, parking, loading areas, or other covering materials which are impervious to surface absorption prior to the installation of sanitary sewers. Upon installation of sanitary sewers, the total impervious coverage shall not exceed seventy-five percent (75%) and the floor area ratioBuilding Footprint shall not exceed fifty percent (50%).

(Sections 15.26(1) and (5) were amended by Enrolled Ordinance 159-69, effective 1-17-05.)

15.27 Signs.

- 4-(1) Landscape and Site Plans for Seigns must be submitted to, reviewed and approved by the plan commission and the zoning administrator.
- 2.(2) Sign regulations:
 - (aA) Wall Ssign: Placed on or against the exterior wall of the Bbuilding or one projecting Ssign attached to the Bbuilding front may be permitted and shall be subject to the following:
 - (1)1. Single-use structure Seigns shall not exceed one-half (.5) square footfeet for each one (1) foot width of the Beuilding.
 - (2)2. Multi-use structure Seigns shall not exceed one-quarter (.25) square footfeet for each one (1) foot in width per front foot per individual use.
 - (bB) Free standing Seigns: One free standing Seign may be permitted per property and may be in conjunction with a wall Seign and may not exceed thirty (30) square feet in area on each sign face. Free standing Seigns may not be closer than the one

hundred fifty (150) feet from another free standing Ssign.

- (eC) Signs used for identification of individual tenants in multi-tenant buildings must be uniform with regard to panel design, letter style and color. Said Ssign may contain painted metal surfaces with or without illumination or individual letters routed out of metal, plastic or wood surfaces.
- (dD) Signs may be non-illuminated or internally illuminated.
- (eE) The materials of the Ssign shall be compatible to the adjacent building materials.

(Section 15.27(1) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

SECTION 16 Q-1 QUARRYING DISTRICT

16.01 Use regulations.

- (1) Permitted Uuses:
 - (A) Any use as permitted in the A-1 Aagricultural Delistrict.
 - (B) Quarrying, although permitted by right, shall be authorized as a conditional use under Section 3.08 of this Ordinance. By placing a property in this category, it has been determined that the subject area is appropriate for such Qequarrying designation and the issuance of a conditional use permit to authorize the Qequarrying of the site shall be conditional on compliance with the standards and regulations as set forth in Section 3.08(7)(S).
 - (C) The following related operations, where accessory to the permitted quarrying operation, subject to the regulations of Section 3.08(7)(S)₂.
 - 1. The manufacture of concrete building blocks or other similar blocks.
 - 2. Production of ready-mixed concrete.

16.02 Building location.

- (1) Road Setback:
 - (A) Quarrying operations: As required by Section 3.08(7)(S).
 - (B) Other Ppermitted Uuses: Fifty (50) feet minimum, unless served by sewer and measured from a Local Road, in which case, the setback is thirty-five (35) feet minimum.
 - (C) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.

		(B)	Additional regulations a	and exceptions from Section 3.09(2) apply.
· [(<u>23</u>)	Offset:		
		(A)	Quarrying operations: A	As required by Section 3.08(7)(S).
[(B)	Other Ppermitted Uuses	s: Twenty (20) feet minimum.
I		<u>(C)</u>	Additional regulations a	and exceptions from Section 3.09(3) apply.
16				d exceptions from Section 3.10 apply, except that Buildings limited to a maximum height of sixty (60) feet.
	(1)	Princip	oal building: Thirty five (3	(35) feet maximum.
	(2)	Access	ory buildings:	
		(A)	Quarrying operations: S	Sixty (60) feet maximum.
		(B)	Other permitted uses: Fi	iifteen (15) feet maximum.
16	.04 Area re	gulation	ıs.	
	(1)	Floor a	reaArea and Building Foo	potprint:
		(A)	Minimum Floor Area re	equired for residence-Single-family Dwellingpurposes:
			1. <u>First floor</u> : Nine	e-Eight hundred fifty (900850) square feet.
			2. <u>Total, one (1) fa</u>	<u>Family</u> : One thousand <u>Eleven hundred</u> (1,000100) square feet.
		(B)		dding Footprint permitted: Ten (10)-percent (10%), or eleven e feet, whichever is greater.
		<u>(C)</u>	Additional regulations a	and exceptions from Section 3.11 apply.
	(2)	Lot size	<u>e</u> :	
		(A)	Minimum area: Three (3	(3) acres.
		(B)	Minimum average width	th: Two hundred (200) feet.
	(3)	Open s	pace: Two acre minimum	n per family.
SE	CCTION 17	M-1 LI	MITED INDUSTRIAL	DISTRICT
17	.01 Use regu	ılations.		
	(1)	Permitt	ted U uses :	
			169	Effective 05-xx-2016

- (A) Any use as permitted in a B-3 General B-business or A-1 Agricultural Delistrict, except that residential use shall be permitted only in conjunction with or accessory to an otherwise Permitted useUse.
- (B) Trades or industries of a restrictive character which are not detrimental to the Delistrict or to the adjoining residential areas by reason of appearance, noise, dust, smoke or odor, provided the location, building plan and a Site Plan and Plan of Operation have been submitted to and approved by the plan commission and zoning administrator, but not including any use enumerated under Section 18.01(1)(C) or any of the following:
 - 1. Junk yards, as regulated by Section 3.08(7)(V).
 - 2. Drop forges, foundries, refineries, tanneries or any similar use, the normal operation of which causes objectionable noise, odor, dust or smoke.

(Section 17.01(1)(B) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

17.02 Building location.

- (1) Road Setback:
 - (A) Fifty (50) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.

Setback: Fifty (50) feet minimum.

- $(\frac{23}{})$ Offset:
 - (A) Ten (10) feet minimum_. (Exception: wexcept where a lot-Lot abuts on a district boundary line of a more restrictive Delistrict permitting residence residential use, the following restrictions shall apply:)
 - (A) Buildings or uses permitted in the more restrictive Delistrict shall comply with the offset requirements of the more restrictive Delistrict.
 - 2. (B)—Buildings or uses not permitted in the more restrictive Delistrict shall provide a fifty (50) feet minimum Oeffset and shall be screened from the more restrictive Delistrict by a Pelanting Secreen at least six (6) feet high and fifteen (15) feet in width.

	(B) Additional re	egulations and exceptions from Section 3.09(3) apply.		
17.03 Heigh	regulations.			
(1)	Principal building Building: Sixty (60) feet maximum. If the Structure is located on a Lo less than sixty-five (65) feet in width, the provisions of Section 3.10(1) apply.			
<u>(2)</u>	_(2)Accessory b	uildingsBuildings: Sixty (60) feet maximum.		
<u>(3)</u>	Additional regulation	ns and exceptions from Section 3.10 apply.		
17.04 Area	gulations.			
(1)	(1) Floor areaAı	ea and Building Envelope Footprint:		
	(A) <u>Minimum Fl</u> hundred (900) square	loor Area required for residence purposesSingle-family Dwelling: 4 e feet per family.		
	1. First	t floor: Eight hundred fifty (850) sq. ft. minimum.		
	2. Tota	al: Eleven hundred (1,100) sq. ft. minimum.		
		- A. R. Bbuilding Ffootprint permitted: Seventy (70) percent (70%).		
	.,	egulations and exceptions from Section 3.11 apply.		
(2)	Lot size:			
	(A) <u>Minimum area</u> : One (1) acre.			
	(B) <u>Minimum av</u>	verage width: One hundred fifty (150) feet.		
(3)	Open space: No requ	virement.		
SECTION 1	M A CENEDAL IN	DUSTRIAL DISTRICT		
		DUSTRIAL DISTRICT		
18.01 Use re	ilations.			
(1)	Permitted Uuses:			
	(A) Any use as p	permitted in the M-1 Limited Lindustrial Delistrict.		
	(B) Quarrying, s	ubject to the regulations of Section 3.08(7)(S).		
	their location	ommercial or industrial use not otherwise prohibited by law, providen, building plan and a Site Plan and Plan of Operation have been and approved by the plan commission and zoning administrator, ex		

Cement, lime, gypsum, or plaster of paris manufacture.

Effective 05-xx-2016

the following:

171

- Acid manufacture.
- Manufacture of explosives, but not including the making of small arms ammunition.
- 4. Storage of explosives, except as incidental to a Permitted Utse.
- Fertilizer manufacture.
- 6. Offal or dead animal reduction.
- 7. Glue manufacture, fat rendering or distillation of bones.
- 8. Stockyards or commercial slaughter of animals.

(Section 18.01(1)(C) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

18.02 Building location.

- (1) Road Setback:
 - (A) Fifty (50) feet minimum.
 - (A)(B) except that wWhere the opposite road frontage is in a residential or agricultural district, a one hundred (100) foot minimum Rroad Setback shall be required.
 - (C) Additional regulations and exceptions from Section 3.09(1) apply.
- (2) Wetland Setback:
 - (A) Seventy-five (75) feet minimum.
 - (B) Additional regulations and exceptions from Section 3.09(2) apply.
- (23) Offset:
 - (A) Ten (10) feet minimum, except that where a <u>L</u>tot abuts on a district boundary line of a more restrictive <u>D</u>district permitting <u>residence-residential</u> use, the following regulations shall apply:
 - (A) —Buildings or uses permitted in the more restrictive <u>D</u>district shall comply with the offset requirements of the more restrictive <u>D</u>district.
 - 2. (B) —Buildings or uses not permitted in the more restrictive <u>D</u>district shall provide a one hundred (100) foot minimum <u>D</u>offset from a restricted or local business district and a two hundred (200) foot minimum <u>D</u>offset from a residential or agricultural district and shall be screened from the more restrictive <u>D</u>district by a <u>P</u>planting <u>S</u>-creen at least six (6) feet high and fifteen (15) feet in width.
 - (B) Additional regulations and exceptions from Section 3.09(3) apply.

18.03 Height regulations.

(1) Principal buildingBuilding: Sixty (60) feet maximum. If the Structure is located on a Llot of less than sixty-five (65) feet in width, the provisions of Section 3.10(1) apply.

- (2) <u>Accessory Bbuildings</u>: Sixty (60) feet maximum.
- (3) Additional regulations and exceptions from Section 3.10 apply.

18.04 Area regulations.

- (1) Floor area Area and Building Footprint:
 - (A) Minimum Floor Area required for residence-Single-family Dwellingpurposes: Nine hundred (900) square feet per family.
 - 1. First floor: Eight hundred fifty (850) sq. ft. minimum.
 - 2. Total: Eleven hundred (1,100) sq. ft. minimum.
 - (B) <u>Maximum F.A.R.Building Footprint- permitted</u>: Seventy (70) percent (70%).
 - (C) Additional regulations and exceptions from Section 3.11 apply.
- (2) Lot size:
 - (A) Minimum area: One (1) acre.
 - (B) Minimum average width: One hundred fifty (150) feet.
- (3) Open space: No requirement.

SECTION 19 BOARD OF ADJUSTMENT

19.01 Establishment.

- (1) <u>Authority</u>: There is hereby created a Board of Adjustment pursuant to Section 59.694 of the Wisconsin Statutes, to consist of five (5) members and two (2) alternates to be appointed by the County Executive and confirmed by the County Board. The first appointments shall be for a term of one (1), two (2), and three (3) years respectively, and thereafter on July 1 of each year the new appointment shall be for three (3) year terms.
- (1) General: All members of the board shall reside within the county and outside the limits of incorporated areas, provided, however, that no two (2) members shall reside in the same town. A vacancy shall be filled for the unexpired term of any member whose term becomes vacant, by appointment of the Ceounty Eexecutive and confirmation by the Ceounty Beoard. The actual and necessary expenses incurred by the board in performance of its duties shall be paid and allowed as cases of other claims against the county. The members of the board shall also receive per diem compensation as provided for by the Ceounty Beoard.

(Sections 19.01(1) and (2) were amended by Enrolled Ordinance 159-69, effective 1-17-05.)

19.02 Rules.

- (1) General: The board shall elect its own chairman to hold office for one (1) year and until his successor is elected. The chairman, or in his absence the acting chairman, may administer oaths and compel the attendance of witnesses. The board shall keep minutes of its proceedings, showing the vote of each member upon each question, or, if absent, or failing to vote, indicating such fact, and shall keep records of its examinations, and other official actions, all of which shall be immediately filed in the office of the board and shall be a public record.
- (2) Meetings: Meetings of the board shall be held at the call of the chairman and at such other times as the board may determine, and shall be open to the public.
- (3) <u>Procedural</u>: The board shall adopt such other rules governing its procedures as are necessary, consistent with this Ordinance.
- (4) <u>Cooperation with zoning agency</u>: The board shall keep the county zoning agency informed as to any matters brought before it and shall call upon the zoning agency for such information as is pertinent to the matters under consideration.

19.03 Powers.

- (1) Defined: The Bboard of Andjustment shall have the following powers as defined by statute:
 - (A) To hear and decide appeals where it is alleged there is error in any order, requirement, decision or determination made by an administrative official in the enforcement of Section 59.69 Wisconsin Statutes, or of this Ordinance.
 - (B) To hear and decide Sepecial Eexceptions to the terms of this Ordinance upon which such board is required to pass under this Ordinance.
 - (C) To authorize upon appeal in specific cases such <u>V</u> variances from the terms of this Ordinance as will not be contrary to the public interest, where owing to special conditions a literal enforcement of the provisions of this Ordinance will result in practical difficulty or unnecessary hardship, so that the spirit of this Ordinance shall be observed, public safety and welfare secured, and substantial justice done.
- (2) Additional requirements: In making its determination, the board shall consider whether the proposed Special Eexception, V**ariance">V**ariance or use would be hazardous, harmful, noxious, offensive, or a nuisance to the surrounding neighborhood by reason of physical, social or economic effects; and may impose such requirements and conditions with respect to location, construction, maintenance and operation, in addition to any which may be stipulated in this Ordinance, as the board may deem necessary for the protection of adjacent properties and the public interest and welfare.
- (3) Performance standards: In order to reach a fair and objective decision, the board may utilize and give recognition to appropriate performance standards which are available in model codes or Ordinances, or which have been developed by planning, manufacturing, health, architectural and engineering research organizations.
- (4) Enforcement of decision: In exercising the above-mentioned powers, such board may, in conformity with the provisions of this Ordinance, reverse or affirm, wholly or partly, or may modify the order, requirements, decision or determination appealed from, and may make

such order, requirement, decision or determination as ought to be made, and to that end shall have all the powers of the officer from whom the appeal is taken; and may issue or direct the issue of a permit provided that no such action shall have the effect of permitting in any Delistrict a use prohibited in that Delistrict; of rezoning; of allowing the division of a parcel to create additional parcels which are not in conformity with the zoning district regulations in which it is located; or of permitting, without the approval of the county zoning agency, any Bevilding within the base setback area as established by Section 3.09(1) of this Ordinance, or of granting exception to the state plumbing code, or other state, county or local Ordinances.

- (5) Required vote: The concurring vote of three (3) members of the board shall be necessary to reverse any order, requirement, decision or determination of any such administrative official, or to decide in favor of the Amplicant on any matter upon which it is required to pass under this Ordinance, or to effect any variation therefrom. The ground of every such determination shall be stated.
- (6) Further appeal: Any person or persons, jointly or severally, aggrieved by any decision of the Bboard of Aadjustment, or any taxpayer, or any officer, department, board or bureau of the municipality, may appeal from a decision of the Bboard of Aadjustment within thirty (30) days after the filing of the decision in the office of the Bboard of Aadjustment in the manner provided in Sections 59.692(4)(b), 59.693(4)(b), 59.694(4) and 59.694(10) of the Wisconsin Statutes.

(Sections 19.03(1)(A), (4) and (6) were amended by Enrolled Ordinance 159-69, effective 1-17-05.)

19.04 Appeals.

- (1) How filed: Appeals to the Bboard of Aadjustment may be taken by any person aggrieved or by any officer, department, board or bureau of the municipality affected by any such decision of the zoning administrator or other Aadministrative Qefficer. Such appeal shall be taken within twenty (20) days from the date of the decision of the zoning administrator or other Aadministrative Qefficer appealed from by filing with the officer from whom the appeal is taken, and with the Bboard of Aadjustment, a notice of appeal specifying the grounds thereof, together with the proper fee as established under Section 22.01(4) of this Ordinance. The officer from whom the appeal is taken shall forthwith transmit to the board all the papers constituting the record upon which the action appealed from was taken.
- (2) Stay: An appeal shall stay all legal proceedings in furtherance of the action appealed from, unless the officer from whose decision the appeal is taken certifies to the Bboard of Aadjustment, after the notice of appeal shall have been filed with him, that by reason of facts stated in the certificate, a stay would, in his opinion, cause imminent peril to life or property. In such cases, proceedings shall not be stayed otherwise than by a restraining order, which may be granted by the Bboard of Aadjustment or by a court of record on application, on notice to the officer from whom the appeal is taken, and on due cause shown.
- 3) Hearing: Each appeal shall be heard within a reasonable time and not to exceed ninety (90) days from the time the appeal was filed with the Board. Notice of hearing shall be given by publishing in a newspaper of general circulation in the vicinity of the appeal at least once each week for two (2) consecutive weeks and not less than seven (7) days from the date of hearing. In addition, written notice shall be given to the county zoning administrator, any other Aadministrative Oefficer appealed from, and by first class mail to the petitioner, the

clerk of the town wherein the affected lands are located, the owners of each parcel of land within one hundred (100) feet of the land in question, and any other specifically interested parties. At the hearing, any party may appear in person, or by agent or by attorney.

(4) <u>Decision</u>: The decision on any appeal shall be made within fifteen (15) days after completion of the hearing thereon.

(Section 19.04(3) was amended by Enrolled Ordinance 162-48, effective 10-9-07.)

19.05 Special Eexceptions.

Requests for Sepecial Eexceptions upon which the Beoard of Aedjustment is required to pass by the terms of this Ordinance shall be presented by petition and a public hearing held thereon as provided for appeals.

SECTION 20 CHANGES AND AMENDMENTS

20.01 Authority.

Pursuant to the provisions of Section 59.69 of the Wisconsin Statutes the county board may amend the regulations of this Ordinance or change the Deistrict boundaries.

(Section 20.01 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

20.02 Procedure.

- (1) Petition: A petition for amendment of this Ordinance may be made by any property owner in the area to be affected by the amendment, by the town board of any town wherein the Ordinance is in effect, by any member of the county board, or by the county zoning agency.
- (2) Filing of petition: Such petition shall be submitted in triplicate directly to the zoning administrator in order that notice of hearings and other processing may be initiated without unnecessary delay. The zoning administrator shall immediately file the original of said petition with the county clerk, who shall present it to the county board at its next meeting for formal referral to the zoning agency for report and recommendation as required by Section 59.69(5) of the Wisconsin Statutes.
- (3) <u>Fee</u>: A petition submitted by other than a governmental body or agency shall be accompanied by the proper fee as established under Section 22.01(4) of this Ordinance and payable to the Waukesha County Park and Planning Commission.
- (4) <u>Data required</u>: In addition to all information required on the petition form, the petitioner shall supply the following:
 - (A) A plot map in triplicate accurately drawn to a scale of not less than <u>one hundred</u> (100) feet to the inch showing the land in question, its location, the length and direction of each boundary thereof, the location and existing use of all <u>B</u>+uildings on such land, and the <u>P</u>+rincipal <u>U</u>+se of all properties within three hundred (300) feet of such land.
 - (B) The names and complete mailing addresses, including zip codes, of the owners of

176

Effective 05-xx-2016

- all properties within three hundred (300) feet of any part of the land included in the proposed change.
- (C) Any further information which may be required by the zoning administrator to facilitate the making of a comprehensive report to the county board, including a detailed description of the intended new use.
- (5) <u>Hearing</u>: As soon as practical after receipt of each petition, the zoning agency shall call a public hearing thereon. Notice of the time and place of such hearing shall be given in the manner prescribed under Section 21 of this Ordinance.
- (6) Zoning agency action and report: As soon as possible after such public hearing, the county zoning agency shall act on such petition either approving, modifying and approving, or disapproving of the same. If its action is favorable to granting the requested change, or any modification thereof, it shall cause an Ordinance to be drafted effectuating its determination and shall submit such proposed Ordinance directly to the county board with its recommendations. If the county zoning agency, after its public hearing, shall recommend denial of the petition, it shall report its recommendation directly to the county board with its reasons for such action. Proof of publication of the notice of the public hearing held by the county zoning agency and proof of the giving of notice to the town clerk of such hearing shall be attached to either such report.
- (7) County board action: Upon receipt of the report of the county zoning agency, the county board may adopt the Ordinance as drafted by such zoning agency or with amendments, or it may refuse to deny the petition for amendment as recommended by the county zoning agency, in which case it shall re-refer the petition to the county zoning agency, with direction to draft an Ordinance to effectuate the petition, and report the same back to the county board, which may then adopt or reject such Ordinance, or it may re-refer the petition to the county zoning agency for reconsideration including possible further public hearing.
- (8) Protest: In case a protest against a proposed amendment is filed with the county clerk at least twenty-four (24) hours prior to the date of the meeting of the county board at which the report of the county zoning agency is to be considered, duly signed and acknowledged by the owners of fifty (50) percent (50) or more of the area proposed to be altered, or by the owners of at least fifty (50) percent (50%) of the frontage immediately in the rear or along the side boundaries thereof within three hundred (300) feet of the area proposed to be changed, or by the owners of at least fifty (50) percent (50%) of the frontage directly opposite and across a public street, Hhighway or alley from the area proposed to be altered, action on such Ordinance may be deferred until the county zoning agency shall have had a reasonable opportunity to ascertain and report to the county board as to the authenticity of such ownership statements. Each signer of such protest shall state the amount of area or frontage owned by him, and shall include a description of the lands owned by him. If such statements are found to be true, such Ordinance shall not be adopted except by the affirmative vote of three-fourths (3/4) of the members of the county board present and voting. If such statements are found to be untrue to the extent that the required frontage or area ownership is not present, such protest may be disregarded.

(9) <u>Effectuation</u>.

(A) If a town affected by the proposed amendment disapproves of the proposed amendment, the town board of such town may file a certified copy of the resolution adopted by such Board disapproving of the petition with the county zoning agency prior to, at or within ten (10) days after the public hearing. If the town board of the town affected in the case of an Ordinance relating to the location of boundaries of Delistricts files such a resolution, or the town boards of a majority of the towns affected in the case of all other amendatory Ordinances file such resolutions, the county zoning agency may not recommend approval of the petition without a change but may only recommend approval with change or recommend disapproval.

If any proposed Ordinance amendment makes only the change sought in the petition, and if the petition is not disapproved at or within ten (10) days after the public hearing by the town board of the town affected in the case of an Ordinance relating to the location of district boundaries or by the town boards of a majority of the towns affected in the case of all other amendatory Ordinances, it shall become effective upon passage by the county board. The county clerk shall record in his office the date on which such Ordinance becomes effective and he shall notify the town clerk of all towns affected by such Ordinance of such effective date, and also insert such effective date in the proceedings of the county board. Any other such amendatory Ordinance which would be a change from the change sought in the petition, when so adopted by the county board, shall within seven (7) days thereafter be submitted in duplicate by the county clerk, by registered mail, to the town clerk of each town in which lands affected by such Ordinance are located. If, after forty (40) days from the date of such adoption, a majority of such towns have not filed certified copies of resolutions approving such amendment with the county clerk or, if within a shorter time, a majority of the towns in which the Ordinance is in effect have filed certified copies of resolutions approving the amendment with the county clerk, the amendment shall thereupon be in effect in all the towns affected by the Ordinance. Any such Ordinance relating to the location of boundaries of Delistricts shall, within seven (7) days after adoption by the county board, be transmitted by the county clerk by registered mail only to the town clerk of the town in which the lands affected by such change are located and shall become effective forty (40) days after adoption of the Ordinance by the county board unless such town board prior to such date files a certified copy of a resolution disapproving of such Ordinance with the county clerk. If such town board approves the Ordinance prior to the forty (40)-day limit, said Ordinance shall become effective upon the filing of the resolution of the town board approving same with the county clerk. The county clerk shall record in his office the date on which such Ordinance becomes effective, and he shall notify the town clerk of all towns affected by such Ordinance of such effective date, and also make such report to the county board, which report shall be printed in the proceedings of the county board.

(Section 20.02(2) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

20.03 Zoning county-owned lands.

The county board may, by Ordinance, zone and rezone any lands owned by the county without necessity of securing the approval of the town boards of the towns wherein such lands are situated, and without following the procedure outlined in Section 59.69(5) of the Wisconsin Statutes, provided that the county board shall give written notice to the town board of the town wherein such lands are situated of its intent to so rezone and shall hold a public hearing on the proposed rezoning Ordinance and give notice of such hearing by posting in five (5) public places in the town.

(Section 20.03 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

20.04 Zoning in annexed areas.

- (1) Removal from map: When any lands previously under the jurisdiction of a county zoning Ordinance shall have been finally removed from such jurisdiction by reason of annexation to an incorporated municipality, and after the regulations imposed by the county zoning Ordinance have ceased to be effective as provided in Section 59.69(7) of the Wisconsin Statutes, the county board may, on the recommendation of its zoning agency, adopt such amendatory Ordinances and shall remove or delete such annexed lands from the official zoning map or written descriptions without following any of the procedures provided in Section 59.69 (5)(a) to (e). Wisconsin Statutes, and such amendatory Ordinances shall become effective upon passage and publication. A copy of such Ordinance shall be forwarded by the county clerk to the clerk of each town in which the lands affected were previously located. Nothing in this paragraph shall be construed to nullify or supersede the provisions of Section 80.64 of the Wisconsin Statutes.
- (2) Continued effect of Ordinance: Whenever any area which has been subject to a county zoning Ordinance petitions to become a part of a village or city, the regulations imposed by such county zoning Ordinance shall continue in effect, without change, and shall be enforced by such village or city until such regulations have been changed by official action of the governing body of such village or city, except that in the event an Ordinance of annexation is contested in the courts, the county zoning shall prevail and the county shall have jurisdiction over the zoning in the area affected until ultimate determination of the court action.

(Section 20.04 (1) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

SECTION 21 PUBLIC HEARINGS

21.01 Notice.

In order that the owners of property involved and other legitimately interested parties may have fair opportunity to be heard, adequate notice shall be given of any public hearing required by the provision of this Ordinance stating the time and place of such hearing and the purpose for which the hearing is being held.

21.02 Procedure.

- (1) Posting and publishing:
 - (A) Except as may be otherwise herein specifically provided, notice of public hearing shall be given by publication once a week for two (2) consecutive weeks in the official newspaper of the county, or in the newspaper of general circulation in the area of the proposed change or conditional use.
 - (B) When the hearing involves a proposed change in the zoning district classification of any property, or the granting of a conditional use, notice of the public hearing shall be given by first class mail to the owners of all lands within three hundred (300) feet of any part of the land included in such proposed change or conditional use at least seven (7) days before such public hearing. The failure of such notice to reach any property owner provided such failure be not intentional, shall not invalidate any

179

amending Ordinance or grant of conditional use.

- (C) When the hearing involves an amendment to the zoning Ordinance, a copy of such notice shall be sent without delay by first class mail to the town clerk of each town which would be affected by the amendment, and in no case less than seven (7) days prior to the date of such hearing. The town clerk shall in turn notify the plan commission without delay.
- (2) <u>Joint hearing</u>: When the hearing involves a proposed change in the zoning district classification of any property, the hearing shall be held jointly by the County Zoning Agency, or its designee, and the Plan Commission of any town or towns affected by such change. Within thirty (30) days after the hearing, the Plan Commission shall transmit its recommendation on the proposed change to the County Zoning Administrator. Approval by the Town Board in such zoning amendments is not required and disapproval by such Town Board is advisory only.

(Sections 21.02(1)(B) and (C) were amended by Enrolled Ordinance 162-48, effective 10-09-07.)

SECTION 22 GENERAL ADMINISTRATION

22.01 Zoning agency

- Park and planning commission designated: The Waukesha County Park and Planning Commission is hereby designated as the zoning agency pursuant to Section 59.69(2)(a) of the Wisconsin Statutes.
- (2) Responsibilities: The county zoning agency shall oversee the administration of this Ordinance, hold the necessary public hearings, and make recommendations to the county board relative to all zoning matters. The county zoning agency shall keep minutes of its proceedings and shall keep records of its examinations and other official actions, all of which shall be public record.
- (3) Approvals required: Where, in the interest of preserving the maximum degree of local administration, the determination of the town plan commission or town board is required by the provisions of this Ordinance for conditional uses and other special approvals, such determination shall be subject in all cases to final approval by the County Zoning Agency before it shall be effective. It shall be the responsibility of the local determining body to notify the Ceounty Zeoning Agency of any petitions or requests in such cases, and of any hearings to be held, and to transmit the final determination to the County Zoning Agency within ten (10) days in order that they may act promptly upon its ratification.
- (4) Appeal: Any person or persons, jointly or severally, aggrieved by any decision of the zoning agency, or any taxpayer, or any officer, department, board or bureau of the municipality, may appeal from a decision of the zoning agency within thirty (30) days after the filing of the decision in the office of the zoning agency by seeking the remedy available by certiorari. No appeal shall be taken from a decision of the zoning agency to the Board of Aadjustment.

(Sections 22.01(1) and (4) were amended by Enrolled Ordinance 159-69, effective 1-17-05.)

180

22.02 Zoning administrator.

Effective 05-xx-2016

Commented [BA68]: Added language to match shoreland ordinance.

- (1) <u>Designation</u>: The Director of the Waukesha County Parks and Land Use Department is designated as "zoning administrator" for the administration and enforcement of the provisions of this Ordinance and the zoning administrator has the authority to designate staff under his or her direction to perform delegated tasks and duties.
- (2) <u>Duties</u>: In the administration and enforcement of this Ordinance, the zoning administrator shall perform the following duties:
 - (A) Issue the necessary zoning and occupancy and use permits, provided the provisions of this Ordinance and of any applicable building code have been complied with, and make or cause to be made the necessary inspections.
 - (B) Keep an accurate record of all zoning and occupancy and use permits issued.
 - (C) Keep accurate records and maps of the zoning Ordinance and any amendments or changes thereto.
- (3) <u>Authority</u>: In the enforcement of this Ordinance, the zoning administrator shall have the power and authority for the following:
 - (A) At any reasonable time, and for any proper purpose, to enter upon any public or private premises and make inspection thereof.
 - (B) Upon reasonable cause or question as to proper compliance, to revoke any zoning or occupancy and use permit and issue cease and desist orders requiring the cessation of any building, moving, alteration or use which is in violation of the provisions of this Ordinance, such revocation to be in effect until reinstated by the zoning administrator or the zoning board of adjustment.
 - (C) To refer to the Office of Corporation Counsel for commencement of any legal proceedings necessary to enforce the provisions of this Oerdinance. The collection of forfeitures provided for herein shall occur through the established procedures of the Waukesha County Clerk of Courts and Waukesha County Department of Administration, Collection Division. The issuance of citations provided for under this Oerdinance shall not require such referral and may be issued by the Zoning Administrator directly.
- (4) Deputies: To expedite local administration of this Ordinance, the zoning agency may designate the town building inspector as a deputy to the county zoning administrator for the purpose of field inspection and verification of the conditions shown on the application for zoning and occupancy and use permits. The deputy shall be authorized to accept application for zoning and occupancy and use permits, and shall promptly make any necessary inspection to verify the correctness of the application and transmit the application to the county zoning agency. The deputy shall also make the necessary inspections as provided in Section 3.03(3)(B) of this Ordinance before an occupancy and use permit shall be issued.
- (5) Fee schedule: The fees referred to in other Sections of this Ordinance shall be established by the annual Waukesha County budget adopted by the Waukesha County Board and may from time to time be modified. The processing fees are related to costs involved in handling zoning permit applications, Site Plan and Plan of Operation review, conditional use petitions, appeals to the Beoard of Aedjustment, and zoning amendments.

Effective 05-xx-2016

181

22.03 Violations.

- (1) Penalties: Any person, firm, company, or corporation who violates, disobeys, omits, neglects, refuses to comply with, or who resists the enforcement of any of the provisions of this Ordinance, shall be subject to a fine of not less than ten dollars (\$10.00) and not to exceed the sum of two hundred dollars (\$200.00) for each offense, together with the costs of the action, and in default of the payment thereof, shall be imprisoned in the County Jail of Waukesha County, for a period of not to exceed six (6) months or until such fine and the subsequent costs have been paid. Each day that a violation is permitted to exist shall constitute a separate violation and be punishable as such.
- (2) Enforcement by injunction: Compliance with the provisions of this Ordinance may also be enforced by injunctional order at the suit of the county or one (1) or more owners of real estate situated within an area affected by the regulations of this Ordinance. It shall not be necessary to prosecute for fine or imprisonment before resorting to injunctional proceedings.
- (3) <u>Declared nuisances</u>: Any <u>B</u>-building erected, structurally altered, or placed on a <u>L</u>-lot, or any use carried on in violation of the provisions of this Ordinance is hereby declared to be a nuisance *per se*, and the county may apply to any court of competent jurisdiction to restrain or abate such nuisance.
- (4) Enforcement by Citation: The County elects to use the citation method of enforcement under Section 66.0113 of the Wisconsin Statutes for violations of this Code of Ordinances, including those for which a statutory counterpart exists.
 - (A) In addition to all law enforcement officers, the issuance of citations is expressly limited to the zoning administrator. The authority delegated to such official or employees to issue citations may only be granted or revoked by the County Board.
 - (B) The citation shall contain the following information:
 - 1. The name and address of the alleged violator.
 - 2. The factual allegations describing the alleged violation.
 - 3. The time and place of the offense.
 - 4. The Section of the $\underline{O}\Theta$ rdinance violated.
 - A designation of the offense in such a manner as can be reasonably understood by a person making a reasonable effort to do so.
 - 6. The time at which the alleged violator may appear in court.
 - 7. A statement which, in essence, informs the alleged violator:
 - a. That a cash deposit based on the schedule established by the County Board, from time to time, and on file in the office of the County Clerk, be made to and deposited with the Clerk of the Waukesha County Circuit Court or the Sheriff's Department prior to the time of the scheduled court appearance.

- That if a deposit is made, no appearance in court is necessary unless he is subsequently summoned or the citation requests a court appearance.
- c. That if a cash deposit is made and the alleged violator does not appear in court, he will be deemed to have entered a plea of no contest and submitted to a forfeiture, a penalty assessment, a jail assessment crime lab assessment and drug/law enforcement assessment and any applicable domestic abuse or consumer information assessments of, if the court does not accept the plea of no contest, a summons will be issued commanding him or her to appear in court to answer the complaint.
- d. That if no cash deposit is made and the alleged violator does not appear in court at the time specified, the court may issue a summons or a warrant for the defendant's arrest or consider the nonappearance to be a plea of no contest and enter judgment or an action may be commenced to collect the forfeiture, penalty assessment, jail assessment, crime lab assessment and drug/law enforcement assessment and any applicable domestic abuse or consumer information assessments.
- e. That if the court finds that the violation involves an ordinance that prohibits conduct that is the same as or similar to conduct prohibited by state statute punishable by fine or imprisonment or both, and that the violation resulted in damage to the property of or physical injury to a person other than the alleged violator, the court may summon the alleged violator into court to determine if restitution shall be ordered.
- 8. A direction that if the alleged violator elects to make a cash deposit, the statement which accompanies the citation shall be signed to indicate that the statement required under subparagraph 7. above has been read. Such statement shall be sent or brought with the cash deposit.
- 9. Such other information as the County deems necessary.
- (C). The schedule of cash deposits including penalty assessment, jail assessment, crime lab assessment and drug/law enforcement assessment and any applicable domestic abuse or consumer information assessments for use with citations issued under this Section shall be as adopted by the County Board from time to time and such schedule shall be on file in the Offices of the Sheriff, Zoning Administrator, County Clerk and Clerk of Court and receipts shall be given for cash deposits.
- (D). The procedures contained in Section 66.0113(3) of the Wisconsin Statutes, relating to the options of an alleged violator and default are adopted and incorporated herein by reference.
- (E). This Section does not preclude the County or any authorized officer from proceeding under any other ordinance or law or by any other enforcement method to enforce any ordinance regulation or order.

(Section 22.03(4) was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

SECTION 23 VALIDITY

23.01 Repeal of conflicting Ordinances.

All other Ordinances or parts of Ordinances in conflict with the provisions of this Ordinance are hereby repealed.

23.02 Declaration of severability.

The several Sections, subsections and paragraphs of this Ordinance are hereby declared to be severable. If any Section, subsection, or paragraph or subparagraph of this Ordinance shall be declared by a decision of a court of competent jurisdiction to be invalid, such decision shall not affect the validity of the other provisions of the Ordinance, or of the Section of which the invalid portion or paragraph may be a part.

23.03 Effective date.

Following passage and publication by the county board, this Ordinance shall be in full force and effect in each town upon filing with the county clerk a certified copy of a resolution by the town board approving said Ordinance pursuant to Section 59.69(5)(c) of the Wisconsin Statutes and attached to a copy of the Ordinance as submitted to the town board.

(Section 23.03 was amended by Enrolled Ordinance 159-69, effective 1-17-05.)

23.04 Adoption.

Passed and approved by the Board of Supervisors of Waukesha County, Wisconsin, this 26th day of February, 1959.

23.05 Official Revisor and Editor

The Corporation Counsel shall be the official revisor and editor of this Code and the Corporation Counsel, or his or her designee, is authorized to revise this Code in accordance with any enrolled ordinance. The Corporation Counsel is hereby authorized to make changes to the numbering sequence, lettering, organization, formatting, or capitalization of words of an enrolled ordinances or these Code Sections, as needed to create a consecutive sequence, an orderly format, and to be consistent with other code Sections.

(Section 23.05 was created by Enrolled Ordinance 159-69, effective 1-17-05.)

Editor's Note regarding comprehensive text amendments:

The Waukesha County Basic Zoning Ordinance was originally adopted on June 7, 1946 and was revised February 26, 1959. The ordinance has been subsequently amended, the most recent comprehensive text amendments being Enrolled Ordinance 159-69, effective January 17, 2005, Enrolled Ordinance 160-03, effective May 13, 2005, and Enrolled Ordinance 161-13, effective September 4, 2006.

Prior to July 23, 2015, this ordinance was effective in the Towns of Genesee, Oconomowoc, Ottawa and Vernon. Through Enrolled Ordinance 170-25, effective July 23, 2015, this ordinance is no longer effective in the Town of Genesee.